



GNOME User Guide

SUSE Linux Enterprise Server 12 SP5



GNOME User Guide

SUSE Linux Enterprise Server 12 SP5

Introduces the GNOME desktop of SUSE Linux Enterprise Server. It guides you through using and configuring the desktop and helps you perform key tasks. It is intended mainly for end users who want to make efficient use of GNOME as their default desktop.

Publication Date: November 04, 2019

SUSE LLC

10 Canal Park Drive

Suite 200

Cambridge MA 02141

USA

<https://www.suse.com/documentation> 

Copyright © 2006– 2019 SUSE LLC and contributors. All rights reserved.

Permission is granted to copy, distribute and/or modify this document under the terms of the GNU Free Documentation License, Version 1.2 or (at your option) version 1.3; with the Invariant Section being this copyright notice and license. A copy of the license version 1.2 is included in the section entitled “GNU Free Documentation License”.

For SUSE trademarks, see <http://www.suse.com/company/legal/> . All other third-party trademarks are the property of their respective owners. Trademark symbols (®, ™ etc.) denote trademarks of SUSE and its affiliates. Asterisks (*) denote third-party trademarks.

All information found in this book has been compiled with utmost attention to detail. However, this does not guarantee complete accuracy. Neither SUSE LLC, its affiliates, the authors nor the translators shall be held liable for possible errors or the consequences thereof.

Contents

About This Guide **xii**

I INTRODUCTION **1**

1 Getting Started with the GNOME Desktop 2

1.1 Logging In **2**

Switching the Session Type Before Logging In **3** • Assistive Tools **5**

1.2 Desktop Basics **5**

Activities Overview **7** • Starting Programs **8**

1.3 Pausing or Finishing Your Session **9**

Locking the Screen **9** • Logging Out or Switching Users **10** • Restarting or Shutting Down the Computer **10** • Suspending the Computer **10**

2 Working with Your Desktop 11

2.1 Managing Files and Directories **11**

Key Combinations **12** • Compressing Files or Directories **13** • Burning a CD/DVD **14** • Creating a Bookmark **15** • Accessing Remote Files **15**

2.2 Accessing Removable Media **16**

2.3 Searching for Files **16**

2.4 Copying Text Between Applications **17**

2.5 Managing Internet Connections **17**

2.6 Exploring the Internet **17**

2.7 E-mail and Scheduling **18**

2.8 Opening or Creating Documents with LibreOffice **19**

2.9 Controlling Your Desktop's Power Management **19**

- 2.10 Creating, Displaying, and Decompressing Archives 19
 - Opening an Archive 20 • Extracting Files from an Archive 21 • Creating Archives 22
- 2.11 Taking Screenshots 23
- 2.12 Viewing PDF Files 23
- 2.13 Obtaining Software Updates 24
- 2.14 For More Information 25

3 Customizing Your Settings 26

- 3.1 The GNOME Settings Dialog 26
- 3.2 Personal 27
 - Changing the Desktop Background 28 • Configuring Language Settings 28
- 3.3 Hardware 29
 - Configuring Bluetooth Settings 29 • Configuring Power Settings 30 • Modifying Keyboard Shortcuts 31 • Configuring the Mouse and Touchpad 32 • Installing and Configuring Printers 33 • Configuring Screens 33 • Configuring Sound Settings 35 • Networking 36
- 3.4 System 36
 - Changing Your Password 36 • Setting Preferred Applications 37 • Setting Session Sharing Preferences 38 • Configuring Administrative Settings with YaST 38

4 Assistive Technologies 39

- 4.1 Enabling Assistive Technologies 39
- 4.2 Visual Impairments 39
- 4.3 Hearing Impairments 40
- 4.4 Mobility Impairments 40
- 4.5 For More Information 41

II	CONNECTIVITY, FILES AND RESOURCES	42
5	Accessing Network Resources	43
5.1	Connecting to a Network	43
5.2	General Notes on File Sharing and Network Browsing	44
5.3	Accessing Network Shares	45
5.4	Sharing Directories	46
	Enabling Sharing on the Computer	46 • Enabling Sharing for a Directory 46
5.5	Managing Windows Files	48
5.6	Configuring and Accessing a Windows Network Printer	49
6	Managing Printers	50
6.1	Installing a Printer	50
7	Backing Up User Data	51
7.1	Creating Backups	51
7.2	Restoring Data	52
8	Passwords and Keys: Signing and Encrypting Data	53
8.1	Signing and Encryption	53
8.2	Generating a New Key Pair	54
	Creating OpenPGP Keys	54 • Creating Secure Shell Keys 55
8.3	Modifying Key Properties	56
	Editing OpenPGP Key Properties	56 • Editing Secure Shell Key Properties 60
8.4	Importing Keys	61
8.5	Exporting Keys	62
8.6	Signing a Key	62

8.7 Password Keyrings 63

8.8 Key Servers 64

8.9 Key Sharing 65

9 gFTP: Transferring Data from the Internet 66

9.1 ASCII Compared to Binary Transfers 66

9.2 Connecting to a Remote Server 67

9.3 Transferring Files 67

9.4 Setting Up an HTTP Proxy Server 68

9.5 For More Information 69

III LIBREOFFICE 70

10 LibreOffice: The Office Suite 71

10.1 LibreOffice Modules 71

10.2 Starting LibreOffice 72

10.3 The LibreOffice User Interface 73

10.4 Compatibility with Other Office Applications 74

Opening Documents from Other Office Suites 74 • Converting Documents to the OpenDocument Format 74 • Sharing Files with Users of Other Office Suites 75

10.5 Saving Files with a Password 76

10.6 Customizing LibreOffice 76

10.7 Changing the Global Settings 79

10.8 Using Templates 81

10.9 Setting Metadata and Properties 82

10.10 For More Information 83

11 LibreOffice Writer 85

- 11.1 Creating a New Document 85
- 11.2 Formatting with Styles 86
 - The Side Bar Panel *Styles and Formatting* 88 • Applying a Style 89 • Changing a Style 90 • Creating a Style 90
- 11.3 Working with Large Documents 93
 - Navigating in Large Documents 93 • Using Master Documents 94
- 11.4 Using Writer as an HTML Editor 95

12 LibreOffice Calc 97

- 12.1 Creating a New Document 97
- 12.2 Using Formatting and Styles in Calc 98
- 12.3 Working With Sheets 98
- 12.4 Conditional Formatting 99
- 12.5 Grouping and Ungrouping Cells 101
- 12.6 Freezing Rows or Columns as Headers 101

13 LibreOffice Impress, Base, Draw, and Math 103

- 13.1 Using Presentations with Impress 103
 - Creating a Presentation 103 • Using Master Pages 105
- 13.2 Using Databases with Base 106
 - Creating a Database Using Predefined Options 106
- 13.3 Creating Graphics with Draw 110
- 13.4 Creating Mathematical Formulas with Math 111

IV INTERNET, COMMUNICATION AND COLLABORATION 113

14 Firefox: Browsing the Web 114

- 14.1 Starting Firefox 114

14.2	Navigating Web Sites	114
	The Location Bar	115 • Zooming 116 • Tabbed Browsing 116 • Using the Sidebar 117
14.3	Finding Information	117
	Finding Information on the Web	117 • Searching in the Current Page 119
14.4	Managing Bookmarks	119
	Organizing Bookmarks	120 • Tags 121 • Importing and Exporting Bookmarks 122 • Live Bookmarks 122 • Smart Bookmark Folders 122 • The Bookmarks Toolbar 123
14.5	Using the Download Manager	123
14.6	Security	124
	Instant Web Site ID	124 • Importing Certificates 125 • Password Management 126 • Private Browsing 126
14.7	Customizing Firefox	127
	Preferences	127 • Add-ons 129
14.8	Printing from Firefox	131
14.9	For More Information	131
15	Evolution: E-Mailing and Calendaring	132
15.1	Starting Evolution	132
15.2	Setup Assistant	132
	Restoring from a Backup File	132 • Defining Your Identity 133 • Receiving Mail 133 • Receiving Options 135 • Sending Mail 140 • Final Steps 141
15.3	Using Evolution	141
	The Menu Bar	142 • The Shortcut Bar 143 • Using E-Mail 144 • Calendaring 145 • Managing Contacts 145
15.4	For More Information	146
16	Empathy: Instant Messaging	147
16.1	Starting Empathy	147

16.2 Configuring Accounts 147

16.3 Managing Contacts 148

16.4 Chatting with Friends 149

16.5 For More Information 149

17 Ekiga: Using Voice over IP 150

17.1 Starting Ekiga 150

17.2 Configuring Ekiga 150

17.3 The Ekiga User Interface 151

17.4 Making a Call 153

17.5 Answering a Call 154

17.6 Using the Address Book 154

17.7 For More Information 155

V GRAPHICS AND MULTIMEDIA 156

18 GIMP: Manipulating Graphics 157

18.1 Graphics Formats 157

18.2 Starting GIMP 158

18.3 User Interface Overview 158

The Image Window 158 • The Toolbox 159 • Layers, Channels, Paths,
Undo 160

18.4 Getting Started 160

Creating a New Image 160 • Opening an Existing Image 161

18.5 Saving and Exporting Images 161

18.6 Editing Images 162

Changing the Size of an Image 162 • Selecting Parts of
Images 164 • Applying and Removing Color 166 • Adjusting Color

	Levels 169 • Undoing Mistakes 169 • Layers 170 • Image Modes 170 • Special Effects 171
18.7	Printing Images 171
18.8	For More Information 171
19	GNOME Videos 173
19.1	Using GNOME Videos 173
	Opening a Video or Audio File 174 • Opening a Video or Audio File By URI Location 174 • Playing a DVD, VCD, or CD 174 • Seeking Through Movies or Songs 175 • Changing the Zoom Factor 175 • Showing or Hiding Controls 176 • Managing Playlists 176 • Choosing Subtitles 176
19.2	Modifying GNOME Videos Preferences 177
	General Preferences 177 • Display Preferences 178 • Audio Preferences 179
20	Brasero: Burning CDs and DVDs 180
20.1	Creating a Data CD or DVD 180
20.2	Creating an Audio CD 181
20.3	Copying a CD or DVD 181
20.4	Writing ISO Images 182
20.5	Creating a Multisession CD or DVD 182
20.6	For More Information 182
A	Help and Documentation 183
A.1	Using GNOME Help 183
A.2	Additional Help Resources 185
A.3	For More Information 185
	The Linux Documentation Project 185 • Wikipedia: The Free Online Encyclopedia 186 • Standards and Specifications 186

B GNU Licenses 188

B.1 GNU Free Documentation License 188

About This Guide

This manual introduces you to the GNOME graphical desktop environment as implemented in SUSE® Linux Enterprise Server, and shows you how to configure it to meet your personal needs and preferences. It also introduces you to several programs and services. It is intended for users who have experience using a graphical desktop environment such as macOS*, Windows*, or other Linux desktops.

The manual is divided into the following parts:

Introduction

Get to know your GNOME desktop, learn how to cope with basic and daily tasks using the central GNOME applications and various small utilities. Get an overview of the possibilities that GNOME offers for modifying and individualizing the desktop according to your needs and wishes. Learn how to use assistive technologies to improve accessibility in case of vision or mobility impairment.

Connectivity, Files and Resources

Learn how to manage and exchange data on your system or on a network: connecting to a network and sharing files, managing printers, or creating backups of your data. This part also shows how to sign and encrypt your mails and documents and how to use file transfer clients to transfer data from or to the Internet.

LibreOffice

Introduces the LibreOffice suite, including Writer, Calc, Impress, Base, Draw, and Math.

Internet, Communication and Collaboration

Use a Web browser and get to know the e-mailing and calendaring software. Communicate with others using Instant Messaging or Voice over IP.

Graphics and Multimedia

Get to know GIMP, an image manipulation program that meets the needs of both amateurs and professionals. Get introduced to your desktop's applications for playing movies. Learn how to create data or audio CDs and DVDs for archiving your data.

1 Available Documentation



Note: Online Documentation and Latest Updates

Documentation for our products is available at <https://documentation.suse.com>, where you can also find the latest updates, and browse or download the documentation in various formats. The latest documentation updates are usually available in the English version of the documentation.

The following documentation is available for this product:

Article “Installation Quick Start”

Lists the system requirements and guides you step-by-step through the installation of SUSE Linux Enterprise Server from DVD, or from an ISO image.

Book “Deployment Guide”

Shows how to install single or multiple systems and how to exploit the product-inherent capabilities for a deployment infrastructure. Choose from various approaches, ranging from a local installation or a network installation server to a mass deployment using a remote-controlled, highly-customized, and automated installation technique.

Book “Administration Guide”

Covers system administration tasks like maintaining, monitoring and customizing an initially installed system.

Book “Virtualization Guide”

Describes virtualization technology in general, and introduces libvirt—the unified interface to virtualization—and detailed information on specific hypervisors.

Book “Storage Administration Guide”

Provides information about how to manage storage devices on a SUSE Linux Enterprise Server.

Book “AutoYaST”

AutoYaST is a system for unattended mass deployment of SUSE Linux Enterprise Server systems using an AutoYaST profile containing installation and configuration data. The manual guides you through the basic steps of auto-installation: preparation, installation, and configuration.

Book “Security Guide”

Introduces basic concepts of system security, covering both local and network security aspects. Shows how to use the product inherent security software like AppArmor or the auditing system that reliably collects information about any security-relevant events.

Book “Security and Hardening Guide”

Deals with the particulars of installing and setting up a secure SUSE Linux Enterprise Server, and additional post-installation processes required to further secure and harden that installation. Supports the administrator with security-related choices and decisions.

Book “System Analysis and Tuning Guide”

An administrator's guide for problem detection, resolution and optimization. Find how to inspect and optimize your system by means of monitoring tools and how to efficiently manage resources. Also contains an overview of common problems and solutions and of additional help and documentation resources.

Book “Subscription Management Tool for SLES 12 SP5”

An administrator's guide to Subscription Management Tool—a proxy system for SUSE Customer Center with repository and registration targets. Learn how to install and configure a local SMT server, mirror and manage repositories, manage client machines, and configure clients to use SMT.

GNOME User Guide

Introduces the GNOME desktop of SUSE Linux Enterprise Server. It guides you through using and configuring the desktop and helps you perform key tasks. It is intended mainly for end users who want to make efficient use of GNOME as their default desktop.

2 Giving Feedback

Your feedback and contribution to this documentation is welcome! Several channels are available:

Service Requests and Support

For services and support options available for your product, refer to <http://www.suse.com/support/>.

To open a service request, you need a subscription at SUSE Customer Center. Go to <https://scc.suse.com/support/requests>, log in, and click *Create New*.

Bug Reports

Report issues with the documentation at <https://bugzilla.suse.com/>. To simplify this process, you can use the *Report Documentation Bug* links next to headlines in the HTML version of this document. These preselect the right product and category in Bugzilla and add a link to the current section. You can start typing your bug report right away. A Bugzilla account is required.

Contributions





To contribute to this documentation, use the *Edit Source* links next to headlines in the HTML version of this document. They take you to the source code on GitHub, where you can open a pull request. A GitHub account is required.

Mail

Alternatively, you can report errors and send feedback concerning the documentation to doc-team@suse.com. Make sure to include the document title, the product version and the publication date of the documentation. Refer to the relevant section number and title (or include the URL) and provide a concise description of the problem.

3 Documentation Conventions

The following notices and typographical conventions are used in this documentation:

- /etc/passwd: directory names and file names
- PLACEHOLDER: replace PLACEHOLDER with the actual value
- PATH: the environment variable PATH
- ls, --help: commands, options, and parameters
- user: users or groups
- package name: name of a package
- , : a key to press or a key combination; keys are shown in uppercase as on a keyboard
- *File, File > Save As*: menu items, buttons
-  This paragraph is only relevant for the AMD64/Intel 64 architecture. The arrows mark the beginning and the end of the text block. 

System z, POWER This paragraph is only relevant for the IBM architectures Z and POWER. The arrows mark the beginning and the end of the text block. ◀

- *Dancing Penguins* (Chapter *Penguins*, ↑Another Manual): This is a reference to a chapter in another manual.
- Commands that must be run with root privileges. Often you can also prefix these commands with the sudo command to run them as non-privileged user.

```
root # command
tux > sudo command
```

- Commands that can be run by non-privileged users.

```
tux > command
```

- Notices



Warning: Warning Notice

Vital information you must be aware of before proceeding. Warns you about security issues, potential loss of data, damage to hardware, or physical hazards.



Important: Important Notice

Important information you should be aware of before proceeding.



Note: Note Notice

Additional information, for example about differences in software versions.



Tip: Tip Notice

Helpful information, like a guideline or a piece of practical advice.

I Introduction

- 1 Getting Started with the GNOME Desktop 2
- 2 Working with Your Desktop 11
- 3 Customizing Your Settings 26
- 4 Assistive Technologies 39

1 Getting Started with the GNOME Desktop

This section describes the conventions, layout, and common tasks of the GNOME desktop as implemented in your product.

GNOME is an easy-to-use graphical interface that can be customized to meet your needs and personal preferences. This section describes the default configuration of GNOME. If you or your system administrator modify the defaults, some aspects might be different, such as appearance or key combinations.



Note: Included Session Configurations

Some versions of SUSE Linux Enterprise ship with as many as three different session configurations based on GNOME. These are GNOME, GNOME Classic, and SLE Classic. The version described here is the default configuration of SUSE Linux Enterprise Desktop called SLE Classic.

1.1 Logging In

In general, all users must authenticate—unless *Auto Login* is enabled for a specific user. In this case, a particular user will be logged in automatically when the system starts. This can save some time, especially if a computer is used by a single person. It may impact account security. Auto Login can be enabled or disabled during installation or at any time using the YaST User and Group Management module. For more information, refer to *Book “Deployment Guide”, Chapter 16 “Managing Users with YaST”*.

If your computer is running in a network environment and you are not the only person using the machine, you are usually prompted to enter your user name and password when you start the system.




FIGURE 1.1: GNOME LOGIN SCREEN

PROCEDURE 1.1: NORMAL LOGIN

1. If your user name is listed, click it.
If your user name is not listed, click *Not listed?*. Then enter your user name and click *Next*.
2. Enter your password and click *Sign in*.

1.1.1 Switching the Session Type Before Logging In

If you want to try one of the additional GNOME session configurations or try another desktop environment, follow the steps below.

1. On the login screen, click your user name or enter it, as you normally would.
2. To change the session type, click the cog wheel icon. A menu appears.




FIGURE 1.2: GNOME LOGIN SCREEN—SESSION TYPE

3. From the menu, select one of the entries. Depending on your configuration there may be different choices, but the default selection is as follows.

GNOME

A GNOME 3 configuration that is very close to the upstream design. It focuses on interrupting users as little as possible. However, starting applications and switching between them works differently from many other desktop operating systems. It uses a single panel at the top of the screen.

GNOME Classic

A GNOME 3 configuration that is designed to appeal to former users of GNOME 2. The desktop has two panels, one at the top and another at the bottom.

IceWM

A very basic desktop designed to use little resources. It can be used as a fallback, if other options do not work or are slow.

SLE Classic (default)

The default desktop of SUSE Linux Enterprise, designed to appeal to users of older versions of SUSE Linux Enterprise and users of Microsoft* Windows*. This desktop is a GNOME 3 configuration and uses a single panel that is placed at the bottom of the screen.

4. Enter your password into the text box, then click *Sign In*.

After switching to another session type once, the chosen session will become your default session. To switch back, repeat the steps above.

1.1.2 Assistive Tools

In the top right corner, there are status icons and the assistive technologies menu. By clicking the status icons, open a menu that allows you to set the sound volume and restart or power off the machine.

1.2 Desktop Basics

The GNOME desktop appears after you first log in. It displays a panel at the bottom showing the following elements (from left to right):

Applications menu

Click *Applications* in the left corner to open a menu with all the installed programs. These are classified under different categories for a better overview. Sub-items open automatically when you place the mouse above them.

Click *Activities Overview* in the bottom part of the *Applications* menu to open Activities Overview where you can start programs and manage those already running.

The Activity Overview is described further in [Section 1.2.1, “Activities Overview”](#).

Places menu

Click *Places* to open a menu with shortcuts to your personal directories, connected storage media, and network resources.

Task switcher

All applications currently open on the desktop (on the active workspace) appear in the middle part of the panel. You can bring these applications to the foreground by clicking their names.

Notification indicator (*not always visible*)

When there are notifications, for example, for new chat or e-mail messages or concerning system updates, an indicator will appear. The indicator is a blue circle with the number of available notifications displayed in the middle. Click the indicator to open the Message Tray where you can interact with all the notifications.

Workspace switcher

This menu lets you select a workspace (also called a virtual desktop) to work on. This feature can help you work with many windows. For example, you could move windows needed for one project to workspace 1 and windows needed for another project to workspace 2.

Date and time

The current day of the week and time are shown to the right from the workspace switcher. Click it to open a menu where you can access a calendar and adjust date and time settings.

Status icons

In the right corner of the panel, icons showing the current status of the network connection, sound volume and power/battery status are displayed.

Click the icons to open a menu where you can adjust sound volume, display brightness, network connection, and power settings. Click the name to display the options for logging out or for switching to another user.

The three icons in the lower part of the menu allow you to, from left to right, open the GNOME settings dialog, lock the screen, and power off or restart your computer.



FIGURE 1.3: GNOME DESKTOP—SLE CLASSIC

1.2.1 Activities Overview

Activities Overview is a full screen mode that comprises all the ways in which you can switch from one activity to another. It shows previews of all open windows and icons for favorite and running applications. It also integrates searching and browsing functionality.

1.2.1.1 Opening the Activities Overview

There are multiple ways to open the Activities Overview:

- Open the *Applications* menu on the bottom panel and select *Activities Overview*.
- Press `Meta`.
- Forcefully move the pointer to the top left corner (the so-called *hot corner*).

1.2.1.2 Using the Activities Overview

In the following, the most important parts of the Activities Overview are explained.

Dash

The Dash is the bar positioned on the center left. It contains favorite applications and all applications with open windows. If you move the mouse pointer over one of the icons, GNOME will display the name of the corresponding application nearby. A light glow indicates that the application is running and has at least one open window.

Right-clicking an icon opens a menu which offers different actions depending on the associated program. Using *Add to Favorites*, you can place the application icon permanently in Dash. To remove a program icon from Dash, select *Remove from Favorites*. To rearrange an icon, use the mouse to drag it to a new position.

Search box

On the top, there is a search box that you can use to find applications, settings and files in your home directory.

To search, you do not need to click the search box. You can begin typing directly after opening Activity Overview. Search starts immediately, you do not need to press `Enter`.

Workspace selector

On the right, there is an overview of available workspaces. To switch to the selected desktop, click the preview of it.

To move a window from one workspace to another, drag a window preview from one workspace preview to another.

1.2.2 Starting Programs

To start a program, you have several options:

- In the bottom panel, click *Applications* and select the desired program from the hierarchical menu.
- Open the Activities Overview by pressing `Meta`. Now click an application icon or search for an application. If you do not know the exact application name, you can search for generic category names such as “image editor”.
Further information about the activities overview can be found in [Section 1.2.1, “Activities Overview”](#).
- If you know the exact command to start the program, you can press `Alt-F2`, enter the command into the dialog and press `Enter`.

Note that the only button displayed in the window is labeled *Close* and will indeed close the window.

1.3 Pausing or Finishing Your Session

When you have finished using the computer, there are multiple ways to finish the session. Which one is right in a given situation depends on how long you will be away and whether you are worried about energy consumption, among other things.

- **Locking the Computer.** Pause your session, but keep the computer on. Make sure that nobody can look at or change your work while you are away on a break. Other users can log in and work in the meantime. Other users can shut down the computer, but a prompt will warn them that you are still logged in.
- **Logging Out.** Finish the current session, but leave the computer on, so other users can log in.
- **Shutting Down.** Finish the current session and turn off the computer.
- **Restarting.** Finish the current session and restart the computer. Restarting is necessary to apply some system updates.
- **Suspending the Computer.** Pause your session and put the computer in a state where it consumes a minimal amount of energy. Suspend mode can be configured to lock your screen, so nobody can look at or change your work. Waking up the computer is generally much quicker than a full computer start.
This mode is also known as suspend-to-RAM, sleep or standby mode.

1.3.1 Locking the Screen

To lock the screen, click the status icons on the right of the main panel and click the padlock icon. When you lock your screen, at first a curtain with a clock will appear. After some time the screen turns black. To unlock the screen, move the mouse or press a key to display the locked screen dialog. Enter your password, then press to unlock the screen.

1.3.2 Logging Out or Switching Users

1. Click the status icons on the right of the main panel to open the menu.
2. Click your user name.
3. Select one of the following options:

Log Out

Logs you out of the current session and returns you to the Login screen.

Switch User

Suspends your session, allowing another user to log in and use the computer.

Account Settings

Takes you to the user settings where you can change your password.

1.3.3 Restarting or Shutting Down the Computer

1. Click the status icons on the right of the main panel to open the menu.
2. Click the power off icon in the lower right part of the menu.
3. Select one of the following options:

Power Off

Logs you out of the current session, then turns off the computer.

Restart

Logs you out of the current session, then restarts the computer.

1.3.4 Suspending the Computer

1. Click the status icons on the right of the main panel to open the menu.
2. Hold **Alt** pressed. The power off icon in the lower right part of the menu turns into a pause icon. Click the pause icon.

2 Working with Your Desktop

In this chapter you will learn how to work with files and burn CDs. You will also find out how to perform regular tasks with your desktop.

2.1 Managing Files and Directories

You can open GNOME Files in multiple ways:

- Click *Applications* > *Accessories* > *Files*.
- Open the Activities Overview and search for files.
- On the desktop, double-click *Home*.
- Open the *Places* menu and select any entry, such as *Home*.




FIGURE 2.1: FILE MANAGER

The elements of the GNOME Files window include the following:

Toolbar

The toolbar contains back and forward buttons, the path bar, a search function, elements to let you change the layout of the content area, and the application menu.

Menu

The menu is the last icon on the toolbar. It lets you perform many tasks, such as opening the preferences dialog, creating a new directory or opening a new window or tab.

Sidebar

The sidebar lets you navigate between often-used directories and external or network storage devices. To display or hide the sidebar, press **F9**.

Content Area

Displays files and directories.

Use the icons in the top right part of the window to switch between list and grid icon view.

Context Menus

Open a context menu by right-clicking inside the content area. The items in this menu depend on where you right-click.

For example, if you right-click a file or directory, you can select items related to the file or directory. If you right-click the background of a content area, you can select items related to the display of items in the content area.










Floating Statusbar










The floating statusbar appears when a file is selected. It displays the file name and size.

2.1.1 Key Combinations

The following table lists a selection of key combinations of GNOME Files.

TABLE 2.1: GNOME FILES KEY COMBINATIONS

Key Combination	Description
Alt +  / Alt + 	Go backward/go forward.
Alt + 	Open the parent directory.
 ,  ,  , 	Select an item.
Alt +  or Enter	Open an item.
Alt + Enter	Open an item's <i>Properties</i> dialog.
Shift + Alt + 	Open an item and close the current directory.

Key Combination	Description
	Transform the path bar from a button view to a text box. Exit this mode by pressing  (go to the location) or  (to remain in the current directory).
	Transform the path bar from a button view to a text box and replace the current path with <u>/</u> .
 Any number or letter key  	<p>Open your home directory.</p> <p>Start a search within the current directories and their subdirectories. The character you pressed is used as the first character of the search term. Search happens as you type, you do not need to press .</p> <p>Start a search within the current directories and their subdirectories. The character you pressed is used as the first character of the search term. Search happens as you type, you do not need to press .</p> <p>Moves the selected file or directory to the trash, from which it can be restored with <i>Undo</i>.</p>

2.1.2 Compressing Files or Directories

Sometimes, it is useful to archive or compress files, for example:

- You want to attach an entire directory, including its subdirectories, to an e-mail.
- You want to attach a large file to an e-mail.
- You want to save space on your hard disk and have files you rarely use.

In all these cases, you can create a compressed file, such as a ZIP file, which can contain multiple original files. How much smaller the compressed version is than the original depends on the file type. Many video, image and office document formats are already compressed and will only become marginally smaller.

1. In the GNOME Files content area, right-click the directory you want to archive, then click *Compress*.
2. Accept the default archive file name or provide a new one.
3. Select a file extension from the drop-down box.
 - .zip files are supported on most operating systems, including Windows*.
 - .tar.gz files are compatible with most Linux* and Unix* systems.
 - .7z files usually offer better compression ratios than other formats, but are not as widely supported.
4. Specify a location for the archive file, then click *Create*.

To extract an archived file, right-click the file, then select *Extract Here*. You can also double-click the compressed file to open it and see which files are included.

For more information on compressed files, see [Section 2.10, “Creating, Displaying, and Decompressing Archives”](#).

2.1.3 Burning a CD/DVD

If your system has a CD or DVD writer, you can use GNOME Files to burn CDs and DVDs. If you want to burn an audio CD or need more control over the result, see [Chapter 20, Brasero: Burning CDs and DVDs](#).

1. Open GNOME Files.
2. Insert a blank medium.
3. Find the files you want to add to the medium and drag them to the sidebar item called *Blank CD-R Disc*. (The label may read slightly differently, depending on the type of medium you inserted.) When your mouse pointer is over the sidebar item, a small + should appear next to the pointer.
4. When you have dragged all files onto the sidebar item *Blank CD-R Disc*, click it.
5. Provide a name next to *Disc Name* or keep the proposal.
6. Click *Write to Disc*.

7. In the appearing dialog *CD/DVD Creator*, make sure the right medium is selected. Then click *Burn*.
The files are burned to the disc. This can take a few minutes, depending on the amount of data being burned and the speed of your burner.
8. After the medium has been burned, it will be ejected from the drive. In the window *CD/DVD Creator*, you can click *Close*.

To burn an ISO disc image, first insert a medium, then double-click the ISO file in GNOME Files. In the dialog *Image Burning Setup*, click *Burn*.

2.1.4 Creating a Bookmark

Use the bookmarks feature in GNOME Files to quickly jump to your favorite directories from the sidebar.

1. Switch to the directory for which you want to create a bookmark in the content area.
2. Click the list icon, then select *Bookmark this Location* from the menu.
The bookmark now appears in the sidebar, with the directory name as the bookmark name.
3. *(Optional)* If you want, you can change the name of the bookmark. This does not affect the name of the bookmarked directory itself. To change the name, right-click the new sidebar item and select *Rename*.
4. *(Optional)* If you want, you can change the order in which the bookmarks are displayed. To reorder, click a bookmark and drag it to the desired location.

To switch to a bookmarked directory, click the appropriate sidebar item.

2.1.5 Accessing Remote Files

You can use GNOME Files to access files on remote servers. For more information, see [Chapter 5, Accessing Network Resources](#).

2.2 Accessing Removable Media

To access CDs/DVDs or flash disks, insert or attach the medium. An icon for the medium is automatically created on the desktop. For many types of removable media, a GNOME Files window pops up automatically. If GNOME Files does not open, double-click the icon for that drive on the desktop to view the contents. In GNOME Files, you will see an item for the medium in the sidebar.



Warning: Unmount to Prevent Data Loss

Do not physically remove flash disks immediately after using them. Even when the system does not indicate that data is being written, the drive may not be finished with a previous operation.

In the sidebar of GNOME Files, click the Eject icon next to the medium to safely remove or unmount the drive.

2.3 Searching for Files

There are multiple ways to search for files or directories. In all cases, the search will be performed on file and directory names. Searching by file size, modification date and other properties is only partially possible in the preinstalled graphical tools. Such searches are easier to do on the command line.

Using GNOME Files

In GNOME Files, navigate to the directory from which you want to start the search. Then start typing the search term. To search for objects with a certain modification date or file type, click the arrow-down icon of the search box and modify the properties.

Using the Activities Overview

Open the Activities Overview by pressing **Meta**. Then start typing the search term. The search will be performed within your home directory.

Using the Desktop Search application

Click *Applications > Accessories > Desktop Search*. Enter the search term in the text box *Search*. The search will be performed within your home directory.

2.4 Copying Text Between Applications

Copy and paste works the same as in other operating systems. First select the text, so that it appears highlighted, usually in blue. Then press `Ctrl-C`. Now move the keyboard focus to the right position. Finally, to insert the text, press `Ctrl-V`.

To copy or paste in the terminal, additionally press `Shift` together with the above key combinations.

An alternative way of using copy and paste is described in the following. First select the text. To paste the text, middle-click over the position where you want the text to be pasted. As soon as you make another selection, the text from the original selection will be replaced in the clipboard.

When copying information between programs, you must keep the source program open and paste the text before closing it. When a program closes, any content from that application that is on the clipboard is lost.

2.5 Managing Internet Connections

To surf the Web or send and receive e-mail messages, you must have configured an Internet connection. If you have installed SUSE Linux Enterprise Server on a laptop or a mobile device, NetworkManager is enabled by default. On the GNOME desktop, you can then establish Internet connections with NetworkManager as described in *Book "Administration Guide", Chapter 37 "Using NetworkManager", Section 37.3 "Configuring Network Connections"*.

Depending on your environment, you can choose in YaST which basic service to use for setting up network connections (either NetworkManager or wicked). For details, see *Book "Administration Guide", Chapter 16 "Basic Networking", Section 16.4.1.1 "Configuring Global Networking Options"*.

2.6 Exploring the Internet

The GNOME desktop includes Firefox, a Mozilla*-based Web browser. You can start it by clicking *Applications > Internet > Firefox*.


You can type an address into the location bar at the top or click links in a page to move to different pages, like in any other Web browser.

For more information, see [Chapter 14, Firefox: Browsing the Web](#).

2.7 E-mail and Scheduling

For reading and managing your mail and events, use Evolution. Evolution is a groupware program that makes it easy to store, organize and retrieve your personal information.

Evolution seamlessly combines e-mail, a calendar, an address book, and a memo and task list in one easy-to-use application. With its extensive support for communications and data interchange standards, Evolution can work with existing corporate networks and applications, including Microsoft* Exchange.



To start Evolution, click *Applications > Internet > Evolution*.

The first time you start Evolution, it prompts you with a few questions to set up a mail account and import mail from an old mail client. Then it shows you how many new messages you have and lists upcoming appointments and tasks. The calendar, address book and mail tools are available in the shortcut bar on the left.

For more information, see *Chapter 15, Evolution: E-Mailing and Calendaring*.

2.8 Opening or Creating Documents with LibreOffice

For creating and editing documents, LibreOffice is installed with the GNOME desktop. LibreOffice is a complete set of office tools that can both read and save Microsoft Office file formats. LibreOffice has a word processor, a spreadsheet, a database, a drawing tool and a presentation program.

To start LibreOffice, click *Applications > Office > LibreOffice*.

For more information, see *Chapter 10, LibreOffice: The Office Suite*.

2.9 Controlling Your Desktop's Power Management

To see the state of the computer battery on your laptop, check the battery icon in the right part of the panel. On certain events, such as a critically low battery state, GNOME will display notifications informing you about the event.

You can open the power settings via *Applications > System Tools > Settings > Power*.

For more information, see *Section 3.3.2, "Configuring Power Settings"*.

2.10 Creating, Displaying, and Decompressing Archives

You can use the Archive Manager application (also known as File Roller) to create, view, modify or unpack an archive. An archive is a file that acts as a container for other files. An archive can contain many files, directories and subdirectories, usually in compressed form. Archive Manager supports common formats such as zip, tar.gz, tar.bz2, lzh, and rar. You can use Archive Manager to create, open and extract a compressed non-archive file.

To start Archive Manager, click *Applications > Utilities > Archive Manager*.

If you already have a compressed file, double-click the file name in GNOME Files to view the contents of the archive in Archive Manager.




FIGURE 2.2: ARCHIVE MANAGER

2.10.1 Opening an Archive

1. In Archive Manager, click *Open*.
2. Select the archive you want to open.
3. Click *Open*.

Archive Manager displays the following:

- The archive name in the titlebar.
- The archive contents in the content area.

To open another archive, click *Open* again. Archive Manager opens each archive in a new window. To open another archive in the same window, you must first select *Close* from the menu in the right part of the window to close the current archive, then click *Open*.

If you try to open an archive that was created in a format that Archive Manager does not recognize, the application displays an error message.

4. To display the archive's properties, click the last icon in the titlebar and select *Properties*. Details like name, location, type, last modification, number of files, size, and compression ratio are shown.

2.10.2 Extracting Files from an Archive

1. In Archive Manager, select the files that you want to extract.
2. Click *Extract*.
3. Specify the directory where Archive Manager will extract the files.
4. Choose from the following extraction options:

Option	Description
All files	Extracts all files from the archive.
Selected files	Extracts the selected files from the archive.
Files	Extracts from the archive all files that match the specified pattern.
Keep directory structure	<p>Reconstructs the directory structure when extracting the specified files.</p> <p>For example, you specify <u>/tmp</u> in the <i>Filename</i> text box and extract all files. The archive contains a subdirectory called <u>doc</u>. If you select the <i>Keep directory structure</i> option, Archive Manager extracts the contents of the subdirectory to <u>/tmp/doc</u>.</p> <p>If you do not select the <i>Keep directory structure</i> option, Archive Manager does not create any subdirectories. Instead, it extracts all files from the archive, including files from subdirectories, to <u>/tmp</u>.</p>
Do not overwrite newer files	If not active, the Archive Manager overwrites any files in the destination directory that have the same name as the specified files.

Option	Description
	If you select this option, Archive Manager does not extract the specified file if an existing file with the same name already exists in the destination directory.

5. Click *Extract*.

To extract an archived file in a file manager window without opening Archive Manager, right-click the file and select *Extract Here*.

The Extract operation extracts a copy of the specified files from the archive. The extracted files have the same permissions and modification date as the original files that were added to the archive.

The Extract operation does not change the contents of the archive.

2.10.3 Creating Archives

1. In Archive Manager, click the main menu icon in the top left part of the window and select *New Archive*.

2. Specify the name and location of the new archive.

3. Select an archive type from the drop-down box.

4. Click *Create*.

Archive Manager creates an empty archive, but does not yet write the archive to disk. Archive Manager writes a new archive to disk only when the archive contains at least one file. If you create a new archive and quit Archive Manager before you add any files to the archive, the archive will be deleted.

5. Add files and directories to the new archive:

a. Click *Add Files* and select the files or directories you want to add.

b. Click *Add*.

Archive Manager adds the files to the current directory in the archive.

You can also add files to an archive in a file manager window without opening Archive Manager. See [Section 2.1.2, "Compressing Files or Directories"](#) for more information.

2.11 Taking Screenshots

You can take a snapshot of your screen or of an individual application window by using the Take Screenshots utility. Start it by pressing **Print** to take a screenshot of the entire desktop or by pressing **Alt-Print** to take a screenshot of the currently active window or dialog.

The screenshots are automatically saved to your ~/Pictures directory.

You can also use GIMP to take screenshots. (For more information on GIMP, see [Chapter 18, GIMP: Manipulating Graphics](#)). In GIMP, click *File > Create > Screenshot*, select an area, choose a delay and then click *Snap*.

2.12 Viewing PDF Files

Documents that need to be shared or printed across platforms can be saved as PDF (Portable Document Format) files. Document Viewer (also known as Evince) can open PDF files and many similar file types, such as XPS, DjVu, or TIFF.



Note: Rare Display Issues

In rare cases, documents will not be displayed correctly in Document Viewer. This can happen, for example, with certain forms, animations or 3D images. In such cases, ask the authors of the file what viewer they recommend. However, in some cases the recommended viewer will not work on Linux.




FIGURE 2.3: DOCUMENT VIEWER

To open Document Viewer, double-click a PDF file in a file manager window. Document Viewer will also open when you download a PDF file from a Web site. To open Document Viewer without a file, select *Applications > Office > Document Viewer*.

To view a PDF file in Document Viewer, click the cog wheel icon to open the menu and select *Open*. Now locate the desired PDF file and click *Open*.

Use the navigation icons at the top of the window or the thumbnails in the left panel to navigate through the document. If your PDF document provides bookmarks, you can access them in the left panel of the viewer.


2.13 Obtaining Software Updates

When you connect to the Internet, the updater applet automatically checks whether software updates for your system are available. When important updates are available, you will receive a notification on your desktop.

For detailed information on how to install software updates with the updater applet and how to configure it, refer to the chapter about installing and removing software in *Book “Deployment Guide”, Chapter 13 “Installing or Removing Software”, Section 13.5 “Keeping the System Up-to-date”*.

2.14 For More Information

Along with the applications described in this chapter for getting started, you can use many other applications on GNOME. Find detailed information about these applications in the other parts of this manual.

To learn more about GNOME and GNOME applications, see <http://www.gnome.org> .

To report bugs or add feature requests, go to <http://bugzilla.gnome.org> .

3 Customizing Your Settings

You can change the way the GNOME desktop looks and behaves to suit your own personal tastes and needs. Some possible changes of settings are:

- Keyboard and mouse configuration, as described in [Section 3.3.3, “Modifying Keyboard Shortcuts”](#) and [Section 3.3.4, “Configuring the Mouse and Touchpad”](#)
- Desktop background, as described in [Section 3.2.1, “Changing the Desktop Background”](#)
- Sounds, as described in [Section 3.3.7, “Configuring Sound Settings”](#)

These settings and others can be changed in the *All Settings* dialog.

3.1 The GNOME Settings Dialog

Whereas YaST is a desktop-independent system-wide tool to configure most aspects of your product installation, the settings dialog is a GNOME configuration tool. It focuses on look and feel, personal settings and preferences of your GNOME desktop.

To access the GNOME settings dialog, click *Applications > System Tools > Settings*. The dialog is divided into the following three categories:

Personal

From here, you can change the background of your desktop or of the lock screen, and configure language settings. For more information, see [Section 3.2, “Personal”](#).

Hardware

Allows you to configure hardware components such as monitors, printers, mice/touchpads, network adapters and sound devices. You can also change key combination settings and set up power-saving features. For more information, see [Section 3.3, “Hardware”](#).

System

Lets you configure system settings such as date and time, whether to start software when inserting flash disks or whether you want to share your screen with others. You can also set up user accounts. If you want, you can also start YaST from this screen, though it is also available separately from within the menu. For more information, see [Section 3.4, “System”](#).




FIGURE 3.1: GNOME SETTINGS DIALOG

To change some system-wide settings, the control center will prompt you for the `root` password and start YaST. This is mostly the case for administrator settings (including most of the hardware, the graphical user interface, Internet access, security settings, user administration, software installation and system updates and information). Follow the instructions in YaST to configure these settings. For information about using YaST, refer to the integrated YaST help texts or to the *Book* “Deployment Guide”.

This chapter focuses on individual settings you can change directly in the GNOME settings dialog, without having to use YaST.

3.2 Personal

The following sections introduce examples of how to configure some personal aspects of your GNOME desktop, like your languages used or desktop backgrounds.

3.2.1 Changing the Desktop Background

The desktop background is the image or color that is applied to your desktop. You can also customize the image shown when the screen is locked.

To change the desktop background or the lock screen:

1. Click *Applications* › *System Tools* › *Settings* › *Background*.

2. Click *Background* or *Lock Screen*.

3. Click *Wallpapers*, *Pictures*, or *Colors*.

Wallpapers are preconfigured images distributed with your system. Pictures are your own images from your Pictures directory (~/Pictures). Colors are predefined colors chosen by GNOME developers.

4. Choose an option from the list.

5. When you are satisfied with your choice, click *Select*.

3.2.2 Configuring Language Settings

SUSE Linux Enterprise Server can be configured to use any of several languages. The language setting determines the language of dialogs and menus and can also determine the keyboard and clock layout.

To configure your language settings click *Applications* › *System Tools* › *Settings* › *Region and Language*.

Here you can choose:

- Interface language.
- Date and number formats, currency and related options.
- Input sources (keyboard layout). For non-alphabetic languages there can be additional settings.



Note: Settings Made Using **ibus-setup** Do Not Take Effect

On GNOME, settings made using **ibus-setup** do not take effect. **ibus-setup** can only be used to configure IceWM. Instead, always use the *Settings* application:

- To change input methods, use the panel *Region & Language*.
- To change the key combination that switches between input methods, use the panel *Keyboard*. In it, choose the category *Typing* and the entry *Switch to next input source*.

3.3 Hardware

In the following sections you will find examples of how to configure some hardware aspects of your GNOME desktop, including keyboard or mouse preferences, handling of removable drives (and other media) or screen resolution.

3.3.1 Configuring Bluetooth Settings

The Bluetooth module lets you set the visibility of your machine over Bluetooth and connect to available Bluetooth devices. To configure Bluetooth connectivity, follow these steps:

1. Click *Applications > System Tools > Settings > Bluetooth* to open the Bluetooth settings module.
2. To use Bluetooth, turn the *Bluetooth* switch on.
3. To make your computer visible over Bluetooth, turn the *Visibility* switch on. The computer will start searching for other visible Bluetooth devices in the vicinity and display any found devices in the *Devices* list. At first, the list may be empty.



Note: Temporary Visibility

The *Visibility* switch is meant to be used only temporarily. You only need to turn it on for the initial setup of a connection to a Bluetooth device. After the connection has been established, turn off the switch.


4. On the device you want to connect, turn on Bluetooth connectivity and visibility, too.

5. If the desired device has been found and is shown in the list, click it to establish a connection to it.

You will be asked whether the PINs of the two devices match.

6. If the PINs match, confirm this on *both* your computer and the device.

Both are now paired. On your computer, the device in the list is shown as *Connected*.



Depending on the device type, you can now either see it as a storage device in GNOME Files, set a volume for it in the Sound settings or other things.

To connect to a paired Bluetooth device, select the device in the list. In the dialog that appears, turn the *Connection* switch on. You can send files to the connected device by using the *Send Files* button. If you are connected to a device such as a mobile phone, you can use it as a network device by activating the appropriate option.

To remove a connected device from the list on your computer, click *Remove Device* and confirm your choice. To completely remove the pairing, you also need to do so on your device.

3.3.2 Configuring Power Settings

1. Click *Applications > System Tools > Settings > Power* to open the Power settings module.
2. In the upper part of the dialog, you can see the current state of the battery.
3. In the *Power Saving* section of the dialog, set the *Screen Brightness* to conserve power. You can also set whether to dim the screen after a period of inactivity and set the time interval. You can also set whether to turn off wireless networking after the period of inactivity.
4. In the *Suspend and Power Button* section of the dialog, set the *Automatic Suspend*. When you click it, a separate dialog opens.

In it, you can turn on automatic suspending and associated time intervals. If you are using a computer with a battery, you can set these separately for computer running on battery power or plugged in.

You can also set the action performed when the power button is pressed. Choose *Hibernate* to use a mode where the computer turns off completely but saves your running session to the hard disk. Alternatively, choose *Suspend* or *Nothing*.

3.3.3 Modifying Keyboard Shortcuts

To modify keyboard shortcuts click *Applications > System Tools > Settings > Keyboard*.





FIGURE 3.2: KEYBOARD DIALOG

The *Keyboard* dialog shows the keyboard shortcuts that are configured for your system. Click the categories on the right to view the current shortcuts.

To edit a key combination, first click the row. To set a new key combination, press the keys. To disable a shortcut, press  instead.

To configure keyboard accessibility options, refer to [Section 4.4, “Mobility Impairments”](#). To configure your keyboard layout, refer to [Section 3.2.2, “Configuring Language Settings”](#).

3.3.4 Configuring the Mouse and Touchpad

To modify mouse and touchpad options, click *Applications > System Tools > Settings > Mouse and Touchpad*.




FIGURE 3.3: MOUSE AND TOUCHPAD SETTINGS DIALOG

- In the *General* section of the dialog, you can set the *Primary button* orientation (left or right).
- In the *Mouse* section of the dialog, use *Mouse Speed* to adjust the sensitivity of the mouse pointer.
- In the *Touchpad* section of the dialog, you can turn the touchpad on and off. Use *Touchpad Speed* to adjust the sensitivity of the touchpad pointer. You can also disable the touchpad while typing and enable clicks by tapping the touchpad.
- To test your settings, click *Test Your Settings* and try the pointing device.

For configuration of mouse accessibility options, refer to the [Section 4.4, “Mobility Impairments”](#).

3.3.5 Installing and Configuring Printers

The *Printers* module lets you connect to any available local or remote CUPS server and configure printers.

To start the Printers module, click *Applications > System Tools > Settings > Printers*. For detailed information, refer to [Chapter 6, Managing Printers](#).

3.3.6 Configuring Screens

To specify resolution and orientation for your screen or to configure multiple screens, click *Applications > System Tools > Settings > Displays*.

PROCEDURE 3.1: CHANGING THE SETTINGS FOR A MONITOR

1. To find the right monitor, look for the numbers displayed in the upper left corner of all monitors after you have opened the *Display* dialog. To set options for a monitor, click the list item of the monitor. A new dialog appears.
2. If multiple monitors are attached to the computer, the left part of the dialog will allow you to choose how to use the monitor. You can choose between:

Primary

The screen that shows the panel and important messages.

Secondary Display

A monitor that expands the desktop of the primary monitor.

Mirror

A monitor that mirrors the image on the primary monitor. In terms of resolution, the lowest common denominator will be used.

Turn Off

A screen that is not used.

To rotate the displayed image, use the buttons with the arrows pointing left and right. To mirror the displayed image, use the button with the double arrow icon.

You can set a different resolution by changing the value next to *Resolution*. Not all resolutions provide a sharp and unstretched image. To find the best resolution for your monitor, refer to its manual.

3. When you are done, click *Apply*.

The monitors will now readjust. This can take multiple seconds during which the screen can be black or distorted.

Afterward, a confirmation dialog will appear.

4. If the configuration looks correct, click *Keep Changes*.

If the configuration is not what you hoped for, click *Revert Settings* or wait for 20 seconds. The changes will then be reverted.




FIGURE 3.4: MONITOR RESOLUTION SETTINGS DIALOG

PROCEDURE 3.2: CHANGING THE ARRANGEMENT OF MULTIPLE MONITORS

If you are using multiple screens, set up how they are arranged, so you can use the mouse pointer properly across monitors.

1. Click *Arrange Combined Displays*.
2. To find the right monitor, look for the numbers displayed in the upper left corner of all monitors. Click and drag the monitor image around to move it.
3. When you are done, click *Apply*.

4. If the configuration looks correct, click *Keep Changes*.
If the configuration is not what you hoped for, click *Revert Settings* or wait for 20 seconds.
The changes will then be reverted.

3.3.7 Configuring Sound Settings

The *Sound* tool lets you manage sound devices and set the sound effects. In the top part of the dialog, you can select the general output volume or turn the sound off completely.

To open the sound settings, click *Applications > System Tools > Settings > Sound*.




FIGURE 3.5: CONFIGURING SOUND SETTINGS

3.3.7.1 Configuring Sound Devices

Use the *Output* tab to select the device for sound output. Below the list, choose the sound device setting you prefer, for example balance.

Use the *Input* tab to set the input device volume or to mute the input temporarily. If you have more than one sound device, you can also select a default device for audio input in the *Choose a device for sound input* list.

3.3.7.2 Configuring Sound Effects

Use the *Sound Effects* tab to configure whether and how you want sound to be played when message boxes appear.

Specify the volume at which the sound effects will be played under *Alert volume*. You can also turn the effects on and off.

Select the *Alert Sound* to use.

3.3.8 Networking

To set up networking options, click *Applications > System Tools > Settings > Network*.

In the appearing dialog, you can configure wired or wireless connections and proxies and VPNs.

To learn more about setting up network connections, see Book “Administration Guide”, Chapter 37 “Using NetworkManager”.

3.4 System

In the following sections, you will find examples of how to configure some system aspects of your GNOME desktop. These include preferred applications, changing your user password, and session sharing preferences.

To learn more about configuring assistive technologies, see [Chapter 4, Assistive Technologies](#).

3.4.1 Changing Your Password

For security reasons, it is a good idea to change your login password from time to time. To change your password:

1. Click *Applications > System Tools > Settings > Users*.
2. Click the button labeled with dots next to *Password*.

3. In the first text box, type your current password.
4. In the next text box, type a new password.
You can also click the cog wheel icon at the end of the text box to generate a random password.
5. Confirm your new password by typing it again in the last text box.
6. Click *Change*.

3.4.2 Setting Preferred Applications

1. To change the default application for various common tasks such as browsing the Internet, sending mails or playing multimedia files, click *Applications > System Tools > Settings > Details*.




FIGURE 3.6: PREFERRED APPLICATIONS

2. Click *Default Applications*.

3. Select one of the available applications from the drop-down box. You can choose an application to handle Web, mail, calendar, music, videos or photographs.

3.4.3 Setting Session Sharing Preferences

To open a configuration dialog for sharing a GNOME desktop session between multiple users and set session-sharing preferences, click *Applications > System Tools > Settings > Sharing*.



Important: Sharing Desktop Sessions Affects System Security

Sharing desktop sessions can be a security risk. Use the restriction options available.

Before you can share anything, you need to turn on the switch in the upper part of the dialog. The switch also helps you if you quickly need to disable all sharing options.

- To share your public directory over the network, click *Personal File Sharing* and turn on *Share Public Folder On This Network*. You can also set a password.
- To share your desktop session with other users, click *Screen Sharing* and activate *Allow Remote Control*. To allow other users to control your screen, activate also *Remote Control*. You can also set a password.
- To enable logging in via SSH, click *Remote Login*.

All the sharing screens contain an address which you can give to other users, so they can reach you. To copy a sharing address, click it and select *Copy*. You can then paste it into an e-mail or messaging software.

3.4.4 Configuring Administrative Settings with YaST

For your convenience, YaST is available from the GNOME Settings as well as from the Applications menu. For information about using YaST, refer to *Book "Deployment Guide"*.

4 Assistive Technologies

The GNOME desktop includes assistive technologies to support users with various impairments and special needs, and to interact with common assistive devices. This chapter describes several assistive technology applications designed to meet the needs of users with physical disabilities like low vision or impaired motor skills.

4.1 Enabling Assistive Technologies

To configure accessibility features, open the GNOME Settings dialog (for example using *Applications > System Tools > Settings*) and click *Universal Access*. Each assistive feature can be enabled separately using this dialog.

If you need a more direct access to individual assistive features, turn on *Always Show Universal Access Menu* in the *Universal Access* dialog. A new menu will appear on the bottom panel.

4.2 Visual Impairments

In the *Seeing* section of the *Universal Access* dialog, you can enable features that help people with impaired vision.

- Turning on *High Contrast* enables high contrast black and white icons in the GNOME desktop.
- Turning on *Large Text* enlarges the font used in the user interface.
- Turning on *Zoom* enables a screen magnifier. You can set the desired magnification and magnifier behavior, including color effects.
- If the *Screen Reader* is turned on, any UI element or text that receives keyboard focus is read aloud.
- If the *Sound Keys* are turned on, a sound is played whenever Num Lock or Caps Lock are turned on.

4.3 Hearing Impairments

In the *Hearing* section of the *Universal Access* dialog, you can enable features helping people with impaired hearing.

If the *Visual Alerts* are turned on, a window title or the entire screen is flashed when an alert sound occurs.

4.4 Mobility Impairments

In the *Typing* and *Pointing and Clicking* sections of the *Universal Access* dialog, you can enable features that help people with mobility impairments.

- If the *Screen Keyboard* is turned on, a virtual keyboard appears whenever you need to enter text. You can use the screen keyboard by clicking the virtual keys.
- Click *Typing Assist (AccessX)* to open a dialog where you can enable various features that make typing easier.
 - With *Enable by Keyboard*, you can turn accessibility features on or off by using the keyboard.
 - *Sticky Keys* allows you to type key combinations one key at a time rather than having to hold down all of the keys at once. For example, the **Alt**–**→** shortcut switches between windows.
With sticky keys turned off, you need to hold down both keys at the same time. With sticky keys turned on, press **Alt** and then **→** to do the same.
 - Turn on *Slow Keys* if you want a delay between pressing a key and the letter being displayed on the screen. This means that you need to hold down each key you want to type for a little while before it appears. Use slow keys if you accidentally press several keys at a time when you type, or if you find it difficult to press the right key on the keyboard first time.
 - Turn on *Bounce Keys* to ignore key presses that are rapidly repeated. This can help, for example, if you have hand tremors which cause you to press a key multiple times when you only want to press it once.
- Turn on *Mouse Keys* to control the mouse pointer using the numeric keypad on your keyboard.

- Click *Click Assist* to open a dialog where you can enable various features that make clicking easier: simulated secondary click and hover click.
 - Turn on *Simulated Secondary Click* to activate the secondary click (usually the right mouse button) by holding down the primary button for a predefined *Acceptance delay*. This is useful if you find it difficult to move your fingers individually on one hand, or if your pointing device only has a single button.
 - Turn on *Hover Click* to trigger a click by hovering your mouse pointer over an object on the screen. This is useful if you find it difficult to move the mouse and click at the same time. If this feature is turned on, a small Hover Click window opens and stays above all of your other windows. You can use this to choose what sort of click should happen when you hover. When you hover your mouse pointer over a button and do not move it, the pointer gradually changes color. When it has fully changed color, the button will be clicked.
- Use the slider to adjust the *Double-Click Delay* according to your needs.

4.5 For More Information

You can find further information in the GNOME help, which is also available online at <https://help.gnome.org/users/gnome-help/3.20/a11y.html.en> .

II Connectivity, Files and Resources

- 5 Accessing Network Resources **43**
- 6 Managing Printers **50**
- 7 Backing Up User Data **51**
- 8 Passwords and Keys: Signing and Encrypting Data **53**
- 9 gFTP: Transferring Data from the Internet **66**

5 Accessing Network Resources

From your desktop, you can access files and directories or certain services on remote hosts or make your own files and directories available to other users in your network. SUSE® Linux Enterprise Server offers the following ways of accessing and creating network shared resources.

Network Browsing

Your file manager, GNOME Files, lets you browse your network for shared resources and services. Learn more about this in [Section 5.3, “Accessing Network Shares”](#).

Sharing Directories in Mixed Environments

Using GNOME Files, configure your files and directories to share with other members of your network. Make your data readable or writable for users from any Windows or Linux workstation. Learn more about this in [Section 5.4, “Sharing Directories”](#).

Managing Windows Files

SUSE Linux Enterprise Server can be configured to integrate into an existing Windows network. Your Linux machine then behaves like a Windows client. It takes all account information from the Active Directory domain controller, just as the Windows clients do. Learn more about this in [Section 5.5, “Managing Windows Files”](#).

Configuring and Accessing a Windows Network Printer

You can configure a Windows network printer through the GNOME control center. Learn how to do this in [Section 5.6, “Configuring and Accessing a Windows Network Printer”](#).

5.1 Connecting to a Network

You can connect to a network with wired and wireless connections. To view your network connection, check the network icon in the right part of the main panel. If you click the icon, you can see more details in the menu. Click the connection name to see more details and access the settings.

To learn more about connecting to a network, see *Book “Administration Guide”, Chapter 37 “Using NetworkManager”*.

5.2 General Notes on File Sharing and Network Browsing

Important: Contact Your Administrator Before Setup

Whether and to what extent you can use file sharing and network browsing and in your network highly depends on the network structure and on the configuration of your machine.

Before setting up either of them, contact your system administrator. Check whether your network structure supports a feature and whether your company's security policies permit it.

Network browsing, be it SMB browsing for Windows shares or SLP browsing for remote services, relies heavily on the machine's ability to send broadcast messages to all clients in the network. These messages and the clients' replies to them enable your machine to detect any available shares or services.

For broadcasts to work effectively, your machine must be part of the same subnet as all other machines it is querying. If network browsing does not work on your machine or the detected shares and services do not meet your expectations, contact your system administrator to ensure that you are connected to the appropriate subnet.

To allow network browsing, your machine needs to keep several network ports open to send and receive network messages that provide details on the network and the availability of shares and services. The standard SUSE Linux Enterprise Server is configured for tight security and has a firewall that protects your machine against the Internet.

To adjust the firewall configuration, you either need to ask your system administrator to put your interface into the internal zone or to tear down the firewall entirely (depending on your company's security policy). If you try to browse a network while a restrictive firewall is running on your machine, GNOME Files warns you that your security restrictions are not allowing it to query the network.

5.3 Accessing Network Shares

Networking workstations can be set up to share directories. Typically, files and directories are marked to allow users remote access. These are called *network shares*. If your system is configured to access network shares, you can use your file manager to access these shares and browse them just as easily as if they were located on your local machine. Your level of access to the shared directories (whether read-only or write access, as well) is dependent on the permissions granted to you by the owner of the shares.

To access network shares, open GNOME Files and click *Other Locations* in the sidebar. GNOME Files displays the servers and networks that you can access. Double-click a server or network to access its shares. You might be required to authenticate to the server by providing a user name and password. Common network shares are SFTP-accessible resources (SSH File Transfer Protocol) or Windows shares.




FIGURE 5.1: NETWORK FILE BROWSER

PROCEDURE 5.1: ADDING A NETWORK PLACE

1. Open GNOME Files and click *Other Locations* in the sidebar. It shows a *Connect to Server* text box.

2. Enter the server address.
3. Click *Connect*.

5.4 Sharing Directories

Sharing and exchanging documents is a must-have in corporate environments. GNOME Files offers you file sharing, which makes your files and directories available to both Linux and Windows users.

5.4.1 Enabling Sharing on the Computer


Before you can share a directory, you must enable sharing on your computer. To enable sharing:

1. Start YaST from the main menu.
2. Enter the root password.
3. In the category *Network Services*, click *Windows Domain Membership*.
4. Click *Allow Users to Share Their Directories*, then click *OK*.

5.4.2 Enabling Sharing for a Directory

To configure file sharing for a directory:

1. Open GNOME Files.
2. Right-click a directory, select *Properties* and click *Share*.



3. Select *Share this folder*.
4. If you want other people to be able to write to the directory, select *Allow others to create and delete files in this folder*. To allow access for people without a user account check *Guest Access*.
5. Click *Create Share*.
6. If the directory does not already have the permissions that are required for sharing, a dialog appears. Click *Add the permissions automatically*.

The directory icon changes to indicate that the directory is now shared.

Important: Samba Domain Browsing and Firewalls

Samba domain browsing only works if your system's firewall is configured accordingly. Either disable the firewall entirely or assign the browsing interface to the internal firewall zone. Ask your system administrator how to proceed.

5.5 Managing Windows Files

With your SUSE Linux Enterprise Server machine being an Active Directory client, you can browse, view and manipulate data located on Windows servers. The following examples are the most prominent ones:

Browsing Windows Files with GNOME Files

Use GNOME Files's network browsing features to browse your Windows data.

Viewing Windows Data with GNOME Files

Use GNOME Files to display the contents of your Windows user directory as you would for displaying a Linux directory. Create new files and directories on the Windows server.

Manipulating Windows Data with GNOME Applications

Many GNOME applications allow you to open files on the Windows server, manipulate them and save them back to the Windows server.

Single Sign-On

GNOME applications, including GNOME Files, support Single Sign-On. This means that you do not need to re-authenticate when you access other Windows resources. These can be Web servers, proxy servers or groupware servers like Microsoft Exchange*. Authentication against all these is handled silently in the background using the user name and password you provided when you logged in.

To access your Windows data using GNOME Files, proceed as follows:

1. Open GNOME Files and click *Network* in the Places pane.
2. Double-click *Windows Network*.
3. Double-click the icon of the workgroup containing the computer you want to access.
4. Click the computer's icon (and authenticate if prompted to do so) and navigate to the shared directory on that computer.

To create directories in your Windows user directory using GNOME Files, proceed as you would when creating a Linux directory.

5.6 Configuring and Accessing a Windows Network Printer

Being part of a corporate network and authenticating against a Windows Active Directory server, you can access corporate resources such as printers. GNOME allows you to configure printing from your Linux client to a Windows network printer.

To configure a Windows network printer for use through your Linux workstation, proceed as follows:

1. Start the GNOME control center from the main menu by clicking *Applications > System Tools > Settings > Printers*.



Note: Starting the CUPS Service

The CUPS service is not started by default after installation of SUSE Linux Enterprise Server. If the *Printers* dialog shows a message that the printing service is currently not available, you need to start the CUPS service manually.

Start it by opening a shell and typing:

```
sudo systemctl start cups
```

2. Click *Unlock* and enter the root password.
3. Click the plus icon.
4. Select a Windows printer connected via Samba.

To print to the Windows network printer configured above, select it from the list of available printers.

6 Managing Printers

SUSE® Linux Enterprise Server makes it easy to print your documents, whether your computer is connected directly to a printer or linked remotely on a network. This chapter describes how to set up printers in SUSE Linux Enterprise Server and manage print jobs.

6.1 Installing a Printer

Before you can install a printer, you need to know the root password and have your printer information ready. Depending on how you connect the printer, you might also need the printer URI, TCP/IP address or host, and the driver for the printer. A number of common printer drivers ship with SUSE Linux Enterprise Server. If you cannot find a driver for the printer, check the printer manufacturer's Web site.

1. Click *Applications > System Tools > Settings > Printers*.
2. Click *Unlock* and enter the root password.
3. Click the plus icon.
4. If there are too many printers in the list, filter them by entering an IP address or a keyword into the search field in the lower part of the dialog.
5. Select a printer from the list of available printers and click *Add*.

The installed printer appears in the Printers panel. You can now print to the printer from any application.

7 Backing Up User Data

The Backup tool is a simple framework to let users back up and restore their own data such as home directories or selected files. It is possible to create scheduled backups or backups on request, and to play back a previous state of this data.

7.1 Creating Backups

First schedule which data you want to back up and when to do it.

1. Click *Applications > System Tools > Backup*.
2. If you are opening the application for the first time, you will see a screen welcoming you. Click *Just show my backup settings*.
3. On the *Overview* tab you can turn the *Automatic backups* on and off. You can also see the overview of the current settings.
4. On the *Storage* tab, select a *Backup Location* and a *Folder* to which the backup should be written.
5. On the *Folders* tab select the directories to back up and directories to ignore. For example, if you want to back up your home directory except for the Downloads directory, add your home directory to the category *Folders to back up* and your Downloads directory to the category *Folders to ignore*.
6. On the *Schedule* tab select how often to perform the automatic backups (daily or weekly) and how long to keep the backups.
7. (Optional) If you want to perform a backup immediately, too, switch back to the *Overview* tab and click *Back Up Now*.
 - a. Choose whether you want the backup to be password-protected.
If so, type a password in the two text boxes next to *Encryption Password* and *Confirm Password*.
If not, click *Allow Restoring Without a Password*.
 - b. Click *Continue* to start the backup process. When the backup is finished, the window will close.

7.2 Restoring Data

To restore a previous state of your data, proceed as follows:

1. Select *Applications > System Tools > Backup*.
2. On the *Overview* tab, click *Restore*.
3. Choose the location from which to restore. Click *Forward*. The tool searches for backups stored in that location.
4. Choose a date. Click *Forward*.
5. Choose whether to restore the files to the original location or to another directory. Click *Forward* to see a summary of your choices.
6. Click *Restore* to start the restoration process.

8 Passwords and Keys: Signing and Encrypting Data

The GNOME Passwords and Keys program is an important component of the encryption infrastructure on your system. With this program, you can create and manage PGP and SSH keys, import, export and share keys, back up your keys and keyring, and cache your passphrase.

Start the program by choosing *Applications > Utilities > Passwords and Keys*




FIGURE 8.1: PASSWORD AND KEYS MAIN WINDOW

8.1 Signing and Encryption

Signing. Attaching electronic signatures to pieces of information, such as e-mail messages or software to prove its origin. To keep someone else from writing messages using your name, and to protect both you and the people you send them to, you should sign your mails. Signatures help you check the sender of the messages you receive and distinguish authentic messages from malicious ones.

Software developers sign their software so that you can check the integrity. Even if you get the software from an unofficial server, you can verify the package with the signature.

Encryption. You might also have sensitive information you want to protect from other parties. Encryption helps you transform data and make it unreadable for others. This is important for companies so they can protect internal information and their employees' privacy.

8.2 Generating a New Key Pair

To exchange encrypted messages with other users, you must first generate your own pair of keys. It consists of two parts:

- **Public Key.** This key is used for encryption. Distribute it to your communication partners, so they can use it to encrypt files or messages for you.
- **Private Key.** This key is used for decryption. Use it to make encrypted files or messages from others (or yourself) legible again.



Important: Access to the Private Key

If others gain access to your private key, they can decrypt files and messages intended only for you. Never grant others access to your private key.

8.2.1 Creating OpenPGP Keys

OpenPGP is a non-proprietary protocol for encrypting e-mail with the use of public-key cryptography based on PGP. It defines standard formats for encrypted messages, signatures, private keys, and certificates for exchanging public keys.

1. Click *Applications > Utilities > Passwords and Keys*.
2. Click *File > New*.
3. Select *PGP Key* and click *Continue*.
4. Specify your full name and e-mail address.
5. Click *Advanced key options* to specify the following advanced options for the key.

Comment

An optional comment.

Encryption Type

Specifies the encryption algorithms used to generate your keys. *DSA ElGamal* is the recommended choice because it lets you encrypt, decrypt, sign, and verify as needed. Both *DSA (sign only)* and *RSA (sign only)* allow only signing.

Key Strength

Specifies the length of the key in bits. The longer the key, the more secure it is (provided a strong passphrase is used). Keep in mind that performing any operation with a longer key requires more time than it does with a shorter key. Acceptable values are between 1024 and 4096 bits. At least 2048 bits are recommended.

Expiration Date

Specifies the date at which the key will cease to be usable for performing encryption or signing operations. You will need to either change the expiration date or generate a new key or subkey after this amount of time passes. Sign your new key with your old one before it expires to preserve your trust status.

6. Click *Create* to create the new key pair.

The *Passphrase for New PGP Key* dialog opens.

7. Specify the passphrase twice for your new key, then click *OK*.

When you specify a passphrase, use the same practices you use when you create a strong password.

8.2.2 Creating Secure Shell Keys

Secure Shell (SSH) is a method of logging in to a remote computer to execute commands on that machine. SSH keys are used in key-based authentication system as an alternative to the default password authentication system. With key-based authentication, there is no need to manually type a password to authenticate.

1. Click *Applications > Utilities > Passwords and Keys*.
2. Click *File > New*.
3. Select *Secure Shell Key*, then click *Continue*.
4. Specify a description of what the key is to be used for.
You can use your e-mail address or any other reminder.

5. Optionally, click *Advanced key options* to specify the following advanced options for the key.

Encryption Type. Specifies the encryption algorithms used to generate your keys. Select *RSA* to use the Rivest-Shamir-Adleman (RSA) algorithm to create the SSH key. This is the preferred and more secure choice. Select *DSA* to use the Digital Signature Algorithm (DSA) to create the SSH key.

Key Strength. Specifies the length of the key in bits. The longer the key, the more secure it is (provided a strong passphrase is used). Keep in mind that performing any operation with a longer key requires more time than it does with a shorter key. Acceptable values are between 1024 and 4096 bits. At least 2048 bits is recommended.

6. Click *Just Create Key* to create the new key, or click *Create and Set Up* to create the key and set up another computer to use for authentication.
7. Specify the passphrase for your new key, click *OK*, then repeat.
When you specify a passphrase, use the same practices you use when you create a strong password.

8.3 Modifying Key Properties

You can modify properties of existing OpenPGP or SSH keys.

8.3.1 Editing OpenPGP Key Properties

The descriptions in this section apply to all OpenPGP keys.

1. Click *Applications > Utilities > Passwords and Keys*.
2. Double-click the PGP key you want to view or edit.
3. Use the options on the *Owner* tab to add a photo to the key or to change the passphrase associated with the key.

Photo IDs allow a key owner to embed one or more pictures of themselves in a key. These identities can be signed like normal user IDs. A photo ID must be in JPEG format. The recommended size is 120 × 150 pixels.

If the chosen image does not meet the required file type or size, *Passwords and Keys* can resize and convert it on the fly from any image format supported by the GDK library.

4. Click the *Names and Signatures* tab to add a user ID to a key.

See [Section 8.3.1.1, "Adding a User ID"](#) for more information.

5. Click the *Details* tab, which contains the following properties:

Key ID: The Key ID is similar to the Fingerprint, but the Key ID contains only the last eight characters of the fingerprint. It is generally possible to identify a key with only the Key ID, but sometimes two keys might have the same Key ID.

Type: Specifies the encryption algorithm used to generate a key. DSA keys can only sign. ElGamal keys are used to encrypt.

Strength: Specifies the length, in bits, of the key. The longer the key, the more security it provides. However, a long key will not compensate for the use of a weak passphrase.

Fingerprint: A unique string of characters that exactly identifies a key.


Created: The date the key was created.

Expires: The date the key can no longer be used (a key can no longer be used to perform key operations after it has expired). Changing a key's expiration date to a point in the future re-enables it. A good general practice is to have a master key that never expires and multiple subkeys that do expire and are signed by the master key.

Override Owner Trust: Here you can set the level of trust in the owner of the key. Trust is an indication of how sure you are of a person's ability to correctly extend the Web of trust. When there is a key that you have not signed, the validity of the key is determined from its signatures and how much you trust the people who made those signatures.

Export Secret Key: Exports the key to a file.

Subkeys: See [Section 8.3.1.2, "Editing OpenPGP Subkey Properties"](#) for more information.



6. Click *Close*.

8.3.1.1 Adding a User ID

User IDs allow multiple identities and e-mail addresses to be used with the same key. Adding a user ID is useful, for example, when you want to have an identity for your job and one for your friends. They take the following form:


Name (*COMMENT*) <*E-MAIL*>

1. Click *Applications > Utilities > Passwords and Keys*.
2. Double-click the PGP key you want to view or edit.
3. Click the *Names and Signatures* tab, then click *Add Name*.
4. Specify a name in the *Full Name* field.
You must enter at least five characters in this field.
5. Specify an e-mail address in the *E-Mail Address* field.
Your e-mail address is how most people will locate your key on a key server or other key provider. Make sure it is correct before continuing.
6. In the *Key Comment* field, specify additional information that will display in the name of your new ID.
This information can be searched for on key servers.
7. Confirm your changes and enter the passphrase when prompted for it.

8.3.1.2 Editing OpenPGP Subkey Properties

Each OpenPGP key has a single master key used to sign only. Subkeys are used to encrypt and to sign as well. In this way, if your subkey is compromised, you do not need to revoke your master key.

1. Click *Applications > Utilities > Passwords and Keys*.
2. Double-click the PGP key you want to edit.
3. Click the *Details* tab, then click to show the *Subkeys* category.
4. Use the buttons on the left of the dialog to add, delete, expire, or revoke subkeys.



Each subkey has the following information:

ID: The identifier of the subkey.

Type: Specifies the encryption algorithm used to generate a subkey. DSA keys can only sign, ElGamal keys are used to encrypt, and RSA keys are used to sign or to encrypt.

Usage: Shows if the key can be used to sign, to certify, or also to encrypt.

Created: Specifies the date the key was created.

Expires: Specifies the date the key can no longer be used.

Status: Specifies the status of the key.

Strength: Specifies the length, in bits, of the key. The longer the key, the more security it provides. However, a long key will not compensate for the use of a weak passphrase.

5. Click *Close*.

8.3.2 Editing Secure Shell Key Properties

The descriptions in this section apply to all SSH keys.

1. Click *Applications > Utilities > Passwords and Keys*.
2. Double-click the Secure Shell key you want to view or edit.
3. Use the options on the *Key* tab to change the name of the key or the passphrase associated with the key.
4. Click the *Details* tab, which contains the following properties:


Algorithm: Specifies the encryption algorithm used to generate a key.

Strength: Indicates the length in bits of a key. The longer the key, the more security it provides. However, a long key does not make up for the use of a weak passphrase.

Location: The location where the private key has been stored.

Fingerprint: A unique string of characters that exactly identifies a key.

Export Complete Key: Exports the key to a file.



5. Click *Close*.

8.4 Importing Keys

Keys can be exported to text files. These files contain human-readable text at the beginning and at the end of a key. This format is called an ASCII-armored key.

To import keys:

1. Click *Applications > Utilities > Passwords and Keys*.
2. Click *File > Import*.
3. Select a file containing at least one ASCII-armored public key.
4. Click *Open* to import the key.

You can also paste keys inside *Passwords and Keys*:

1. Select an ASCII-armored public block of text, then copy it to the clipboard.
2. Click *Applications > Utilities > Passwords and Keys*.
3. Click *Edit > Paste*

8.5 Exporting Keys

To export keys:

1. Click *Applications > Utilities > Passwords and Keys*.
2. Select the keys you want to export.
3. Click *File > Export*.
4. Specify a file name and location for the exported key.
5. Click *Save* to export the key.

You can also export keys to the clipboard in an ASCII-armored block of text:

1. Click *Applications > Utilities > Passwords and Keys*.
2. Select the keys you want to export.
3. Click *Edit > Copy*.


8.6 Signing a Key

Signing another person's key means that you are giving trust to that person. Before signing a key, carefully check the key's fingerprint to ensure that the key really belongs to that person.

Trust is an indication of how sure you are of a person's ability to correctly extend the Web of trust. When there is a key that you have not signed, the validity of the key is determined from its signatures and how much you trust the people who made those signatures.

1. Click *Applications > Utilities > Passwords and Keys*.
2. Select the key you want to sign from the *My Personal Keys* or *Other Keys* tabs.
3. Click *File > Sign*.

4. Select how carefully the key has been checked, then indicate if the signature should be local to your keyring, and if your signature can be revoked:



The screenshot shows a GPG signing dialog box. At the top, there is a red seal icon and the text: "By signing you indicate your trust that this key belongs to: Tux Linux <tux@example.com>". Below this, the question "How carefully have you checked this key?" is followed by three radio buttons: "Not at all" (selected), "Casually", and "Very Carefully". A note below the radio buttons states: "Not at all: means you believe the key is owned by the person who claims to own it, but you could not or did not verify this to be a fact." The next section, "How others will see this signature:", has two checkboxes: "Others may not see this signature" (unchecked) and "I can revoke this signature at a later date." (checked). Below this is the "Sign key as:" section with a dropdown menu showing "Signer: Tux Linux <tux@example.com>". At the bottom, there are three buttons: "Help", "Cancel", and "Sign" (with a blue arrow icon).

5. Click *Sign*.

8.7 Password Keyrings

You can use password keyring preferences to create or remove keyrings, to set the default keyring for application passwords or to change the unlock password of a keyring. To create a new keyring, follow these steps:


1. Click *Applications > Utilities > Passwords and Keys*.
2. Click *File > New > Password Keyring*, then click *Continue*.
3. Enter a name for the keyring and click *Add*.
4. Set and confirm a new *Password* for the keyring and click *Create*.

To change the unlock password of an existing keyring, right-click the keyring in the *Passwords* tab and click *Change Password*. You need to provide the old password to be able to change it. To change the default keyring for application passwords, right-click the keyring in the *Passwords* tab and click *Set as Default*.

8.8 Key Servers

You can keep your keys up-to-date by synchronizing keys periodically with remote key servers. Synchronizing will ensure that you have the latest signatures made on all of your keys, so that the Web of trust will be effective.

1. Click *Applications > Utilities > Passwords and Keys*.
2. Click *Edit > Preferences*, then click the *Key Servers* tab.



Passwords and Keys provides support for HKP and LDAP key servers.

HKP Key Servers: HKP key servers are ordinary Web-based key servers, such as the popular [hkp://pgp.mit.edu:11371](http://pgp.mit.edu:11371), also accessible at <http://pgp.mit.edu>.

LDAP Key Servers: LDAP key servers are less common, but use the standard LDAP protocol to serve keys. <ldap://keyserver.pgp.com> is a good LDAP server.

You can *Add* or *Remove* key servers to be used using the buttons on the left. To add a new key server, set its type, host and port, if necessary.

3. Set whether you want to automatically publish your public keys and which keyserver to use. Set whether you want to automatically retrieve keys from key servers and whether to synchronize modified keys with key servers.
4. Click *Close*.

8.9 Key Sharing

Key Sharing is provided by DNS-SD, also known as Bonjour or Rendezvous. Enabling key sharing adds the local *Passwords and Keys* users' public key rings to the remote search dialog. Using these local key servers is generally faster than accessing remote servers.

1. Click *Applications > Utilities > Passwords and Keys*.
2. Click *Edit > Preferences*, then click the *Key Servers* tab.
3. Select *Automatically synchronize modified keys with key servers*.
4. Click *Close*.

9 gFTP: Transferring Data from the Internet

gFTP is a multithreaded file transfer client. It supports the FTP, FTPS (control connection only), HTTP, HTTPS, SSH, and FSP protocols. Furthermore, it allows the transfer of files between two remote FTP servers via FXP. To start gFTP, click *Applications > Internet > gFTP*.




FIGURE 9.1: GFTP—MAIN WINDOW

9.1 ASCII Compared to Binary Transfers

There are two common ways of transferring files via FTP: ASCII and binary. *ASCII* mode transfers files as text. ASCII files are `.txt`, `.asp`, `.html`, and `.php` files, for example. *Binary* mode transfers files as raw data. Binary files are `.wav`, `.jpg`, `.gif`, and `mp3` files, for example.

To change the transfer mode, click the *FTP* menu and select *Binary* or *Ascii*.

When transferring ASCII files from Linux/Unix to Windows or vice versa, open the *Preferences* dialog by clicking *FTP > Preferences*. Switch to the *FTP* tab and select *Transfer Files in ASCII Mode* to ensure that newline characters are correctly converted. This option will automatically be disabled in Binary mode.

9.2 Connecting to a Remote Server


To connect to a remote server, do the following:

1. Click *Remote > Open Location*.
2. Specify a URL to connect to and click *Connect*.
3. Specify your user name and click *Connect*. Then specify your password and click *Connect*. To connect anonymously, leave the user name blank.
4. If the connection is successful, the right part of the gFTP window lists files from the remote computer. The file listing on the left side continues to show files from your local computer. You can now upload and download files via drag and drop or by using the arrow buttons.

To bookmark a site you access frequently, click *Bookmarks > Add Bookmark*. Specify a name for the bookmark, then click *Add*. The new bookmark is added to your list of bookmarks.

9.3 Transferring Files

In the following figure, the file list on the right contains the remote server's directory of files. The file list on the left side contains your local computer's directory of files (on your hard disk or network).



```

RETR /pub/people/ug/autoyast/driverupdate.SLES9SP3
150 Opening BINARY mode data connection for /pub/people/ug/autoyast/driverupdate.SLES9SP3 (6787072 bytes).
226 File send OK.
Successfully transferred /pub/people/ug/autoyast/driverupdate.SLES9SP3 at 25499.76 KB/s

```

FIGURE 9.2: GFTP FILE TRANSFER

To download files, select the files you want to download in the remote list of files, then click the arrow button pointing to the left. The progress of each download is listed in the field in the middle of the window. If the transfer is successful, the files appear in the directory listing on the left.

To upload a file, select the files you want to upload in your local directory listing on the left, then click the arrow button pointing to the right. The progress of each download is listed in the field in the middle of the window. If the transfer is successful, the files appear in the remote directory listing on the right.

To modify preferences for your downloads, select *FTP > Preferences* from the menu.


9.4 Setting Up an HTTP Proxy Server

To set up an HTTP proxy server, do the following:

1. From the menu, select *FTP > Preferences*, then select the *FTP* tab.

2. Enter the *Proxy hostname* and *Proxy port*. If applicable, also provide your login credentials for the proxy server. Choose a proxy type from the *Proxy Server Type* drop-down box.
3. Click the *HTTP* tab, and enter the same proxy server information in the dialog as described above. Port numbers for FTP and HTTP proxy may differ.
4. Click *OK*.

9.5 For More Information

You can find more information about gFTP at <http://www.gftp.org> .

III LibreOffice

- 10 LibreOffice: The Office Suite **71**
- 11 LibreOffice Writer **85**
- 12 LibreOffice Calc **97**
- 13 LibreOffice Impress, Base, Draw, and Math **103**

10 LibreOffice: The Office Suite

LibreOffice is an open source office suite that provides tools for all types of office tasks such as writing texts, working with spreadsheets, or creating graphics and presentations. With LibreOffice, you can use the same data across different computing platforms. You can also open and edit files in other formats, including Microsoft* Office* formats, then save them back to this format, if needed. This chapter contains information that applies to all LibreOffice modules.

10.1 LibreOffice Modules

LibreOffice consists of several application modules (subprograms) which are designed to integrate with each other. While this chapter contains information that applies to all LibreOffice modules, the following chapters and sections contain information on individual modules. Find a short description and where each module is described in *Table 10.1, “The LibreOffice Application Modules”*.

A full description of each module is available in the application help, described in *Section 10.10, “For More Information”*.

TABLE 10.1: THE LIBREOFFICE APPLICATION MODULES

Module	Purpose	Described in
Writer	Word processor module	<i>Chapter 11</i>
Calc	Spreadsheet module	<i>Chapter 12</i>
Impress	Presentation module	<i>Section 13.1</i>
Base	Database module	<i>Section 13.2</i>
Draw	Module for drawing vector graphics	<i>Section 13.3</i>
Math	Module for generating mathematical formulas	<i>Section 13.4</i>

10.2 Starting LibreOffice

To start LibreOffice, click *Applications > Office > LibreOffice*. In the LibreOffice start center, choose the type of document you want to create.

There are multiple methods to directly start one of the LibreOffice modules:

- If any LibreOffice module is open, you can start any of the other modules by clicking *File > New* and then selecting the type of document you want to create.
- You can also start individual LibreOffice modules from the menu *Applications*.
- As an alternative, use the command **libreoffice** and one of the options `--writer`, `--calc`, `--impress`, `--draw`, or `--base` to start the respective module.
LibreOffice has many command line options, especially for allowing document conversions. To learn more about the command line options of LibreOffice, see **libreoffice --help** or the man page of LibreOffice (`man libreoffice(1)`).

Before you start working with LibreOffice, you may be interested in changing some options from the preferences dialog. Click *Tools > Options* to open it. The most important ones are:

LibreOffice > User Data

Specify your user data such as company, first and last name, street, city, and other useful information. This data has many uses: It is used in the comment functions of Writer and Calc, for authorship information in PDF documents, and for serial letters in Writer.

LibreOffice > Fonts

Map font names to installed fonts. This can be useful if you exchange documents with others and the document you received contains fonts that are not available on your system.

Load/Save > General

Contains loading and saving specific options. For example, you can choose whether to always create a backup copy and which file format LibreOffice should use by default.

To learn more about configuring LibreOffice, see [Section 10.7, “Changing the Global Settings”](#).

10.3 The LibreOffice User Interface

The user interface of most of LibreOffice is very similar across its modules:

Menu Bar

At the top of the application, there is the menu bar which gives access to almost all functionality of LibreOffice. The menu bar can be customized to include more or fewer functions. You can also add and remove menus.

Toolbars

By default, the toolbars are positioned directly below the menu bar. The toolbars comprise the most used and most important items of the module.

To dock a toolbar to any other side of the window, drag it to the right position. To make a toolbar float, drag it into the middle of the window. They can be customized to include more or fewer functions. You can also add and remove toolbars.

Side Bar

By default, the side bar is positioned at the right side of the LibreOffice window. On the first start of LibreOffice, it is only visible as several icons stacked vertically. Clicking one of the icons opens a panel with more elements. Click the icon again to close the panel. Similarly to the toolbars, the side bar comprises the most important functions.

To dock the side bar to the left or right side of the window, drag it to the right position. To make the side bar float, drag it into the middle of the window. To hide the side bar, click the vertical arrowhead button on the document-facing side of the side bar.

You can hide or show side bar panels but cannot customize their functionality.

Statusbar

The statusbar is displayed at the bottom of the window. It mainly shows information about the document, such as the number of words (in Writer) or the sum of values of selected cells (in Calc). However, it can also be used to change the zoom or language settings. Many elements open additional menus or dialogs on left click, right click, or double click.

For more information on customizing LibreOffice, see [Section 10.6, "Customizing LibreOffice"](#).

10.4 Compatibility with Other Office Applications

The native file format of LibreOffice is the OpenDocument format. OpenDocument is an ISO-standardized format for office documents that is based on XML. However, LibreOffice can also work with documents, spreadsheets, presentations, and databases in many other formats, including Microsoft Office formats. Files in Microsoft Office formats can be opened and saved back normally.

10.4.1 Opening Documents from Other Office Suites

If you use LibreOffice in an environment where you need to share documents with Microsoft Word users, you should have little or no trouble exchanging document files. However, very complex documents can require editing after opening. Complex documents are documents containing, for example, complicated tables, Microsoft Office macros, or unusual fonts, formatting, or graphical objects.

In case there should ever be issues with opening documents, try the following strategies:

- **Text Documents.** Consider opening text documents in the original application and saving them as RTF or plain text (TXT). However, saving as plain text means that all formatting will be lost.
- **Spreadsheets.** Consider opening spreadsheets in the original application and saving them as Excel files. If this does not work, try the CSV format. However, saving as CSV means that all formatting, cell type definitions, formulas, and macros will be lost.

10.4.2 Converting Documents to the OpenDocument Format

LibreOffice can read, edit, and save documents in several formats. It is not necessary to convert files from those formats to the OpenDocument format used by LibreOffice to use those files. However, if you want to convert the files, you can do so. To convert several documents, such as when first switching to LibreOffice, do the following:

1. Select *File > Wizards > Document Converter*.
2. Choose the file format from which to convert.
3. Click *Next*.

4. Specify where LibreOffice should look for templates and documents to convert and in which directory the converted files should be placed.
Documents retrieved from a Windows partition are usually in a subdirectory of /windows.
5. Make sure that all other settings are correct, then click *Next*.
6. Review the summary of the actions to perform, then start the conversion by clicking *Convert*.
The amount of time needed for the conversion depends on the number of files and their complexity. For most documents, conversion does not take long.
7. When everything is done, close the Wizard.

10.4.3 Sharing Files with Users of Other Office Suites

LibreOffice is available for several operating systems. This makes it an excellent tool when a group of users frequently need to share files and do not use the same system on their computers. When sharing documents with others, you have several options:

If the recipient needs to be able to edit the file

Save the document in the format the other user needs. For example, to save as a Microsoft Word file, click *File > Save As*, then select the Microsoft Word file type for the version of Word the other user needs.

If the recipient only needs to read the document

Export the document to a PDF file with *File > Export as PDF*. PDF files can be read on any platform using a PDF viewer.

Sharing a document for editing

Agree on a common exchange format that works for everyone. TXT and RTF formats, although limited in formatting, can be a good option for text documents.

E-mailing a document as a PDF

Click *File > Send > E-mail as PDF*. Your default e-mail program opens with the file attached.

E-mailing a document to a Microsoft Word user

Click *File > Send > E-mail as Microsoft Word*. Your default e-mail program opens with the file attached.

10.5 Saving Files with a Password

You can save files, no matter in which LibreOffice format, with a password. Unlike older versions of LibreOffice, the encryption applied to the document with recent versions of LibreOffice is very strong. However, this encryption does not protect file names and file sizes of encrypted files. If that is important to you, see the alternate encryption methods described in *Book “Security Guide”, Chapter 12 “Encrypting Partitions and Files”*.

PROCEDURE 10.1:

1. To save a file with a password, select *File > Save* or *File > Save As*.
2. In the dialog that opens, activate the check box *Save with password* at the bottom and click *Save*.
3. Type and confirm your password, then click *OK*.

The next time you open the file, you will be prompted for the password.

To change the password, do either of the following:

- Overwrite the same file by selecting *File > Save As*. Make sure *Save with Password* is deactivated.
- Select *File > Properties* and click *Change Password* to access the password dialog.

10.6 Customizing LibreOffice

You can customize LibreOffice to best suit your needs and working style. Toolbars, menus, and key combinations can all be reconfigured to help you more quickly access the features you use the most.

You can also assign macros to application events if you want specific actions to occur when those events take place. For example, if you always work with a specific spreadsheet, you can create a macro that opens the spreadsheet and assign the macro to the *Start Application* event.

This section contains simple, generic instructions for customizing your environment. The changes you make are effective immediately. This means you can see if the changes are what you wanted and go back and modify them if they are not. See the LibreOffice help files for detailed instructions.

To access the customization dialog in any open LibreOffice module, select *Tools > Customize*.




FIGURE 10.1: CUSTOMIZATION DIALOG IN WRITER



Note: Further Information

Click *Help* for more information about the options in the *Customize* dialog.

PROCEDURE 10.2: CUSTOMIZING TOOLBARS

1. In the customization dialog, click the tab *Toolbar*.
2. From the drop-down box *Toolbar*, select the toolbar you want to customize.
3. Activate the check boxes next to the commands you want to appear on the toolbar, and deactivate the check boxes next to the commands you do not want to appear. A short description for each command is shown at the bottom of the dialog.

4. With *Save In*, select whether to save your customized toolbar in the current LibreOffice module or in the current document. If you decide to save it in the LibreOffice module, the customized toolbar is used whenever you open that module. If you decide to save it together with the current document, the customized toolbar is used whenever you open that document.
5. Repeat to customize additional toolbars.
6. Click *OK*.

To switch back to the original settings again, open the customization dialog, click the *Toolbar* drop-down box and select *Restore Default Settings*. Click *Yes* and *Reset* to proceed.

PROCEDURE 10.3: SHOWING OR HIDING BUTTONS IN THE TOOLBAR

1. Click the arrow icon at the right edge of the toolbar you want to change.
2. Click *Visible Buttons* to display a list of buttons.
3. Select the buttons in the list to enable (check) or disable (uncheck) them.

PROCEDURE 10.4: CUSTOMIZING MENUS

You can add or delete items from current menus, reorganize menus, and even create new menus.

1. Click *Tools > Customize > Menus*.
2. Select the menu you want to change, or click *New* to create a new menu.
3. Modify, add, or delete menu items as desired.
4. Click *OK*.

PROCEDURE 10.5: CUSTOMIZING KEY COMBINATIONS

You can reassign currently assigned key combinations and assign new ones to frequently used functions.

1. Click *Tools > Customize > Keyboard*.
2. Select the keys you want to assign to a combination.
3. Select a *Category* and an appropriate *function*.
4. Click *Modify* to assign the function to the key or *Delete* to remove an existing assignment.
5. Click *OK*.

PROCEDURE 10.6: CUSTOMIZING EVENTS

LibreOffice also provides ways to assign macros to events such as application start-up or the saving of a document. The assigned macro runs automatically whenever the selected event occurs.

1. Click *Tools > Customize > Events*.
2. Select the event you want to change.
3. Assign or remove macros for the selected event.
4. Click *OK*.

10.7 Changing the Global Settings

Global settings can be changed in any LibreOffice module by clicking *Tools > Options* on the menu bar. This opens the window shown in the figure below. A tree structure is used to display categories of settings.

The screenshot shows the 'Options' dialog box in LibreOffice. On the left is a tree view with the following categories: LibreOffice, User Data (selected), General, Memory, View, Print, Paths, Colors, Fonts, Security, Personalization, Application Colors, Accessibility, Advanced, Basic IDE Options, OpenCL, Load/Save, Language Settings, LibreOffice Writer, LibreOffice Writer/Web, LibreOffice Base, Charts, and Internet. The right pane is titled 'Address' and contains the following fields: Company (single line), First/last name/initials (three separate lines), Street (single line), City/state/zip (three separate lines), Country/region (single line), Title/position (two separate lines), Telephone (home/work) (two separate lines), and Fax/e-mail (two separate lines). At the bottom of the right pane is a checked checkbox labeled 'Use data for document properties'. At the bottom of the dialog are three buttons: Help, OK, and Cancel. A Reset button is also present at the bottom right.

FIGURE 10.2: THE OPTIONS WINDOW

The settings categories that appear depend on the module you are working in. For example, if you are in Writer, the LibreOffice Writer category appears in the list, but the LibreOffice Calc category does not. The LibreOffice Base category appears in both Calc and Writer. The Module column in the table shows where each setting category is available.

The following table lists the settings categories along with a brief description of each category:

TABLE 10.2: GLOBAL SETTING CATEGORIES

Settings Category	Description	Module
<i>LibreOffice</i>	Basic settings, including your user data (such as your address and e-mail), important paths, and settings for printers and external programs.	All
<i>Load/Save</i>	Settings related to the opening and saving of several file types. There is a dialog for general settings and several special dialogs to define how external formats should be handled.	All
<i>Language Settings</i>	Settings related to languages and writing aids, such as your locale and spell checker settings. This is also the place to enable support for Asian languages.	All
<i>LibreOffice Writer</i>	Settings related to word processing, such as the basic units, fonts and layout that Writer should use.	Writer
<i>LibreOffice Writer/ Web</i>	Settings related to the HTML authoring features of LibreOffice.	Writer
<i>LibreOffice Calc</i>	Settings related to spreadsheets, such as spreadsheet appearance, Microsoft Excel compatibility options, and calculation options.	Calc
<i>LibreOffice Impress</i>	Settings related to presentations, such as enabling the smartphone remote control and the grid of the page to use.	Impress

Settings Category	Description	Module
<i>LibreOffice Draw</i>	Settings related to drawings, such as the grid of the page to use.	Draw
<i>LibreOffice Base</i>	Allows setting and editing database connections and registered databases.	Base
<i>Charts</i>	Allows defining the default colors used for newly created charts.	All
<i>Internet</i>	Allows configuring a proxy and the e-mail software to use.	All



Important: Settings Apply Globally

All settings listed in the table apply *globally* for the specified modules. That means, they are used as defaults for every new document you create.

10.8 Using Templates

A template is a document containing only the styles—and content—that you want to appear in every document of that type. When a document is created or opened with the template, the styles are automatically applied to that document. Templates greatly enhance the use of LibreOffice by simplifying formatting tasks for a variety of different types of documents.

For example, in a word processor, you can write letters, memos, and reports, all of which look different and require different styles. Or, for example, for spreadsheets, you could use different cell styles or headings for certain types of spreadsheets. If you use templates for each of your document types, the styles you need for each document are always readily available.

LibreOffice comes with a set of predefined templates. You can also find additional templates on the Internet, for example at <http://templates.libreoffice.org>⁷. For details, see *Section 10.10, “For More Information”*.

Creating your own templates requires some planning. You need to determine how you want the document to look, so you can create the styles you need in that template.

A detailed explanation of templates is beyond the scope of this section. *Procedure 10.7, “Creating LibreOffice Templates”* only shows how to generate a template from an existing document.

PROCEDURE 10.7: CREATING LIBREOFFICE TEMPLATES

For text documents, spreadsheets, presentations, and drawings, you can create a template from an existing document as follows:

1. Start LibreOffice and open or create a document that contains the styles and content that you want to re-use for other documents of that type.
2. Click *File > Templates > Save as Template*.
3. Choose a directory to save the image in by double-clicking one of the directory icons. If you are in a subdirectory and want to go up again, use the path bar displayed above the directories.
4. From the toolbar, choose *Save*.
5. Specify a name for the template.
6. Click *OK*.



Note: Converting Microsoft Word Templates

You can convert Microsoft Word templates like you would convert any other Word document. For more information, see *Section 10.4.2, “Converting Documents to the OpenDocument Format”*.

10.9 Setting Metadata and Properties

When exchanging documents with other people, it is sometimes useful to store metadata like the owner of the file, who it was received from, and a URL. LibreOffice lets you attach such metadata to the file. This helps you track metadata which you do not want to or cannot save in the content of the file. This feature is also the basis for later sorting, searching and retrieving your documents based on metadata.

As an example, we assume you want to set these properties to your file:

- A title, subject, and some keywords
- The owner of the file
- Who sent you the file

To attach such metadata to your document, proceed as follows:

PROCEDURE 10.8: SETTING PROPERTIES

1. Click *File > Properties*. A dialog opens. It has, among others, the following tabs:
2. Change to the *Description* tab and insert title, subject, and your keywords.
3. Switch to the *Custom Properties* tab.
4. To add a row for a property, click *Add*.
5. In the *Name* column, click the drop-down box for the entry. A list of properties appears, from it, choose *Owner*.
6. Insert the name of the owner in the *Value* column.
7. Repeat from *Step 4* but as the name of the property, this time, choose *Received from*.
Optionally, repeat from *Step 4* for more properties.
To remove a property, click the red icon at the end of the corresponding row.
8. Leave the dialog with *OK*.
9. Save the file.

10.10 For More Information

LibreOffice contains extensive online help. In addition, a large community of users and developers support it. The following list shows some places where you can go for additional information.

LibreOffice Application Help (*Help > LibreOffice Help*)

Extensive help on performing any task in LibreOffice.

<https://www.libreoffice.org> 

Home page of LibreOffice

<https://ask.libreoffice.org> ↗

Official question and answer page for LibreOffice.

<http://www.taming-libreoffice.com/> ↗

Taming LibreOffice: books, news, tips and tricks.

<http://www.pitonyak.org/oo.php> ↗

Extensive information about creating and using macros.

<http://extensions.libreoffice.org/> ↗

Extension and template directory for LibreOffice.

<https://www.worldlabel.com/Pages/openoffice-template.htm> ↗

Templates for creating labels with LibreOffice.

11 LibreOffice Writer

LibreOffice Writer is a full-featured word processor with page and text formatting capabilities. Its interface is similar to interfaces of other major word processors, and it includes some features that are usually found only in desktop publishing applications.

This chapter highlights a few key features of Writer. For more information about these features and for complete instructions for using Writer, look at the LibreOffice help or at the sources listed in [Section 10.10, “For More Information”](#).

Much of the information in this chapter can also be applied to other LibreOffice modules. For example, other modules use styles similarly to how they are used in Writer.

11.1 Creating a New Document

There are multiple ways to create a new Writer document:

- **From Scratch.** To create a new empty document, click *File > New > Text Document*.
- **Using a Wizard.** To use a standard format and predefined elements for your own documents, use a wizard. Click *File > Wizards > Letter* and follow the steps.
- **From a Template.** To use a template, click *File > New > Templates* and open, for example, *Business Correspondence*. From the list of text document templates, select the one that fits your needs.

For example, to create a business letter, click *File > Wizards > Letter*. Using the wizard, you can easily create a basic document using a standard format. A sample wizard dialog is shown in [Figure 11.1](#).




FIGURE 11.1: A LIBREOFFICE WIZARD

Enter text in the document window as desired. Use the tools for applying and changing styles or the tools for direct formatting to adjust the appearance of the document. Use the *File* menu or the relevant buttons in the toolbar to print and save your document. With the options under *Insert*, add extra items to your document, such as a table, picture, or chart.

11.2 Formatting with Styles

The traditional way of formatting office documents is direct formatting. That means, you use a button, such as *Bold*, which sets a certain property (in this case, a bold typeface). With styles, you can bundle a set of properties (for example, font size and font weight) and give them a speaking name, such as *Headline, first level*. Using styles, rather than direct formatting has the following advantages:

- Gives your pages, paragraphs, texts, and lists a consistent look.
- Makes it easy to consistently change formatting later.
- Allows reuse and import of styles from another document.
- Change one style and its properties are passed on to its descendants.

EXAMPLE 11.1: USE OF STYLES

Imagine that you emphasize text by selecting it and clicking the button *Bold*. Later, you decide you want the emphasized text to be italicized. Now, without styles, you need to find all bold text and manually change it to italics.

If you had used a character style from the beginning, however, you would only need to change the style from bold to italics once. All text formatted with a style changes its appearance as the style is changed.

LibreOffice can use styles for applying consistent formatting to various elements in a document. The following types of styles are available in Writer:

TABLE 11.1: TYPES OF STYLES

Type of Style	Function
<i>Paragraph</i>	Applies standardized formatting to the various types of paragraphs in your document. For example, apply a paragraph style to a first-level heading to set the font and font size, spacing above and below the heading, location of the heading, and other formatting specifications.
<i>Character</i>	Applies standardized formatting for types of text. For example, if you want emphasized text to appear in italics, you can create an emphasis style that italicizes selected text when you apply the style to it.
<i>Frame</i>	<p>Applies standardized formatting to frames. For example, if your document uses marginal notes, you can create frames with specified borders, location, and other formatting, so that all of your marginal notes have a consistent appearance.</p> <p>Frames are also used for captioning images: A frame can keep the caption and the image together. Here, you can use frame style to make sure that all your images have the same size and background color, for example.</p>
<i>Page</i>	Applies standardized formatting to a specified type of page. For example, if every page of your document contains a header and footer except for the first page, you can use a first page style that

Type of Style	Function
	disables headers and footers. You can also use different page styles for left and right pages so that you have bigger margins on the insides of pages and your page numbers appear on an outside corner.
<i>List</i>	Applies standardized formatting to specified list types. For example, you can define a checklist with square check boxes and a bullet list with round bullets, then easily apply the correct style when creating your lists.

Direct formatting overrides any styles you have applied. For example, format a piece of text both with a character style and using the button *Bold*. Now, the text will be bold, no matter what is set in the style.

To remove all direct formatting, first select the appropriate text, then right-click it and choose *Clear Direct Formatting*.

Likewise, if you manually format paragraphs using *Format > Paragraph*, you can end up with inconsistent paragraph formatting. This is especially true if you copy and paste paragraphs from other documents with different formatting. However, if you apply paragraph styles, formatting remains consistent. If you change a style, the change is automatically applied to all paragraphs formatted with that style.

11.2.1 The Side Bar Panel *Styles and Formatting*

The side bar panel *Styles and Formatting* is a versatile formatting tool for applying styles to text, paragraphs, pages, frames, and lists. To open this panel, click *Styles > Styles and Formatting*, click the button *Styles and Formatting* (a T) in the side bar or press F11.




FIGURE 11.2: **STYLES AND FORMATTING PANEL**

LibreOffice comes with several predefined styles. You can use these styles as they are, modify them, or create new styles. Use the icons at the top of the panel to display formatting styles for the most common elements such as paragraphs, frames, pages or lists. To learn more about styles, continue with the instructions below.

11.2.2 Applying a Style

To apply a style, select the element you want to apply the style to, and double-click the style in the panel *Styles and Formatting*. For example, to apply a style to a paragraph, place the cursor anywhere in that paragraph and double-click the desired paragraph style.

Alternatively, use the paragraph style selector in the toolbar *Formatting*.

11.2.3 Changing a Style

By changing styles, you can change formatting throughout a document, rather than applying the change separately everywhere you want to apply the new formatting.

To change an existing style, proceed as follows:

1. In the panel *Styles and Formatting*, right-click the style you want to change.
2. Click *Modify*.
3. Change the settings for the selected style.
For information about the available settings, refer to the LibreOffice online help.
4. Click *OK* or *Apply*.

11.2.4 Creating a Style

LibreOffice comes with a collection of styles to suit many needs of most users. However, if you need a style that does not yet exist and want to create your own style, follow the procedure below:

PROCEDURE 11.1: CREATING A NEW STYLE

1. Open the panel *Styles and Formatting* with *Styles > Styles and Formatting*, or pressing **F11**.
2. Make sure you are in the list of styles for the type of style you want to create.
For example, if you are creating a character style, make sure you are in the character style list by clicking the corresponding icon in the panel *Styles and Formatting*.
3. Right-click anywhere in the list of styles in the panel *Styles and Formatting*.
4. To open the style dialog, click *New*. The *Organizer* tab is preselected.
5. Configure three basic properties of the new style:

Name

The name of your style. Choose any name you like.

Next Style

The style that follows your style. The style selected here is used when starting a new paragraph by pressing **Enter**. This is useful, for example, for headlines, after which you usually want to start a normal paragraph of text.

Inherit From

A style that your style depends on. If the selected style is changed, your style changes as well. For example, to make headers consistent, create a “parent” header style and have subsequent headers depend on it. This is useful when you only want to change the properties that need to be different.

For details about the style options available in any tab, click the *Help* button of the dialog.

6. Confirm with *OK*. This closes the window.

11.2.4.1 Example: Defining a Note Style

Let us assume, you need a note with a different background and borders. To create such a style, proceed as follows:

PROCEDURE 11.2: CREATING A NOTE STYLE

1. Press **F11**. The panel *Styles and Formatting* opens.
2. Make sure you are in the *Paragraph Style* list by checking that the pilcrow icon (¶) is selected.
3. Right-click anywhere in the list of styles in the panel *Styles and Formatting* and select *New*.
4. Specify the following parameters in the tab *Organizer*:

<i>Name</i>	Note
<i>Next Style</i>	Note
<i>Inherit from</i>	- None -
<i>Category</i>	Custom Styles

5. Change the indentation in the tab *Indents & Spacing*, using the text field *Before Text*. If you also want more space above and below individual paragraphs, change the values in the *Above paragraph* and *Below paragraph* accordingly.
6. Switch to the tab *Background* and choose a color for the background.
7. Switch to the tab *Borders* and determine your line arrangements, line style, color and other parameters.

8. Confirm with *OK*. This closes the window.
9. Select your text in your document and double-click the style *Note*. Your style parameters are applied to the text.

11.2.4.2 Example: Defining an Even-Odd Page Style

If you want to create double-sided printouts of your documents, especially if they are supposed to be bound, use templates for even and odd pages. To create page styles for this, proceed as follows:

PROCEDURE 11.3: CREATE AN EVEN (LEFT) PAGE STYLE

1. Press **F11**. The panel *Styles and Formatting* opens.
2. Make sure you are in the list *Page Style* by checking that the paper sheet icon is selected.
3. Right-click anywhere in the list of styles in the panel *Styles and Formatting* and select *New*.
4. Enter the following parameters in the tab *Organizer*:

<i>Name</i>	Left Content Page
<i>Next Style</i>	Leave empty, will be changed later
<i>Inherit from</i>	not applicable
<i>Category</i>	not applicable

5. Change additional parameters as you like in the other tabs. You can also adapt the page format and margins (tab *Page*) or any headers and footers.
6. Confirm with *OK*. This closes the window.

PROCEDURE 11.4: CREATE AN ODD (RIGHT) PAGE STYLE

1. Follow the instruction in *Procedure 11.3, "Create an Even (Left) Page Style"* but use the string Right Content Page in the *Organizer* tab.
2. Select the entry *Left Content Page* from the drop-down box *Next Style*.
3. Choose the same parameters as you did for the left page style. If you used different sizes for the left and right margin of your even page, mirror these values in your odd pages.

4. Confirm with *OK*. This closes the window.

Then connect the left page style with the right page style:

PROCEDURE 11.5: CONNECT THE RIGHT PAGE STYLE WITH THE LEFT PAGE STYLE

1. Right-click the entry *Left Content Page* and choose *Modify*.
2. Choose *Right Content Page* from the drop-down box *Next Style*.
3. Confirm with *OK*. This closes the window.

To attach your style, make sure your page is a left (even) page and double-click *Left Content Page*. Whenever your text exceeds the length of a page, the following page automatically receives the alternative page style.

11.3 Working with Large Documents

You can use Writer to work on large documents. Large documents can be either a single file or a collection of files assembled into a single document.

11.3.1 Navigating in Large Documents

The Navigator tool displays information about the contents of a document. It also lets you quickly jump to different elements. For example, use the Navigator to get a quick overview of all images included in a document.

To open the Navigator, click *View > Navigator* or press **F5**. The elements listed in the Navigator vary with the document loaded in Writer.

The Navigator is also an element of the side bar: There, it can be opened using the button *Navigator* (a compass).

Double-click an item in the Navigator to jump to that item in the document.




FIGURE 11.3: NAVIGATOR TOOL IN WRITER

11.3.2 Using Master Documents

If you are working with a very large document, such as a book, it can be easier to manage the book with a master document, rather than keeping the book in a single file. A master document enables you to quickly apply formatting changes to a large document or to jump to each subdocument for editing.

A master document is a Writer document that serves as a container for multiple Writer files. You can maintain chapters or other subdocuments as individual files collected in the master document. Master documents are also useful if multiple users are working on a single document. You can separate each user's section of the document into subdocuments collected in a master document, allowing multiple writers to work on their subdocuments at the same time without fear of overwriting the work of others.

PROCEDURE 11.6: CREATING A MASTER DOCUMENT

1. Click *New > Master Document*.
- or

Open an existing document and click *File > Send > Create Master Document*.

2. The *Navigator* window will open. In it, select *Insert* (📎), then choose *File*.
3. Select a file to add an existing file to the master document.

PROCEDURE 11.7: ADDING A NEW DOCUMENT TO A MASTER DOCUMENT

1. In the window or panel *Navigator*, choose *Insert* (📎), then select *New Document*.
2. A file chooser opens, to allow saving the new document. Specify a name, then click *Save*.
3. When you are done editing the new document, save it. Then switch back to the master document.
4. Update the master document with the contents of the new document. To do so, right-click the entry of your new document in the *Navigator*, then click *Update > Selection*.

To enter some text directly into the master document, select *Insert > Text*.

The LibreOffice help files contain more complete information about working with master documents. Look for the topic named *Using Master Documents and Subdocuments*.



Tip: Styles and Templates in Master Documents

The styles from all of your subdocuments are imported into the master document. To ensure that formatting is consistent throughout your master document, use the same template for each subdocument. Doing so is not mandatory.

However, if subdocuments are formatted differently, you might need to do some reformatting to successfully bring subdocuments into the master document without creating inconsistencies. For example, if two documents within a master document include styles with the same name, the master document will use the formatting specified for the style in the document imported first.

11.4 Using Writer as an HTML Editor

In addition to being a full-featured word processor, Writer also functions as an HTML editor. You can style HTML pages like any other document, but there are specific *HTML Styles* that help with creating good HTML. You can view the document as it will appear online, or you can directly edit the HTML code.

PROCEDURE 11.8: CREATING AN HTML PAGE

1. Click *File* > *New* > *HTML Document*.
2. Press **F11** to open the panel *Styles and Formatting*.
3. At the bottom of the panel *Styles and Formatting*, click the drop-down box to open it.
4. Select *HTML Styles*.
5. Create your HTML page, using the styles to tag your text.
6. Click *File* > *Save As*.
7. Select the location where you want to save your file and name the file. Make sure that in the bottom drop-down box, *HTML Document* is selected.
8. Click *OK*.

To edit HTML code directly or to see the HTML code created when you edit the HTML file as a Writer document, click *View* > *HTML Source*. In HTML Source mode, the *Formatting and Styles* list is not available.

The first time you switch to *HTML Source* mode, you are prompted to save the file as HTML, if you have not already done so.

To switch back from *HTML Source* mode to Web Layout, click *View* > *HTML source* again.

12 LibreOffice Calc

Calc is the LibreOffice spreadsheet module. Spreadsheets consist of several sheets, containing cells which can be filled with elements like text, numbers, or formulas. A formula can manipulate data from other cells to generate a value for the cell in which it is inserted. Calc also allows you to define ranges, filter and sort data and creates charts from data to present it graphically. Using pivot tables, you can combine, analyze or compare larger amounts of data.

This chapter can only introduce some very basic Calc functionality. For more information and for complete instructions, see the LibreOffice application help and the sources listed in [Section 10.10, “For More Information”](#).



Note: VBA Macros

Calc can process many VBA macros in Excel documents. However, support for VBA macros is not complete. When opening an Excel spreadsheet that makes heavy use of macros, you might discover that some do not work.

12.1 Creating a New Document

There are two ways to create a new Calc document:

- **From Scratch.** To create a new empty document, click *File > New > Spreadsheet*.
- **From a Template.** To use a template, click *File > New > Templates* and open, for example, *Finances*. From the list of spreadsheet templates, select the one that fits your needs.

Access the individual sheets by clicking their respective tabs at the bottom of the window.

Enter data in the cells as desired. To adjust the appearance, either use the *Formatting* toolbar or side bar panel, or use the *Format* menu—or define styles as described in [Section 12.2, “Using Formatting and Styles in Calc”](#). Use the *File* menu or the relevant buttons in the toolbar to print and save your document.

12.2 Using Formatting and Styles in Calc

Calc comes with a few built-in cell and page styles to improve the appearance of your spreadsheets and reports. Although these built-in styles are adequate for many uses, you will probably find it useful to create styles for your own frequently used formatting preferences.

PROCEDURE 12.1: CREATING A STYLE

1. Click *Format > Styles > Styles and Formatting* or press **F11**.
2. At the top of the panel *Styles and Formatting*, click either *Cell Styles* (a green cell) or *Page Styles* (a document).
3. Right-click anywhere in the list of styles in the panel *Styles and Formatting*. Then click *New*.
4. Specify a name for the style and use the various tabs to set the desired formatting options.
5. When you are done configuring the style, click *OK*.

PROCEDURE 12.2: MODIFYING A STYLE

1. Click *Format > Styles > Styles and Formatting*.
2. At the top of the panel *Styles and Formatting*, click either *Cell Styles* (a green cell) or *Page Styles* (a document).
3. Right-click the name of the style you want to change, then click *Modify*.
4. Change the desired formatting options.
5. When you are done configuring the style, click *OK*.

To apply a style to specific cells, select the cells you want to format. Then double-click the style you want to apply in the *Styles and Formatting* window.

12.3 Working With Sheets

Sheets are a good method to organize your calculations. For example, if you have a business, accounting might be much clearer if you create a sheet for each month.

To insert a new sheet after the last sheet, click the button **+** next to the sheet tabs.

To insert one or more new sheets into your spreadsheet from a file or at a specific position at once, do the following:

PROCEDURE 12.3: INSERTING NEW SHEETS

1. Right-click a sheet tab and select *Insert Sheet*. A dialog opens.
2. Decide whether the new sheet should be positioned before or after the selected sheet.
3. To create a new sheet, make sure the *New Sheet* radio button is activated. Enter the number of sheets and the sheet name. Skip the rest of this step.

Alternatively, to import a sheet from another file, do the following:

- a. Select *From file* and click *Browse*.
 - b. Select the file name and confirm with *OK*. All the sheet names are now displayed in the list.
 - c. Select the sheet names you want to import by holding the **Shift** key and clicking them.
4. To add the sheet or sheets, confirm with *OK*.

To rename a sheet, right-click the tab of the sheet and select *Rename Sheet*. Alternatively, you can also double-click the sheet tab.

To delete one or multiple sheets, do the following: Select the sheet you want to delete. To select more than one sheet, hold down **Shift** while making the selection. Then right-click the tab of the sheet, choose *Delete Sheet* and confirm with *Yes*.

12.4 Conditional Formatting

Conditional formatting is a useful feature to highlight certain values in your spreadsheet. For example, define a condition and if the condition is true, a style is applied to each cell that fulfills this condition.



Note: Enable AutoCalculate

Before you apply conditional formatting, choose *Tools > Cell Contents > AutoCalculate*. You should see a check mark in front of *AutoCalculate*.

PROCEDURE 12.4: USING CONDITIONAL FORMATTING

1. Define a style first. This style is applied to each cell when your condition is true. Use *Format > Styles and Formatting* or press **F11**. For more information, see *Procedure 12.1, "Creating a Style"*. Confirm with **OK**.
2. Select the cell range where you want to apply your condition.
3. Select *Format > Conditional Formatting > Condition* from the menu. A dialog opens.
4. You now see a template for a new condition. Conditions can operate in multiple modes:

Cell value is

The condition tests if a cell matches a certain value. Next to the first drop-down box, select an operator such as *equal to*, *less than*, or *greater than*.

Formula is

The condition tests if a certain formula returns true.

Date is

The condition tests if a certain date value is reached.

All Cells

This mode allows creating data visualizations that depend on the value of a cell, similarly to *Cell value is*. However, with *All Cells*, you can use one condition to apply an entire range of styles.

The types of styles that can be used are color scales (cell background color), data bars (bars with changing width in the cell) and icon sets (an icon in the cell).

For example, a color scale allows assigning 0 a black background and 100 a green background. All values in between are calculated automatically. For example, 50 receives a dark green background.

5. For this example, keep the default: *Cell value is*.
6. Select an operator and the value of the cell you want to test for.
7. Choose the style you want to apply when this condition is true or click *New Style* to define a new appearance.
8. If you need additional conditions, click *Add*. Then repeat the previous steps.
9. Confirm with **OK**. Now the style of your cells has changed.

12.5 Grouping and Ungrouping Cells

Grouping a cell range allows hiding parts of a spreadsheet. This makes spreadsheets more readable, as you can hide all the parts you are not currently interested in. It is possible to group rows or columns and nest groups in other groups.

To group a range, proceed as follows:

PROCEDURE 12.5: GROUPING A SELECTED CELL RANGE

1. Select a cell range in your spreadsheet.
2. Select *Data > Group and Outline > Group*. A dialog appears.
3. Decide if you want to group your selected range by rows or by columns. Confirm with *OK*.

After grouping selected cells, a line indicating the grouped cell range appears in the upper-left margin. Fold or unfold the cell range with the + and – icons. The numbers at the top left of the margins display the depth of your groups and can be clicked too.

To ungroup a cell range, click into a cell which belongs to a group and select *Data > Group and Outline > Ungroup*. The line in the margin disappears. The innermost group is always deleted first.

12.6 Freezing Rows or Columns as Headers

If you have a spreadsheet with lots of data, scrolling usually makes the header disappear. LibreOffice can lock rows or columns or both, so they remain fixed as you scroll around.

To freeze a single row or a single column, proceed as follows:

PROCEDURE 12.6: FREEZING A SINGLE ROW OR COLUMN

1. To create a frozen area before a row, click the header of the row (1, 2, 3, ...).
Alternatively, to create a frozen area above a column, click the header of the column (A, B, C, ...).
2. Select *View > Freeze Rows and Columns*. A dark line appears, indicating the frozen area.

It is also possible to freeze both rows and columns:

PROCEDURE 12.7: FREEZING ROW AND COLUMN

1. Click into the cell to the right of the column and below the row you want frozen. For example, if your header occupies the space from A1 to B3, click cell C4.

2. Select *View > Freeze Rows and Columns*. A dark line appears, indicating which area is frozen.

To unfreeze, select *View > Freeze Rows and Columns*. The check mark before the menu item disappears.

13 LibreOffice Impress, Base, Draw, and Math

Besides LibreOffice Writer and LibreOffice Calc, LibreOffice also includes the modules Impress, Base, Draw, and Math. With these you can create presentations, design databases, draw up graphics and diagrams, and create mathematical formulas.

13.1 Using Presentations with Impress

Use LibreOffice Impress to create presentations for screen display or printing. If you have used other presentation software, Impress makes it easy to switch. It works very similarly to other presentation software.

13.1.1 Creating a Presentation


There are multiple ways to create a new Impress document:

- **From Scratch.** To create a new empty document, click *File > New > Presentation*.
- **Using a Wizard.** To use a standard format and predefined elements for your documents use a wizard. Click *File > Wizards > Presentation* and follow the steps.
- **From a Template.** To use a template, click *File > New > Templates* and open, for example, *Presentation Backgrounds*. From the list of presentation templates, select the one that fits your needs.

The following procedure describes how to create a presentation by using the wizard. Proceed as follows:

PROCEDURE 13.1: CREATING A PRESENTATION USING THE WIZARD

1. Start LibreOffice.
2. Select *File > Wizards > Presentation*.
3. Choose *From template*. Select *Presentation Backgrounds* from the pop-up menu to set your preferred background and click *Next*.



4. Select an output medium. The output medium is the form the final presentation will take, such as: *Overhead sheet*, *Paper*, a slideshow on a 4:3 *Screen* or a 16:9 *Widescreen*, among other choices.

To see a thumbnail showing your choices, make sure *Preview* is activated. If all options are set according to your wishes, click *Next*.

5. To use effects for slide transitions, select an *Effect* and its *Speed*. The effect will be pre-viewed immediately.
6. Either use the default presentation type or choose *Automatic* to specify the amount of time each page displays and the length of the pause between presentations.
7. If all options are set according to your wishes, click *Create*.

The presentation opens, ready for editing.

13.1.2 Using Master Pages

Master pages give your presentation a consistent look by defining what fonts and other design elements are used. Impress uses two types of master pages:

Slide Master

Contains elements that appear on all slides. For example, you might want your company logo to appear in the same place on every slide. The slide master also determines the text formatting style for the heading and outline of every slide that uses that master page, as well as any information you want to appear in a header or footer.

Notes Master

Determines the formatting and appearance of the notes in your presentation.

13.1.2.1 Creating a Slide Master

Impress comes with a collection of preformatted master pages. To customize presentations further, create your own slide masters.

1. Start Impress with an existing presentation or create a new one as described in [Section 13.1.1, "Creating a Presentation"](#).
2. Click *View > Slide Master*.
This opens the current slide master in *Master View*. The *Master View* toolbar appears.
3. Right-click the left-hand panel, then click *New Master*.
4. Edit the slide master until it has the desired look.
Master view allows editing outline styles by directly formatting the sample text on the slide.
5. To finish editing slide masters, in the *Master View* toolbar, click *Close Master View*. Alternatively, choose *View > Normal*.



Tip: Collect Slide Masters in a Template

When you have created all of the slide masters you want to use in your presentations, you can save them in an Impress template. Then, any time you want to create presentations that use those slide masters, open a new presentation with your template.

13.1.2.2 Applying a Slide Master

Slide masters can be applied to selected slides or to all slides of a presentation.

1. Open your presentation.
2. (Optional) To apply a slide master to multiple slides but not all slides: Select the slides that you want a slide master applied to.
To select multiple slides, press **Ctrl** in the *Slides Pane* while clicking the slides you want to use.
3. In the *Tasks* pane, open the *Master Pages* and click the master page you want to apply. The slide master is applied to the corresponding page or pages.
If you do not see the *Task Pane*, click *View > Task Pane*.

13.2 Using Databases with Base

LibreOffice includes the database module Base. Use Base to design a database to store many kinds of information. From a simple address book or recipe file to a sophisticated document management system.

Tables, forms, queries, and reports can be created manually or by using convenient wizards. For example, the Table Wizard contains several common fields for business and personal use. Databases created in Base can be used as data sources, such as when creating form letters.

It is beyond the scope of this document to detail database design with Base. Find more information at the sources listed in [Section 10.10, "For More Information"](#).

13.2.1 Creating a Database Using Predefined Options

Base comes with several predefined database fields to help you create a database. A wizard guides you through the steps to create a new database. The steps in this section are specific to creating an address book using predefined fields, but it should be easy to follow them to use the predefined fields for any of the built-in database options.

The process for creating a database can be broken into several subprocesses:

1. *Creating the Database*
2. *Setting Up the Database Table*

3. Creating a Form

4. Modifying the Form

13.2.1.1 Creating the Database

1. Start LibreOffice Base.

The *Database Wizard* starts.

You can choose between creating an HSQLDB or Firebird database.

HSQLDB Embedded (*default*)

This database format is also available in older versions of OpenOffice.org and LibreOffice. It depends on Java being installed on the computer.

Firebird Embedded

This database format can only be used in newer versions of LibreOffice. It does not depend on Java. When you do large database operations, Firebird can perform better.

2. Proceed with *Next*.
3. Click *Yes, register the database for me* to make your database information available to other LibreOffice modules and select the check boxes to *Open the database for editing* and *Create tables using the table wizard*. Then click *Finish*.
4. Browse to the directory where you want to save the database, specify a name for the database, then click *Save*.

13.2.1.2 Setting Up the Database Table

After you have created the database, if you have selected the *Create tables using the table wizard* check box, the table wizard opens. If you have not, go to the *Task* area and click *Use Wizard to Create Table*. Next, define the fields you want to use in your database table.

In this example, set up an address database.

1. For this example, click *Personal*.
The list *Sample tables* changes to show the predefined tables for personal use where the address table template is. The table templates listed under *Business* contain predefined business tables.
2. In the *Sample tables* list, click *Addresses*.

The available fields for the predefined address book appear in the *Available fields* menu.

3. In the *Available fields* menu, click the fields you want to use in your address book.

Select one item at a time by clicking. Alternatively, to select multiple items, hold **Shift** and click each of the items separately.

4. Click the icons *single right arrow* and *single left arrow* to move selected items to or off the *Selected fields* list.

To move all available fields to the *Selected fields* menu, click the icon *double right arrow*.

5. Use the icons *up arrow* and *down arrow* to adjust the order of the selected entries, then click *Next*.

The fields appear in the table and forms in the order in which they are listed.

Steps

1. Select fields
2. Set types and formats
3. Set primary key
4. Create table

Select fields for your table

This wizard helps you to create a table for your database. After selecting a table category and a sample table, choose the fields you want to include in your table. You can include fields from more than one sample table.

Category
☐ Business ☒ Personal

Sample tables
Addresses

Available fields
Notes
Photo
Title
Hobbies
Nickname
SendCard
AddressID
Birthdate

Selected fields
City
Address
LastName
PostalCode
CountryOrRegion

Help < Back Next > Finish Cancel

6. Make sure each of the fields is defined correctly.

You can change the field name, type, maximum characters and whether it is a required field. For this example, leave the settings as they are, then click *Next*.

7. Make sure that *Create a primary key* and *Automatically add a primary key* are activated. Additionally activate *Auto value*.

Proceed with *Next*.

8. Give the table a name, and activate *Create a form based on this table*.

Proceed with *Finish*.

13.2.1.3 Creating a Form

Next, create the form to use when entering data into your address book.

After the previous step, you should be in the *Form Wizard* already. Otherwise, open it by going to the main window. Under *Tables*, right-click the correct table. Click *Form Wizard*.

1. In the *Form Wizard*, click the double right-arrow icon to move all available fields to the *Fields in the form* list, then click *Next*.
2. To add a subform, activate *Add Subform*, then click *Next*.
For this example, accept the default selections.
3. Select how you want to arrange your form, then click *Next*.
4. Select *The form is to display all data* and leave all of the check boxes deactivated, then click *Next*.
5. Apply a style and field border, then click *Next*.
For this example, accept the default selections.
6. Name the form, activate *Modify the form*, then click *Finish*.

13.2.1.4 Modifying the Form

After the form has been defined, you can modify the appearance of the form to suit your preferences.

After the previous step, you should be in the *Database Form* editor already. If not, select the right form by clicking *Forms* in the side bar of the main window. Then, in the *Forms* area, right-click the correct form. Select *Edit*.

1. Arrange the fields on the form by dragging them to their new locations.
For example, move the field *First Name*, so it appears to the right of the field *Last Name*.
2. When you have finished modifying the form, save it and close it.

13.2.1.5 Further Steps

After you have created your database tables and forms, you are ready to enter your data. You can also design queries and reports to help sort and display the data.

Refer to LibreOffice online help and other sources listed in [Section 10.10, “For More Information”](#) for additional information about Base.

13.3 Creating Graphics with Draw

Use LibreOffice Draw to create graphics and diagrams. You can export your drawings to the most common vector graphics formats and import them into any application that lets you import graphics, including other LibreOffice modules. You can also create Adobe* Flash* (SWF) versions of your drawings.

PROCEDURE 13.2: CREATING A GRAPHIC

1. Start LibreOffice Draw.
2. Use the toolbar *Drawing* at the right side of the window to create a graphic. To create a new shape or text object, use the shape buttons of the toolbar:
 - To create a single shape or text object, click a shape button once. Then click and drag over the document to create an object.
 - To create a multiple shape or text object, double-click a shape button. Then click and drag over the document to create objects. When you are done, click the mouse pointer icon in the toolbar.
3. Save the graphic.

To embed an existing Draw graphic into a LibreOffice document, select *Insert > Object > OLE Object*. Select *Create from file* and click *Search* to navigate to the Draw file to insert.

To be able to edit the graphic later on its own, activate *Link to file*.

If you insert a file as OLE object, you can edit the object later by double-clicking it.

PROCEDURE 13.3: OPENING DRAW FROM OTHER LIBREOFFICE MODULES

One particularly useful feature of Draw is the ability to open it from other LibreOffice modules, so you can create a drawing that is automatically imported into your document.

1. From a LibreOffice module (for example, from Writer), click *Insert > Object > OLE Object > LibreOffice Drawing > OK*.

The user interface of Writer will now be replaced by that of Draw.

2. Create your drawing.
3. Click in your document, outside the Draw frame.
The drawing is automatically inserted into your document.

13.4 Creating Mathematical Formulas with Math

It is usually difficult to include complex mathematical formulas in your documents. To make this task easier, the LibreOffice Math equation editor lets you create formulas using operators, functions, and formatting assistants. You can then save those formulas as an object that can be imported into other documents. Math functions can be inserted into other LibreOffice documents like any other graphic object.



Note: Math is For Creating Mathematical Formulas

Math is not a calculator. The functions it creates are graphical objects. Even if they are imported into Calc, these functions cannot be evaluated.

To create a formula, proceed as follows:

1. Start LibreOffice Math.
2. Click *File > New > Formula*. The formula window opens.
3. Enter your formula in the lower part of the window. For example, the binomial theorem in LibreOffice Math syntax is:

$$(a + b)^2 = a^2 + 2 a b + b^2$$

The result is displayed in the upper part of the window.

4. Use the side bar panel *Formula Elements* or right-click the lower part of the window to insert other terms. If you need symbols, use *Tools > Symbols* to, for example, insert Greek or other special characters.
5. Save the document.

The result is shown in *Figure 13.1, “Mathematical Formula in LibreOffice Math”*:




FIGURE 13.1: MATHEMATICAL FORMULA IN LIBREOFFICE MATH

It is possible to include your formula in Writer, for example. To do so, proceed as follows:

1. Create a new Writer document or open an already existing one.
2. Select *Insert > Object > OLE Object* in the main menu. The *Insert OLE Object* window appears.
3. Select *Create from file*.
4. Click *Search* to locate your formula. To choose the formula file, click *Open*.
To be able to edit the formula later on its own, activate *Link to file*.
5. Confirm with *OK*. The formula is inserted at the current cursor position.

IV Internet, Communication and Collaboration

- 14 Firefox: Browsing the Web 114
- 15 Evolution: E-Mailing and Calendaring 132
- 16 Empathy: Instant Messaging 147
- 17 Ekiga: Using Voice over IP 150

14 Firefox: Browsing the Web

The Mozilla Firefox Web browser is included with SUSE® Linux Enterprise Server. With features like tabbed browsing, pop-up window blocking and download management, Firefox combines the latest browsing and security technologies with an easy-to-use interface. Firefox gives you easy access to different search engines to help you find the information you need.

14.1 Starting Firefox

To start Firefox, select *Applications > Internet > Firefox*.

14.2 Navigating Web Sites

The look and feel of Firefox is similar to that of other browsers. It is shown in *Figure 14.1, "The Browser Window of Firefox"*. At the top of the window you find the location bar for a Web address, and the search bar. Bookmarks are also available for quick access from the bookmarks toolbar. For more information about the various Firefox features, use the *Help* menu in the menu bar.



Note: Using the Menu Bar

While most functions of Firefox are available through the three-lines button (≡), some are only available from the menu bar.

The menu bar of Firefox is hidden by default. To temporarily show it, press **Alt**. It will then be displayed until you click elsewhere in the Firefox window.

To permanently enable the Firefox menu bar, first press **Alt**, then choose *View > Toolbars* and activate *Menu Bar*.




FIGURE 14.1: THE BROWSER WINDOW OF FIREFOX

14.2.1 The Location Bar

When typing into the location bar, an auto-completion drop-down box opens. It shows all previous location addresses and bookmarks containing the characters you type. The matching phrase is highlighted in bold. Entries visited most frequently and recently are listed first.

List entries from the bookmark list are marked with a star. Bookmarks with tags are marked with an additional label followed by the tag names. List entries from the browsing history are not marked. To search in your bookmarks only, type `*` as the first character of your search.

Use `↑` and `↓` or the mouse wheel to navigate the list. Press `Enter` or click an entry to go to the selected page. `Del` removes an entry from the list if it is an entry from the history. Bookmarked entries can only be removed by deleting the associated bookmark.

14.2.2 Zooming

Firefox offers two zooming options: page zoom, the default, and text zoom. Page zoom enlarges the entire page as is, with all elements of a page, including graphics, expanding equally while text zoom only changes the text size.

To toggle between page and text zoom, from the menu bar, choose *View > Zoom > Zoom Text Only*. To zoom in or out either use the mouse wheel while holding the **Ctrl** key, or use **Ctrl**+**+** and **Ctrl**+**-**. Reset the zoom factor with **Ctrl**+**0**.

14.2.3 Tabbed Browsing

Tabbed browsing allows you to load multiple Web sites in a single window. To switch between pages in use, use the tabs at the top of the window. If you often use more than one Web page at a time, tabbed browsing makes it easier to switch between pages.

Opening Tabs

To open a new tab, from the menu bar, select *File > New Tab* or press **Ctrl**+**T**. This opens an empty tab in the Firefox window. To open a link on a Web page or a bookmark in a tab, middle-click it. Alternatively, right-click a link and select *Open Link in New Tab*. You may also open an address in the location bar in a new tab with a middle-click or by pressing **Ctrl**+**Enter**.

Closing Tabs

Right-click a tab to open a context menu, giving you access to tab managing options such as closing, reloading, or bookmarking. To close a tab, you may also use **Ctrl**+**W** or click the close button. Any closed tab can be restored by choosing from the menu bar, *History > Recently Closed Tabs*. To reopen the last closed tab, either choose *Undo Close Tab* from the context menu or press **Ctrl**+**Shift**+**T**.

Sorting Tabs

By default, tabs are sorted in the order you opened them. Rearrange the tab order by dragging and dropping a tab to the desired position. If you have opened a large number of tabs, they cannot all be displayed in the tab bar at the same time. Use the arrows at the ends of the bar to move left or right-click the down arrow at the right end of the tab bar to get a list of all tabs.

Dragging and Dropping

Drag and drop also works with tabs. Drag a link onto an existing tab to open it in that tab or drag and drop a link on an empty space in the tab bar to open a new tab. Drag and drop a tab outside of the tab bar to open it in a new browser window.

14.2.4 Using the Sidebar

Use the left side of your browser window for viewing bookmarks or browsing history. Extensions may add new ways to use the sidebar as well. To display the sidebar, from the menu bar, select *View > Sidebar* and select the desired contents.

14.3 Finding Information

There are two ways to find information in Firefox: to search the Internet with a search engine, use the search bar. To search the page currently displayed, use the find bar.

14.3.1 Finding Information on the Web

Firefox has a search bar that can access different engines like Google, Yahoo, or Amazon. For example, if you want to find information about SUSE using the current engine, click in the search bar, type SUSE, and press . The results appear in your window.

To choose a different search engine, type your search term, then click one of the search provider icons at the bottom of the appearing pop-up.

14.3.1.1 Customizing the Search Bar

If you want to change the order, add, or delete a search engine, proceed as follows.

1. Click the icon to the left of the search bar.
2. From the pop-up, select *Change Search Settings*. The *Search* dialog shows the engine that is currently set as default search engine and other available search engines.
3. To change the order of entries, use the mouse to drag them.
To delete an entry, select it and click *Remove*.

To add a search engine, click *Add More Search Engines*. Firefox displays a Web page with available search plug-ins. To install a search plug-in, select it and click *Add to Firefox*.




FIGURE 14.2: FIREFOX—MANAGE SEARCH ENGINES

Some Web sites offer search engines that you can add directly to the search bar. Whenever you are visiting such a Web site, the icon to the left of the search bar gains a + sign. Click the icon and select *Add*.

14.3.1.2 Adding Keywords to Your Online Searches

Firefox lets you define own *keywords*: abbreviations to use as a URL shortcut for a particular search engine. If you have defined ws as a keyword for the Wikipedia search for example, you can type ws SEARCHTERM into the location bar to search Wikipedia for SEARCHTERM.

To assign a shortcut for a search engine from the search bar, click the icon to the left of the search bar and select *Change Search Settings*. Select a search engine, double-click its *Keyword* column, enter a keyword and press **Enter**.

It is also possible to define a keyword for any search field on a Web site. Proceed as follows:

1. Right-click the search field and choose *Add a Keyword for this Search* from the menu that opens. The *Add Bookmark* dialog appears.
2. In *Name*, enter a descriptive name for this keyword.

3. Enter your *Keyword* for this search.
4. Save this keyword.



Tip: Keywords for Regular Web Sites

Using keywords is not restricted to search engines. You can also add a keyword to a bookmark (via the bookmark's properties). For example, if you assign suse to the SUSE home page bookmark, you can open it by typing suse into the location bar.

14.3.2 Searching in the Current Page

To search inside a Web page, in the menu bar, click *Edit > Find* or press **Ctrl-F**. The find bar opens. It is usually displayed at the bottom of a window. Type your query in the text box. Firefox finds the first occurrence of this phrase as you type. You can find other occurrences of the phrase by pressing **F3** or the *Next* button in the find bar. Clicking the *Highlight All* button will highlight all occurrences of the phrase. Checking the *Match Case* option makes the query case-sensitive. Firefox also offers two quick-find options. Click anywhere you like to start a search on a Web page, type the key **/** immediately followed by the search term. The first occurrence of the search term will be highlighted as you type. Use **F3** to find the next occurrence. It is also possible to limit quick-find to links only. This search option is available by typing the key **l**.

14.4 Managing Bookmarks

Bookmarks offer a convenient way of saving links to your favorite Web sites. Firefox not only makes it very easy to add new bookmarks with just one mouse click, it also offers multiple ways to manage large bookmark collections. You can sort bookmarks into folders, classify them with tags, or filter them with smart bookmark folders.

Add a bookmark by clicking the star in the location bar. The star will turn blue to indicate the page was bookmarked. The bookmark will be saved in the *Unsorted Bookmarks* folder under the page title. To change the name and folder of your bookmark or add tags, after bookmarking, click the star again. This will open a pop-up where you can make your changes.

To bookmark all open tabs, right-click in a tab and choose *Bookmark All Tabs*. Firefox asks you to create a new folder for the tab links.

To remove a bookmark, open the bookmarked location. Then, click the star and click *Remove Bookmark*.

14.4.1 Organizing Bookmarks

The *Library* can be used to manage the properties (name and address location) for each bookmark and organize the bookmarks into folders and sections. It resembles *Figure 14.3, “The Firefox Bookmark Library”*.




FIGURE 14.3: THE FIREFOX BOOKMARK LIBRARY

To open the *Library*, in the menu bar, click *Bookmarks > Show All Bookmarks*. The library window is split into two parts: the left pane shows the folder tree view, the right pane the subfolders and bookmarks of the selected folder. Use *Views* to customize the right pane. The left pane contains three main folders:

History

Contains your complete browsing history. You cannot alter this list other than by deleting entries from it.

Tags

Lists bookmarks for each tag you have specified. See *Section 14.4.2, “Tags”* for more information on tags.

All Bookmarks

This category contains the three main bookmark folders:

Bookmarks Toolbar

Contains the bookmarks and folders displayed beneath the location bar. See [Section 14.4.6, “The Bookmarks Toolbar”](#) for more information.

Bookmarks Menu

Holds the bookmarks and folder accessible via the *Bookmarks* entry in the main menu or the bookmarks side menu.

Unsorted Bookmarks

Contains all bookmarks created with a single click the star in the location bar. This folder is only visible in the library and the bookmarks sidebar.

Organize your bookmarks using the right pane. Choose actions for folders or bookmarks either from the context menu that opens when you right-click an item or from the *Organize* menu. The properties of a chosen folder or bookmark can be edited in the bottom part of the right pane. By default, only *Name*, *Location*, and *Tags* are displayed for a bookmark. Click the arrow next to *More* to gain access to all properties.

To rearrange your bookmarks, use the mouse to drag them. You can use this to move a bookmark or a folder to a different folder, or to change the order of bookmarks in a folder.

14.4.2 Tags

Tags offer a convenient way to file a bookmark under several categories. You can tag a bookmark with as many terms as you want. For example, to access all sites tagged with suse, enter suse into the location bar. For each tag, an item is automatically created in the Recent Tags folder of the library. Drag and drop an item for a tag onto the bookmark toolbar to easily access it.

To add tags to a bookmark, open the bookmark in Firefox and click the yellow star in the location bar. The *Edit This Bookmark* dialog opens where you can add a comma separated list of tags. It is also possible to add tags via the bookmark's properties dialog which you can open in the library or by right-clicking a bookmark in the menu or the toolbar.

14.4.3 Importing and Exporting Bookmarks

To import bookmarks from another browser or from a file in HTML format, open the library by choosing from the menu bar, *Bookmarks > Show All Bookmarks*. To start the Import Wizard, click *Import and Backup > Import Bookmarks from HTML* and choose an import location. Start the import by clicking *Next*. Imports from an HTML file are imported as is.

Exporting bookmarks is also done via *Import and Backup* in the library window. To save your bookmarks as an HTML file, choose *Export Bookmarks to HTML*. To create a backup of your bookmarks, choose *Backup*. Firefox uses a JavaScript Object Notation file format (.json) for backups.

To restore a bookmark backup, click *Import and Backup > Restore*. Then locate the backup you want to restore from.

14.4.4 Live Bookmarks

Live Bookmarks display headlines in your bookmark menu and keep you up to date with the latest news. This enables you to save time with one glance at your favorite sites. Live bookmarks update automatically. Many sites and blogs support this format.

To create a Live Bookmark, look for orange buttons on Web sites that either read RSS or consist of a dot and three nested quarter circles. Click the icon. Usually, that will lead you to a page where all the headlines of the page are displayed. On that page, choose *Subscribe Now*. A dialog opens in which to select the name and location of your live bookmark. Confirm with *Add*. This page also lets you choose alternative applications to subscribe with, such as *My Yahoo*.

14.4.5 Smart Bookmark Folders

Smart bookmark folders are virtual bookmark folders that are dynamically updated. There are three smart bookmark folders: The *Most Visited* links are available from your bookmarks toolbar. *Recently Bookmarked* links and *Recent Tags* are located in the bookmarks menu.

14.4.6 The Bookmarks Toolbar

The Bookmarks Toolbar is displayed beneath the location bar and lets you quickly access bookmarks. You can also add, organize, and edit bookmarks directly. By default, the Bookmarks Toolbar is populated with a predefined set of bookmarks organized into several folders (see [Figure 14.1, “The Browser Window of Firefox”](#)).

To manage the Bookmarks Toolbar you can use the library as described in [Section 14.4.1, “Organizing Bookmarks”](#). Its content is located in the folder *Bookmarks Toolbar*. It is also possible to manage the toolbar directly. To add a folder, bookmark, or separator, right-click an empty space in the toolbar and select the appropriate entry from the pop-up menu. To add the current page to the bar, click the icon of the Web page in the location bar and drag it to the desired position on the bookmarks toolbar. Hovering over an existing bookmark folder will automatically open it, enabling you to place the bookmark within this folder.

To manage a certain folder or bookmark, right-click it. A menu opens which lets you *Delete* it or change its *Properties*. To move or copy an entry, choose *Cut* or *Copy* and *Paste* it to the desired position.

14.5 Using the Download Manager

Keep track of your current and past downloads with the download manager. To start the download manager, in the menu bar, click *Tools > Downloads*. While downloading a file, a progress bar indicates the download status. If necessary, pause the download and resume it later. To open a downloaded file with the associated application, click *Open*. To open the location to which the file was saved, choose *Open Containing Folder*. *Remove From History* only deletes the entry from the download manager, however, it does not delete the file from the hard disk.

By default, all files are downloaded to ~/Downloads. To change this behavior, in the menu bar, click *Edit > Preferences*. Go to *General*. Under *Downloads*, either choose another location or *Always ask me where to save files*.



Tip: Resuming Downloads

If your browser crashes or is closed while downloading, all pending downloads will automatically be resumed in the background when starting Firefox the next time. A download that was paused before the browser was closed can manually be resumed via the download manager.

14.6 Security

Since browsing the Internet has become more risky, Firefox offers various measures to make browsing safer. It automatically checks whether you are trying to access a site known to contain harmful software (malware) or a site known to steal sensitive data (phishing) and stops you from entering these sites. The Instant Web Site ID lets you easily check a site's legitimacy, and a password manager and the pop-up blocker offer additional security. With Private Browsing, you can surf the Internet without Firefox recording data on your computer.

14.6.1 Instant Web Site ID

Firefox allows you to check the identity of a Web page with a single glance. The icon in the location bar next to the address indicates which identity information is available and whether communication is encrypted:

Gray Globe

The site does not provide any identity information and communication between Web server and browser is not encrypted. Do not exchange sensitive information with such sites.

Gray Triangle

This site is from a domain that has been verified by a certificate, so you can be sure that you are really connected to the very site it claims to be. However, the site tried to load additional elements, such as images or scripts over an insecure connection. Firefox has blocked these items. Therefore, the page can look broken.

Gray Padlock

This site is from a domain that has been verified by a certificate, so you can be sure that you are really connected to the very site it claims to be. Communication with a “gray-padlock” site is always encrypted.

Green Padlock

This site completely identifies itself by a certificate that ensures a site is owned by the person or organization it claims to be. This is especially important when exchanging very sensitive data (for example when doing money transactions over the Internet). In this case you can be sure to be on the Web site of your bank when it sends complete identity information. Communication with a “green-padlock” server is always encrypted.

To view detailed identity information, click the icon of the Web site in the location bar. In the opening pop-up, click *More Information* to open the *Page Info* window. Here, you can view the site's certificate, the encryption level, and information about stored passwords and cookies.

With the *Permissions* view you can set per-site permissions for image loading, pop-ups, cookies and installation permissions. The *Media* view lists all images, background graphics and embedded objects from a site and displays further information on each item together with a preview. It also lets you save individual items.




FIGURE 14.4: THE FIREFOX PAGE INFO WINDOW

14.6.2 Importing Certificates

Firefox comes with a certificate store for identifying certificate authorities (CA). Using these certificates enables the browser to automatically verify certificates issued by Web sites. If a Web site issues a certificate that has not been signed by one of the CAs from the certificate store, it is not trusted. This ensures that no spoofed certificates are accepted.

Large organizations usually use their own certificate authorities in-house and distribute the respective certificates via the system-wide certificate store located at `/etc/pki/nssdb`. To configure Firefox (and other Mozilla tools, such as Thunderbird) to use this system-wide CA store in addition to its own, export the `NSS_USE_SHARED_DB` variable. For example, you can add the following line to `~/.bashrc`:

```
export NSS_USE_SHARED_DB=1
```

Alternatively or additionally you can manually import certificates. To do so, in the menu bar, open the *Preferences* dialog by clicking *Edit > Preferences*. Select *Advanced > Certificates > View Certificates > Your Certificates > Import* and select the certificate to import. Only import certificates you absolutely trust!

14.6.3 Password Management

Each time you enter a user name and a password on a Web site, Firefox offers to store this data. A pop-up at the top of the page opens, asking you whether you want Firefox to remember the password. If you accept by clicking *Remember*, the password will be stored on your hard disk in an encrypted format. The next time you access this site, Firefox will automatically fill in the login data.

To review or manage your passwords, open the password manager by clicking *Edit > Preferences > Security > Saved Passwords* in the menu bar. The password manager opens with a list of sites and their corresponding user names. By default, the passwords are not displayed. You can click *Show Passwords* to display them. To delete single or all entries from the list, click *Remove* or *Remove All*, respectively.

To protect your passwords from unauthorized access, you can set a master password that is required when managing or adding passwords. In the menu bar, click *Edit > Preferences*, choose the category *Security* and activate *Use a Master Password*.

14.6.4 Private Browsing

By default, Firefox keeps track of your browsing history by storing content and links of visited Web sites, cookies, downloads, passwords, search terms and formula data. Collecting and storing this data makes browsing faster and more convenient. However, when you use a public terminal or a friend's computer, for example, you could turn this behavior off. In Private Browsing mode Firefox will not keep track of your browsing history nor will it cache the content of pages you have visited.

To enable the Private Browsing mode, in the menu bar, click *File > New Private Window*. The current Web site and all open tabs will be replaced by the Private Browsing information screen. As long as you will browse in private mode, the string (Private Browsing) will be displayed in the titlebar of the window.

Disable Private Browsing by closing the private window.

To make Private Browsing the default mode, open the *Privacy* tab in the Preference window as described in [Section 14.7.1, “Preferences”](#), set the option *Firefox will:* to *Use custom settings for history* and then choose *Always use private browsing mode*.



Warning: Bookmarks and Downloads

Downloads and bookmarks you made during Private Browsing mode will be kept.

14.7 Customizing Firefox

Firefox can be customized extensively.

- Change the way Firefox behaves by altering its preferences.
- Add functionality by installing extensions.
- Change the look and feel by installing themes.

To manage extensions, themes and plug-ins, Firefox has an add-on manager.

14.7.1 Preferences

Firefox offers a wide range of configuration options. These are available by choosing *Edit > Preferences* in the menu bar. Each option is described in detail in the online help, which can be accessed by clicking the question mark icon in the dialog.




FIGURE 14.5: THE PREFERENCES WINDOW

14.7.1.1 Session management

By default, Firefox automatically restores your session—windows and tabs—only after it has crashed, or after a restart because of an extension. However, it can be configured to restore a session every time it is started: Open the Preferences dialog as described in [Section 14.7.1, “Preferences”](#) and go to the category *General*. Set the option *When Firefox Starts:* to *Show My Windows and Tabs from Last Time*.

When you have multiple windows open they will only be restored the next time when you close all of them at once with *File > Quit* (from the menu bar) or with `Ctrl-Q`. If you close the windows one by one, only the last window will be restored.

14.7.1.2 Language Preferences for Web Sites

When sending a request to a Web server, the browser always sends the information about which language is preferred by the user. Web sites that are available in more than one language (and are configured to evaluate this language parameter) will display their pages in the language the browser requests. On SUSE Linux Enterprise Server, the preferred language is preconfigured to

use the same language as the desktop. To change this setting, open the *Preferences* window as described in [Section 14.7.1, “Preferences”](#), go to the category *Content* and *Choose* your preferred language.

14.7.1.3 Spell Checking

By default, Firefox spell-checks what you type when typing into multiple-line text boxes. Misspelled words are underlined in red. To correct a word, right-click it and select the correct spelling from the context menu. You may also add the word to the dictionary, if it is correct.

To change or add a dictionary, right-click anywhere in a multi-line text box and select the appropriate option from the context menu. Here you may also disable spell-checking for this text box. If you want to globally disable spell checking, open the *Preferences* window as described in [Section 14.7.1, “Preferences”](#) and go to the category *Advanced*. Deactivate *Check My Spelling As I Type*.

14.7.2 Add-ons

Extensions let you personalize Firefox to fit your needs. With extensions, you can change the look and feel of Firefox, enhance existing functionality, and add functions. For example, extensions can enhance the download manager, show the weather, or control Web music players. Other extensions assist Web developers or increase security by blocking content such as ads or scripts. There are thousands of extensions available for Firefox. With the add-ons manager, you can install, enable, disable, update, and remove extensions.

If you do not like the standard look and feel of Firefox, install a new *theme*. Themes do not change the functionality, only the appearance of the browser.

14.7.2.1 Installing Add-ons

To add an extension or theme, start the add-ons manager with *Tools > Add-Ons* from the menu bar. It opens on the *Get Add-Ons* tab either displaying a choice of recommended add-ons or the results of your last search.

Use the *Search All Add-Ons* field to search for specific add-ons. Click an entry in the list to view a short description. Install the add-on by clicking *Install* or open a Web page with detailed information by clicking the *More* link.




FIGURE 14.6: INSTALLING FIREFOX EXTENSIONS

To activate freshly installed extensions or themes, Firefox sometimes needs to be restarted by clicking *Restart now* in the add-ons manager. Restart this way to make sure that your browsing session will be restored.

14.7.2.2 Managing Add-ons

The Add-ons Manager also offers a convenient interface to manage extensions, themes, and plug-ins. *Extensions* can be enabled, disabled or uninstalled. If an extension is configurable, its configuration options can be accessed via the *Preferences* button. In the *Appearance* tab you may *Uninstall* a theme, or activate a different theme by clicking *Enable*. Pending extension and theme installations are also listed. Select *Cancel* to stop the installation. Although you cannot install *Plug-Ins* as a user, you may disable or enable them with the Add-ons manager.

Some add-ons require you to restart the browser when you uninstall or disable them. In such cases, after clicking either of these actions, a *Restart now* link appears in the add-ons manager.

14.8 Printing from Firefox

Before you actually print a Web page, you can use the print preview function to control how the printed page will look like. From the menu bar, choose *File > Print Preview*. Configure paper size and orientation per printer with *Page Setup*.

To print a Web page either choose, from the menu bar, *File > Print* or press **Ctrl-P**. The *Printer* dialog opens. To print with the default options click *Print*.

The Printer dialog also offers extensive configuration options to fine-tune the printout. On the *General* tab, choose a printer, the range to print, the number of copies and the order. *Page Setup* lets you specify the number of pages per side, the scaling factor, and paper source and type. If the printer supports it, you can also activate double-sided printing here. Control how frames, backgrounds, header and footer are printed on the *Options* tab.

14.9 For More Information

To get more information about Firefox see the following links:

Mozilla forums: <https://www.mozilla.org/about/forums/> ↗

Main Menu reference: <http://support.mozilla.org/kb/Menu+reference> ↗

Preferences reference: <http://support.mozilla.org/kb/Options+window> ↗

Keyboard shortcuts: <http://support.mozilla.org/kb/Keyboard+shortcuts> ↗

15 Evolution: E-Mailing and Calendaring

Evolution makes storing, organizing, and retrieving your personal information easy, so you can work and communicate more effectively with others. It is a professional groupware program and an important part of the Internet-connected desktop.

Evolution can help you work in a group by handling e-mail, contact information, and one or more calendars. It can do that on one or several computers, connected directly or over a network, for one person or for large groups.

Evolution helps you accomplish common daily tasks quickly. For example, you can easily reuse appointment or contact information sent to you by e-mail, or send e-mails to a contact or appointment. If you receive lots of e-mail, you can use advanced features like search folders, which let you save searches as though they were ordinary e-mail folders.

This chapter introduces you to Evolution and helps you get started. For more details, refer to the Evolution application help.

15.1 Starting Evolution

To start Evolution, click *Applications > Internet > Evolution*.

15.2 Setup Assistant

The first time you start Evolution, it opens an assistant to help you set up e-mail accounts and import data from other applications.

The *Evolution Account Assistant* helps you provide all the required information.

15.2.1 Restoring from a Backup File

When the assistant starts, the *Welcome* page is displayed. Proceed to the *Restore from Backup* page. If you previously backed up your Evolution configuration and want to restore it, activate the restoration option and select the backup file in the file chooser dialog.

Otherwise, proceed to *Identity*.

15.2.2 Defining Your Identity

The *Identity* page is the next step in the assistant.

1. Type your full name in the *Full Name* field.
2. Type your e-mail address in the *E-mail Address* field.
3. *(Optional)* (Optional) Type an address in the *Reply-To* field.
Only use this field if you want replies to e-mails from you to be sent to a different e-mail address.
4. *(Optional)* (Optional) Type your organization name in the *Organization* field.
This is the company where you work, or the organization you represent when you send e-mails.
5. Proceed to the next page.

15.2.3 Receiving Mail

The *Receiving E-mail* page lets you determine the server that you want to use to receive e-mail. You need to specify the type of server you want to receive mail from. If you are not sure about the type of server, contact your system administrator or e-mail provider.

Select a server type in the *Server Type* list. The following is a list of available server types:

Exchange Web Services: Allows you to connect to newer Microsoft Exchange servers to synchronize e-mail, calendar, and contact information. This is only available if you have installed the connector for Microsoft* Exchange* which is packaged in evolution-ews .

IMAP+: Keeps the e-mail on your server, so you can access your e-mail from multiple systems.

POP: Downloads your e-mail to your hard disk for permanent storage, freeing up space on the e-mail server.

USENET News: Connects to a news server and downloads a list of available news digests.

Local Delivery: If you want to move e-mail from the spool and store it in your home directory, you need to provide the path to the mail spool you want to use. If you want to leave mail in your system's spool files, select *Standard Unix Mbox Spool File* instead.

MH Format Mail Directories: To download your e-mail using mh or an mh-style program, you need to provide the path to the mail directory you want to use.

Maildir Format Mail Directories: If you download your e-mail using Qmail or another Maildir-style program, select this option. You need to provide the path to the mail directory you want to use.

Standard Unix Mbox Spool File or Directory: To read and store e-mail in the mail spool on your local system, select this option. You need to provide the path to the mail spool you want to use.

None: If you do not plan to check e-mail with this account, select this option. There are no configuration options.

15.2.3.1 Configuration Options for IMAP+, POP, and USENET

If you selected IMAP + , POP, or USENET News as the server type, you need to specify additional information.

If you are not sure about the correct server address, user name or security setting, contact your system administrator or e-mail provider.

1. Type the host name of your e-mail server into the text box *Server*.
2. Type your user name for the account into the text box *Username*.
3. Choose a security setting supported by your mail server. For security reasons, avoid using *No Encryption*.
4. Select your authentication type in the *Authentication* list. To have Evolution check for supported authentication types, click *Check for Supported Types*. Then choose one of the options without a strikeout.
Some servers do not announce the authentication mechanisms they support. Therefore clicking this button is not a guarantee that the shown mechanisms actually work.
5. Proceed to the next page.

15.2.3.2 Configuration Options for Exchange Web Services

If you selected Exchange Web Services as the server type, you need to specify additional information.

If you are not sure about the correct server address, user name or security setting, contact your system administrator or e-mail provider.

1. Type your user name for the account into the text box *Username*.

2. Type the EWS URL of your e-mail server into the text box *Host URL*.
If available, type the address of an Offline Address Book into the text box *OAB URL*.
If your login name and the name of your mailbox differ, select *Open Mailbox of other user*.
Then type the mailbox name into the text box below.
3. Select an authentication type in the *Authentication* list. To have Evolution check for supported authentication types, click *Check for Supported Types*. Then choose one of the options without a strikeout.
Some servers do not announce the authentication mechanisms they support. Therefore clicking this button is not a guarantee that the shown mechanisms actually work.
4. Proceed to the next page.

15.2.3.3 Local Configuration Options

If you selected *Local Delivery*, *MH-Format Mail Directories*, *Maildir-Format Mail Directories*, or *Standard Unix Mbox Spool File or Directory*, specify the path to the local files or directories in the path field.

15.2.4 Receiving Options

After you have selected a mail delivery mechanism, you can set some preferences for its behavior.

15.2.4.1 IMAP+ Receiving Options

If you selected IMAP+ as the receiving server type, you will now see a page of options to specify the behavior of Evolution.

1. You can choose from the following options:

Check for new messages every ... minutes

Select if you want Evolution to automatically check for new mail. Set how often to check.

Check for new message in all folders

Select if you want to check for new messages in all folders.

Check for new message in subscribed folders

Select if you want to check for new messages in subscribed folders.

Use Quick Resync if the server supports it

Select to use Quick Resync which makes browsing mail faster on supported servers.

Listen for server change notifications

Select if you want Evolution to listen for change notifications. If you activate this option, Evolution will show you mail as it arrives. Therefore, you can usually deactivate *Check for new messages every ... minutes*.

Show only subscribed folders

Select if you want Evolution to show only subscribed folders.

You can unsubscribe from folders to cut down on the number of irrelevant folders shown in Evolution and to reduce the amount of mail that is downloaded.

Apply filters to new messages in all folders

Select if you want to apply filters to new messages, and whether to do so in all folders or only in the Inbox folder.

Check new messages for Junk contents

Select if you want to check new messages for junk content, and whether to do so in all folders or only in the Inbox folder.

Automatically synchronize remote mail locally

Select this to download all your mail, so you can read it offline.

2. Proceed to the next page.

15.2.4.2 POP Receiving Options

If you selected POP as the receiving server type, you will now see a page of options to specify the behavior of Evolution.

1. You can choose from the following options:

Check for new messages every ... minutes

Select if you want Evolution to automatically check for new mail. Set how often to check.

Leave messages on server

Select if you want leave your mail on the server or delete it on the server when you download it to your computer. You can also set a period of time for which the messages will be kept on the server after they were downloaded.

Disable support for all POP3 extensions

Disabling POP3 extensions can help with old or misconfigured servers. Select if you have trouble receiving mail.

2. Proceed to the next page.

15.2.4.3 USENET News Receiving Options

If you selected USENET News as the receiving server type, you will now see a page of options to specify the behavior of Evolution.

1. You can choose from the following options:

Check for new messages every ... minutes

Select if you want Evolution to automatically check for new mail. Set how often to check.

Apply filters to new messages in all folders

Select if you want to apply filters to new messages.

Show folders in short notations

Abbreviate folder names, for example, comp.os.linux appears as c.o.linux.

In the subscription dialog, show relative folder names

Display only the name of the folder. For example, the folder evolution.mail would appear as evolution.

2. Proceed to the next page.

15.2.4.4 Exchange Web Services Receiving Options

If you selected Exchange Web Services as the receiving server type, you will now see a page of options to specify the behavior of Evolution.

1. You can choose from the following options:

Check for new messages every ... minutes

Select if you want Evolution to automatically check for new mail. Set how often to check.

Check for new message in all folders

Select if you want to check for new messages in all folders.

Listen for server change notifications

Select if you want Evolution to listen for change notifications. If you activate this option, Evolution will show you mail as it arrives. Therefore, you can usually deactivate *Check for new messages every ... minutes*.

Apply filters to new messages in all folders

Select if you want to apply filters to new messages.

Check new messages for Junk contents

Select if you want to check new messages for junk content, and whether to do so in all folders or only in the Inbox folder.

Automatically synchronize remote mail locally

Select this to download all your mail, so you can read it offline.

Connection timeout (in seconds)

Set maximum time to wait for an answer from the server.

Cache offline address book

If you provided an OAB URL in the prior step, you can select caching an address book. This will make the address book available when offline.

2. Proceed to the next page.

15.2.4.5 Local Delivery Receiving Options

If you selected that you want to receive mail through Local Delivery, you will now see a page of options to specify the behavior of Evolution.

1. Select *Check for new messages every ... minutes* if you want Evolution to automatically check for new mail. Set how often to check.

2. Proceed to the next page.

15.2.4.6 MH-Format Mail Directories Receiving Options

If you selected that you want to receive mail through MH-Format Mail Directories, you will now see a page of options to specify the behavior of Evolution.

1. Select *Check for new messages every ... minutes* if you want Evolution to automatically check for new mail. Set how often to check.
Select *Use the .folders summary file* to use the `.folders` summary file.
2. Proceed to the next page.

15.2.4.7 Maildir-Format Mail Directories Receiving Options

If you selected that you want to receive mail through Maildir-Format Mail Directories, you will now see a page of options to specify the behavior of Evolution.

1. Select *Check for new messages every ... minutes* if you want Evolution to automatically check for new mail. Set how often to check.
Select *Apply filters to new messages in Inbox* if you want to apply filters to new messages.
2. Proceed to the next page.

15.2.4.8 Standard Unix Mbox Spool or Directory Receiving Options

If you selected that you want to receive mail through a Unix mbox Spool File or Directories, you will now see a page of options to specify the behavior of Evolution.

1. Select *Check for new messages every ... minutes* if you want Evolution to automatically check for new mail. Set how often to check.
Select *Apply filters to new messages in Inbox* if you want to apply filters to new messages.
2. Select *Store status headers in Elm/Pine/Mutt format* to store status headers in a way compatible with Elm, Pine, and Mutt.
3. Proceed to the next page.

15.2.5 Sending Mail

Now that you have entered information about how you plan to receive mail, Evolution needs to know about how you want to send it. Usually, a separate server configuration is necessary for this. Otherwise, this page will be skipped.

Select a server type from the *Server Type* list.

The following server types are available:

Sendmail: Uses the Sendmail program to send mail from your system. Sendmail is more flexible, but is not as easy to configure, so you should select this option only if you know how to set up a Sendmail service.

SMTP: Sends mail using a separate mail server. This is the most common choice for sending mail. If you choose SMTP, there are additional configuration options.

PROCEDURE 15.1: SMTP CONFIGURATION

1. Type the host address in the *Server* field.

If you are not sure what your host address is, contact your system administrator or e-mail provider.

2. Select if your server requires authentication.

If you selected that your server requires authentication, you need to provide the following information:

- a. Choose a security setting supported by your mail server. For security reasons, avoid using *No Encryption*.
- b. Select your authentication type in the *Authentication* list.
or
Click *Check for Supported Types* to have Evolution check for supported types. Then choose one of the options without a strikeout.
Some servers do not announce the authentication mechanisms they support. Therefore, clicking this button is not a guarantee that the shown mechanisms actually work.
- c. Type your user name in the *Username* field.

3. Proceed to the next page.

15.2.6 Final Steps

Now that you have finished the e-mail configuration process, you need to give the account a name. The name can be any name you prefer. Type your account name on the *Name* field. Proceed to the next page and confirm your changes.

Depending on your configuration, you may now be asked for your e-mail passwords and whether you want to save them or want to always enter them when starting Evolution.

The Evolution main window will then open for the first time.

15.3 Using Evolution

Now that the first-run configuration has finished, you are ready to begin using Evolution. This section sums up the most important parts of the user interface.




FIGURE 15.1: EVOLUTION WINDOW

Menu Bar

The menu bar gives you access to nearly all of the features of Evolution.

Folder List

The folder list gives you a list of the available folders for each account. To see the contents of a folder, click the folder name. The contents are displayed in the e-mail list.

Toolbar

The toolbar gives you fast and easy access to the frequently used features in each component.

Search Bar

The search bar lets you search for e-mails. You can filter e-mails, contacts, and calendar entries and tasks using different criteria: a label, a search term, and an account or folder. The Search bar can also save frequently used searches to a search folder.

Message List

The message list displays a list of e-mails that you have received. To view an e-mail in the preview pane, select the e-mail.

Shortcut Bar

The shortcut bar at the left lets you switch between folders and program components.

Statusbar

The statusbar periodically displays a message, or informs you about the progress of a task, such as sending e-mail.

On the far left, you will find the Online/Offline indicator. Click the Online/Offline indicator to switch between being using Evolution in online or offline mode.

Preview Pane

The preview pane displays the contents of the e-mails that are selected in the e-mail list.

15.3.1 The Menu Bar

The menu bar's contents always provide all the possible actions for any view of your data.

File: Anything related to a file or to the operations of the application usually falls under this menu, such as creating things, saving them to disk, printing them, and quitting the program itself.

Edit: Contains tools to edit text and most configuration options.

View: Allows configuring the appearance of Evolution.

Message: Contains actions that can be applied to a message.

Folder: Contains actions that can be performed on folders.

Search: Lets you search for messages, or phrases within a message. You can also see previous searches you have made.

Help: Opens the Evolution application help.

15.3.2 The Shortcut Bar

The shortcut bar is the column on the left side of the main window. At the top, there is a list of folders for the selected Evolution component. The buttons at the bottom are shortcuts to the individual components, such as Mail and Contacts.

The folder list organizes your e-mail, calendars, contact lists, and task lists in a tree. Most people find one to four folders at the base of the tree, depending on the component and their system configuration. Each Evolution component has at least one, called *On This Computer*, for local information. For example, the folder list for the e-mail component shows all your e-mail accounts, local folders, and search folders.

If you receive large amounts of e-mail, you need additional ways to organize it. In Evolution, you can create own e-mail folders, address books, calendars, task lists, or memo lists.

15.3.2.1 Creating a folder

To create a new folder:

1. Click *File > New > Mail Folder*.
2. Type the name of the folder in the *Folder Name* field.
3. Select the location of the new folder.
4. Click *Create*.

15.3.2.2 Folder Management

Right-click a folder or subfolder to display a menu with the following options:

Mark All Messages As Read: Marks all the messages in the folder as read.

New Folder: Creates a new folder or subfolder in the same location.

Copy Folder To: Copies the folder to a different location. When you select this item, Evolution offers a choice of locations to copy the folder to.

Move Folder To: Moves the folder to another location.

Delete: Deletes the folder and all contents.

Rename: Lets you change the name of the folder.

Refresh: Refreshes the folder.

Properties: Shows the number of total and unread messages in a folder.

You can also rearrange folders and messages by dragging and dropping them.

Any time new e-mail arrives in an e-mail folder, that folder label is displayed in bold text, along with the number of new messages in that folder.

15.3.3 Using E-Mail

The e-mail component of Evolution has the following standout features:

- It supports multiple e-mail sources from many protocols.
- It lets you guard your privacy with encryption.
- It can speedily handle large amounts of e-mail.
- Search folders allow you to come back to often-used searches.

Below is a summary of the user interface elements of the e-mail window.

Message List

The message list displays all the e-mails that you have. This includes all your read and unread messages and e-mail that is flagged to be deleted. With the *Show* drop-down box above the message you can filter the message list view using predefined and custom labels.

Preview Pane

This is where your e-mail is displayed.

If you find the preview pane too small, you can resize the pane, enlarge the whole window, or double-click the message in the message list to have it open in a new window. To change the size of a pane, drag the divider between the two panes.

As with folders, you can right-click messages in the message list and get a menu of possible actions. This includes moving or deleting them, creating filters or search folders based on them, and marking them as junk mail.

Actions related to e-mail, like *Reply* and *Forward*, appear as buttons in the toolbar and are also located in the right-click menu.

Templates

Evolution allows you to create and edit message templates that you can use at any time to send mail with the same pattern.

15.3.4 Calendaring

To begin using the calendar, click *Calendars* in the shortcut bar. By default, the calendar shows today's schedule on a ruled background. At the upper right, there is a *Tasks* list, where you can keep a list of tasks separate from your calendar appointments. Below that, there is a list for memos.

Appointment List

The appointment list displays all your scheduled appointments.

Month Pane

The month pane is a small view of a calendar month. You can also select a range of days in the month pane to display a custom range of days in the appointment list.

Tasks

Tasks are distinct from appointments because they generally do not have times associated with them. You can see a larger view of your task list by clicking *Tasks* in the shortcut bar.

Memos


Memos, like Tasks, do not have times associated with them. You can see a larger view of your Memo list by clicking *Memos* in the shortcut bar.


15.3.5 Managing Contacts

To use the contacts component, click *Contacts* in the shortcut bar. The Evolution contacts component can handle all of the functions of an address book or phone book.

It does, however, also do more than a paper book. To share your address book on a network, you can use LDAP directories. To create a new contact entry, right-click an e-mail address or double-click an empty space in the right pane. You can also search contacts using the search bar. By default, the display shows all your contacts in alphabetical order, in a card-based view. You can select other views from the *View* menu.

15.4 For More Information

Get more information about Evolution from the application help available via .

Find more information on the project home page <https://wiki.gnome.org/Apps/Evolution> .

16 Empathy: Instant Messaging

Empathy is an instant messaging (IM) client that allows you to connect to multiple accounts simultaneously. Chat live with your contacts in one tabbed interface, regardless of which IM system they use. Empathy uses Telepathy for protocol support.

Empathy supports the following instant messaging protocols: Google Talk (Jabber/XMPP), MSN, IRC, Salut, AIM, Facebook, Yahoo!, Gadu Gadu, Groupwise®, ICQ and QQ. (The supported protocols depend on installed Telepathy Connection Manager components.)

In the following, learn how to set up Empathy and how to communicate with your contacts.

16.1 Starting Empathy

To start Empathy, select *Applications > Internet > Empathy*.

16.2 Configuring Accounts

To use Empathy, you must already have an account for the messaging service you want to use. For example, to use Empathy to chat via AIM, you must first have an AIM account.

PROCEDURE 16.1: ADDING AND EDITING ACCOUNTS IN EMPATHY

1. To start Empathy, select *Applications > Internet > Empathy*.
If you start Empathy for the first time, a message appears, prompting you to configure an account.
2. Enter your account data. The *Messaging and VoIP Accounts* dialog shows the accounts that have been configured so far.
3. To add another account:
 - a. In the *Messaging and VoIP Accounts* dialog, click the plus icon.
 - b. Choose the type of account you want to configure, enter your user ID and password for the account and click *Add*. The dialog to add or modify accounts differs for each type of account, depending on what setup options are available for that account.
4. To enter or modify connection data for an account:
 - a. Select the account and click *Edit Connection Parameters > Advanced*.

- b. Enter a server name and a port to use for the connection. Specify additional parameters, such as encryption options, if necessary. If you are unsure which parameters to use, refer to your system administrator or messaging service.
- c. Click *Apply* to confirm your changes.

To go online with your account, turn the account switch on. When prompted for your password, enter it.

To disable the account, turn the switch off. If you are finished with the configuration of your accounts, close the *Messaging and VoIP Accounts* dialog.

16.3 Managing Contacts

Use the *Contact List* to manage your contacts. You can add and remove contacts and organize them in groups, so they are easy to find.

PROCEDURE 16.2: ADDING CONTACTS

1. To add a contact, click *Contacts > Add Contacts*.
2. Select the *Account* for which you want to add a contact.
3. As *Identifier*, enter the name or user ID of the person you want to add.
4. By default, *Alias* will show the same entry, but you can enter a different name or nickname for the contact person here.
As soon as you start typing into the *Identifier* text box, the dialog will also show any groups that you have already defined.
5. To add the new contact to a group, activate the respective group's check box.
6. To create a new group, type a group name into the text box next to *Add Group* and click *Add Group*.
7. Click *Add* to confirm your changes and to close the dialog.

In case the groups or the newly added contacts are not displayed in the *Contact List*, check the Empathy preferences by clicking *Preferences > General*. Activate *Show offline contacts* and *Show groups* to make all contacts and groups appear in the *Contact List*.

To remove a contact from the list, right-click the name of that contact, select *Remove* and confirm your choice.

16.4 Chatting with Friends

To chat with other participants, you need to be connected to the Internet. After a successful login, you are usually marked as *Available* in the *Contact List*, and thus visible to others. To change your status, click the drop-down box at the top of the *Contact List* and select another option.

To open a chat session, double-click a contact name in the *Contact List*. The chat screen opens. Type your message, then press to send.

If you open more than one chat session, the new session appears as a tab in the existing chat window. To see all messages of a session and to be able to write a reply, click the tab of that session. To see multiple session side by side, use the mouse to drag a tab out of the window. A second window will open.

To close a chat session, close the tab or window for it.

16.5 For More Information

This chapter explained the Empathy options you need to know about to set up Empathy and communicate with your contacts. It does not explain all features and options available. For more information, open Empathy, then click *Help*.

For updates about new features and for the latest information, refer to the home page of the project at <https://wiki.gnome.org/Apps/Empathy>.

17 Ekiga: Using Voice over IP

Ekiga is an application you can use for making phone calls via Voice over IP (VoIP), for video conferencing and for instant messaging.



Note: Ekiga May Not Be Installed

Before proceeding, make sure that the package `ekiga` is installed.

Before starting, make sure that the following requirements are met:

- Your sound card is properly configured.
- A headset or a microphone and speakers are connected to your computer.
- For dialing in to regular phone networks, a SIP account is required. SIP (*Signaling protocol for Internet Telephony*) is the protocol used to establish sessions for audio and video conferencing or call forwarding.

There are many VoIP providers all over the world. One provider is the Ekiga project itself, go to <https://ekiga.im> to learn more.

- For video conferencing: A Web cam is connected to your computer.

17.1 Starting Ekiga

Start Ekiga by clicking *Applications > Internet > Ekiga Softphone*.

17.2 Configuring Ekiga

On first start, Ekiga opens a configuration assistant that requests all data needed to configure Ekiga. Proceed as follows:

1. Click *Forward*.
2. Enter your full name (name and surname). Click *Forward*.

3. Enter your ekiga.net account data or choose not to register with <http://www.ekiga.net>. Click *Forward*.
4. Enter your Ekiga Call Out Account data or choose not to register with <http://www.ekiga.net>. Click *Forward*.
5. Set your connection type and speed. Click *Forward*.
6. Configure the audio devices to use by choosing the audio ringing, output and input device driver. In general, you can keep the *Default* setting. Click *Forward*.
7. Choose a video input device, if available. Click *Forward*.
8. Check the summary of your settings and apply them.
9. If registration fails after making changes to your configuration, restart Ekiga.

Ekiga allows you to maintain multiple accounts. To configure an additional account, proceed as follows:

1. Open *Edit > Accounts*.
2. Choose *Accounts > Add <account type>*. If you are unsure, select *Add a SIP Account*.
3. Enter the *Registrar* to which you have registered. This is usually an IP address or a host name that will be given to you by your Internet Telephony Service Provider. Enter *User*, and *Password* according to the data provided by your provider.
4. Make sure *Enable account* is activated and leave the configuration dialog with *OK*. The account is displayed in the Ekiga main window, including its *Status*, which should change to Registered.

17.3 The Ekiga User Interface

The user interface has different modes. To switch between views, use the toolbar. The first mode is *Contacts*, the second is *Dialpad* and the last one is *Call History*. Click the camera icon to open the *Call Window*. It displays images from your local Web cam (or from a remote Web cam during a call).




FIGURE 17.1: EKIGA USER INTERFACE

By default, Ekiga opens in the *Contacts* mode. This view shows you a local address book which lets you quickly open connections to often-used numbers.

Many of the functions of Ekiga are available with key combinations. [Table 17.1, “Key Combinations for Ekiga”](#) summarizes the most important ones.

TABLE 17.1: KEY COMBINATIONS FOR EKIGA

Key Combination	Description
Ctrl – 0	Initiate a call with the current number.
Esc	Hang up.
Ctrl – N	Add a contact to your address book.
Ctrl – B	Open the <i>Address Book</i> dialog.

Key Combination	Description
H	Hold the current call.
T	Transfer the current call to another party.
M	Suspend the audio stream of the current call.
P	Suspend the video stream of the current call.
Ctrl-W	Close the Ekiga user interface.
Ctrl-Q	Quit Ekiga.
Ctrl-E	Start the account manager.
Ctrl-J	Activate <i>Call Panel</i> on the main user interface.
Ctrl+	Zoom in to the picture from the Web cam.
Ctrl-	Zoom out on the picture from the Web cam.
Ctrl-0	Return to the normal size of the Web cam display.
F11	Use full screen for the Web cam.

17.4 Making a Call

After Ekiga is properly configured, making a call is easy.

1. Switch to the *Dialpad* mode.
2. Enter the SIP address of the party to call at the bottom of the window. The address should look like:
 - for direct local calls: sip:username@domainname or username@hostname
 - sip:username@domainname or userid@sipserver

3. Click *Call* or press **Ctrl**–**0** and wait for the other party to pick up the phone.
4. To end the call, click *Hang up* or press **Esc**.

If you need to tweak the sound parameters, click *Edit > Preferences*.

17.5 Answering a Call

Ekiga can receive calls in two different ways. First, it can be called directly with sip:user@host, or via SIP provider. Most SIP providers enable you to receive calls from a normal land-line to your VoIP account. Depending on the mode in which you use Ekiga, there are several ways in which you are alerted to an incoming call:

Normal Application

Incoming calls can only be received and answered if Ekiga is already started. You can hear the ring sound on your headset or your speakers. If Ekiga is not started, the call cannot be received.

Panel Applet

Normally, the Ekiga panel applet runs silently without giving any notice of its existence. This changes when a call comes in. The main window of Ekiga opens and you hear a ringing sound on your headset or speakers.

Once you have noticed an incoming call, click *Accept* to answer the call then start talking. If you do not want to accept this call, click *Reject*. It is also possible to transfer the call to another SIP address.

17.6 Using the Address Book

Ekiga can manage your SIP contacts. All of the contacts are displayed in the *Contacts* tab, shown in the main window after start-up. To add a contact or a new contact group, select *Chat > Add Contact*.

If you want to add a new group, enter the group name into the bottom text box and click *Add*. The new group is then added to the group list and preselected.

The following entries are required for a valid contact:

Name

Enter the name of your contact. This may be a full name, but you can also use a nickname here.

Address


Enter a valid SIP address for your contact.


Groups



If you have many contacts, add your own groups.

To call a contact from the address book, double-click the contact. The call is initiated immediately.

17.7 For More Information

The official home page of Ekiga is <http://www.ekiga.org/> . This site offers answers to frequently asked questions and more detailed documentation.

For information about the support of the H323 teleconferencing protocol in Linux, see <http://www.voip-info.org/wiki/view/H.323> . This is also a good starting point when searching for projects supporting VoIP.

To set up a private telephone network, you might be interested in the PBX software Asterisk <http://www.asterisk.org/> . Find information about it at <http://www.voip-info.org/wiki-Asterisk> .

V Graphics and Multimedia

- 18 GIMP: Manipulating Graphics **157**
- 19 GNOME Videos **173**
- 20 Brasero: Burning CDs and DVDs **180**

18 GIMP: Manipulating Graphics

GIMP (*the GNU Image Manipulation Program*) is a program for creating and editing raster graphics. In most aspects, its features are comparable to those of Adobe* Photoshop* and other commercial programs. Use it to resize and retouch photographs, design graphics for Web pages, create covers for your custom CDs, or almost any other graphics project. It meets the needs of both amateurs and professionals.

GIMP is an extremely complex program. Only a small range of features, tools, and menu items are discussed in this chapter. See [Section 18.8, “For More Information”](#) for ideas of where to find more information about the program.

18.1 Graphics Formats

There are two main types of digital graphics: raster and vector. GIMP is intended for working with raster graphics, which are most often used for digital photographs or scanned images.

Raster Images. A raster image is a collection of pixels: Small blocks of color that create an entire image when put together. High resolution images contain a large number of pixels. Because of this, such image files can easily become quite large. It is not possible to increase the size of a raster image without losing quality.

GIMP supports most common formats of raster graphics, like JPEG, PNG, GIF, BMP, TIFF, PSD, and more.

Vector Images. Unlike raster images, vector images do not store information about individual pixels. Instead, they use geometric primitives such as points, lines, curves, and polygons. Vector images can be scaled very easily. Depending on their content, vector image files can both be very small or very large. However, their file size is usually independent of their display size.

The disadvantage of vector images is that they are not good at representing complex images with many colors such as photographs. There are many specialized applications for vector graphics, for example Inkscape. GIMP has very limited support for vector graphics. For example, GIMP can open and rasterize vector graphics in SVG format or work with vector paths.

GIMP supports only the most common color spaces:

- RGB images with 8 bits per channel. This equals 24 bits per pixel in RGB images without an alpha channel (transparency). With an alpha channel, that equals 32 bits per pixel.
- Grayscale images with 8 bits per pixel.
- Indexed images with up to 255 colors.

Many high-end digital cameras produce image files with color depths above 8 bits per channel. If you import such an image into GIMP, you will lose some color information. GIMP also does not support a CMYK color mode for professional printing.

18.2 Starting GIMP

To start GIMP, select *Applications > Graphics > GIMP*.

18.3 User Interface Overview

By default, GIMP shows three windows. The toolbox, an empty image window with the menu bar, and a window containing several docked dialogs. The windows can be arranged on the screen as you need them. If they are no longer needed, they can also be closed. Closing the image window when it is empty quits the application.

In the default configuration, GIMP saves your window layout when you quit. Dialogs left open reappear when you next start the program.

If you want to combine all windows of GIMP, activate *Windows > Single-Window Mode*.

18.3.1 The Image Window

If there is currently no image open, the image window is empty, containing only the menu bar and the drop area, which can be used to open any file by dragging and dropping it there. Every new, opened, or scanned image appears in its own window. If there is more than one open image, each image has its own image window. There is always at least one image window open. In Single-Window Mode, all image windows are accessible from a tab bar at the top of the window.

The menu bar at the top of the window provides access to all image functions. You can also access the menu by right-clicking the image or clicking the small arrow button in the top left corner of the rulers.

The *File* menu offers the standard file operations, such as *New*, *Open*, *Save*, *Print* and *Close*. *Quit* quits the application.

With the items in the *View* menu, control the display of the image and the image window. *New View* opens a second display window of the current image. Changes made in one view are reflected in all other views of that image. Alternate views are useful for magnifying a part of an image for manipulation while seeing the complete image in another view. Adjust the magnification level of the current window with *Zoom*. When *Fit Image in Window* is selected, the image window is resized to fit the current image display exactly.

18.3.2 The Toolbox

The toolbox contains drawing tools, a color selector, and a freely configurable space for options pages. If you accidentally close the toolbox, you can reopen it by clicking *Tools > New Toolbox*.

To find out what a particular tool does, hover over its icon. At the very top, there is a drop area which can be used to open any image file by simply dragging and dropping it there.




FIGURE 18.1: THE TOOLBOX

The current foreground and background color are shown in two overlapping boxes. The default colors are black for the foreground and white for the background. Swap the foreground and background color with the bent arrow icon to the upper right of the boxes. Use the black and white icon to the lower left to reset the colors to the default. Click the box to open a color selection dialog.

Under the toolbox, a dialog shows options for the currently selected tool. If it is not visible, open it by double-clicking the icon of the tool in the toolbox.

18.3.3 Layers, Channels, Paths, Undo

Layers shows the different layers in the current image and can be used to manipulate the layers. Information is available in [Section 18.6.6, “Layers”](#).

Channels shows the color channels of the current image and can manipulate them.

Paths are a vector-based method of selecting parts of an image. They can also be used for drawing. *Paths* shows the paths available for an image and provides access to path functions. *Undo* shows a limited history of modifications made to the current image. Its use is described in [Section 18.6.5, “Undoing Mistakes”](#).

18.4 Getting Started

Although GIMP can be a bit overwhelming for new users, most quickly find it easy to use after they work out a few basics. Crucial basic functions are creating, opening, and saving images.

18.4.1 Creating a New Image

1. To create a new image, select *File > New*. This opens a dialog in which you can make settings for the new image.
2. If desired, select a predefined setting called a *Template*.



Note: Custom Templates

To create a custom template, select *Windows > Dockable Dialogs > Templates* and use the controls offered by the window that opens.

3. In the *Image Size* section, set the size of the image to create in pixels or another unit. Click the name of the unit to select another unit from the list of available units.

4. (*Optional*) To set a different resolution, click *Advanced Options*, then change the value for *Resolution*.

The default resolution of GIMP is usually 72 pixels per inch. This corresponds to a common screen display and is sufficient for most Web page graphics. For print images, use a higher resolution, such as 300 pixels per inch.

In *Color space*, select whether the image should be in color (*RGB*) or *Grayscale*. For detailed information about image types, see [Section 18.6.7, “Image Modes”](#).

In *Fill With* select the color the image is filled with. You can choose between *Foreground Color* and *Background Color* set in the toolbox, *White* or *Transparency* for a transparent image. Transparency is represented by a gray checkerboard pattern.

5. When the settings meet your needs, click *OK*.

18.4.2 Opening an Existing Image

To open an existing image, select *File > Open*.

In the dialog that opens, select the desired file and click *Open*.

18.5 Saving and Exporting Images

GIMP makes a distinction between saving and exporting images.

Saving an Image. The image is stored with all its properties in a lossless format. This includes, for example, layer and path information. This means that repeatedly opening and saving the image will neither degrade its quality nor how well it can be edited.

To save an image, use *File > Save* or *File > Save as*. To be able to store all properties, only the native format of GIMP is allowed in this mode: the XCF format.

Exporting an image. The image is stored in a format in which some properties can be lost. For example, most image formats do not support layers. When exporting, GIMP will often tell you which properties will be lost and ask you to decide how to proceed.

To export an image, use *File > Overwrite* or *File > Export As*. Below is a selection of the most common file formats that GIMP can export to:

JPEG

A common format for photographs and Web page graphics without transparency. Its compression method enables reduction of file sizes, but information is lost when compressing. It may be a good idea to use the preview option when adjusting the compression level. Levels of 85% to 75% often result in an acceptable image quality with reasonable compression. Repeatedly opening a JPEG and then saving can quickly result in poor image quality.

GIF

Although very popular in the past for graphics with transparency, GIF is less often used now. GIF is also used for animated images. The format can only save *indexed* images. See [Section 18.6.7, “Image Modes”](#) for information about indexed images. The file size can often be quite small if only a few colors are used.

PNG

With its support for transparency, lossless compression, and good browser support, PNG is the preferred format for Web graphics with transparency. An added advantage is that PNG offers partial transparency, which is not offered by GIF. This enables smoother transitions from colored areas to transparent areas (*antialiasing*). It also supports the full RGB color space which makes it usable for photos. However, it cannot be used for animations.

18.6 Editing Images

GIMP provides several tools for making changes to images. The functions described here are those most interesting for smaller edits.

18.6.1 Changing the Size of an Image

After an image is scanned or a digital photograph is loaded from the camera, it is often necessary to modify the size for display on a Web page or for printing. Images can easily be made smaller either by scaling them down or by cutting off parts of them.

Enlarging an image is much more problematic. Because of the nature of raster graphics, quality is lost when an image is enlarged. It is recommended to keep a copy of your original image before scaling or cropping.

18.6.1.1 Cropping an Image

1. Select the crop tool from the toolbox (the paper knife icon) or click *Tools > Transform Tools > Crop*.
2. Click a starting corner and drag to outline the area to keep. A rectangle showing the crop area will appear.
3. To adjust the size of the rectangle, move your mouse pointer above any of the rectangle's sides or corners, then click and drag to resize as desired. If you want to adjust both width and height of the rectangle, use a corner. To adjust only one dimension, use a side. To move the whole rectangle to a different position without resizing, click anywhere near its center and drag to the desired position.
4. When you are satisfied with the crop area, click anywhere inside to crop the image or press . To cancel the cropping, click anywhere outside the crop area.

18.6.1.2 Scaling an Image

1. Select *Image > Scale Image* to change the overall size of an image.
2. Select the new size by entering it in *Width* or *Height*.

To change the proportions of the image when scaling (this distorts the image), click the chain icon to the right of the fields to break the link between them. When those fields are linked, all values are changed proportionately. Adjust the resolution with *X resolution* and *Y resolution*.

The *Interpolation* option controls the quality of the resulting image. The default *Cubic* interpolation method usually is a good standard to use.
3. When you are finished, click *Scale*.

18.6.1.3 Changing the Canvas Size

The canvas is the entire visible area of an image. Canvas and image are independent from each other. If the canvas is smaller than the image, you can only see part of the image. If the canvas is larger, you see the original image with extra space around it.

1. Select *Image > Canvas Size*.

2. In the dialog that opens, enter the new size. To make sure the dimensions of the image stay the same, click the chain icon.
3. After adjusting the size, determine how the existing image should be positioned in comparison to the new size. Use the *Offset* values or drag the box inside the frame at the bottom.
4. When you are finished, click *Resize*.

18.6.2 Selecting Parts of Images

It is often useful to perform an image operation on only part of an image. To do this, the part of the image with which you want to work must be selected. Areas can be selected using the selection tools available in the toolbox, using the quick mask, or combining different options. Selections can also be modified with the items under *Select*. The selection is outlined with a dashed line, called *marching ants*.

18.6.2.1 Using the Selection Tools

The main selection tools are easy to use. The more complicated paths tool is not described here. To determine whether a new selection should replace, be added to, be subtracted from, or intersect with an existing selection, use the *Mode* row in the tool options.

Rectangle Select

This tool can be used to select rectangular or square areas. To select an area with a fixed aspect ratio, width, height or size, activate the *Fixed* option and choose the relevant mode in the *Tool Options* dialog. To create a square, hold **Shift** while selecting a region.

Ellipse Select

Use this to select elliptical or circular areas. The same options are available as with the rectangular selection. To create a circle, hold **Shift** while selecting a region.

Free Select (Lasso)

With this tool, you can create a selection based on a combination of freehand drawing and polygonal segments. To draw a freehand line, drag the mouse over the image with the left mouse button pressed. To create a polygonal segment, release the mouse button where the segment should start and press it again where the segment should end. To complete the selection, hover the pointer above the starting point and click inside the circle.

Fuzzy Select (Magic Wand)

This tool selects a continuous region based on color similarities. Set the maximum difference between colors in the tool options dialog in *Threshold*. By default, the selection is based only on the active layer. To base the selection on all visible layers, check *Sample merged*.

Select by Color

With this tool, select all the pixels in the image with the same or a similar color as the clicked pixel. The maximum difference between colors can be set in the tool options dialog in *Threshold*. The important difference between this tool and Fuzzy Select is that *Fuzzy Select* works on continuous color areas while *Select by Color* selects all pixels with similar colors in the whole image regardless of their position.

Scissors

Click a series of points in the image. As you click, the points are connected based on color differences. Click the first point to close the area. Convert it to a regular selection by clicking inside it.

Foreground Selection

The *Foreground Selection* tool lets you semi-automatically select an object in a photograph with minimal manual effort.

To use the *Foreground Selection* tool, follow these steps:

1. Activate the *Foreground Selection* tool by clicking its icon in the *Toolbox* or choosing *Tools > Selection Tools > Foreground Select* from the menu.
2. Roughly select the foreground object you want to extract. Select as little as possible from the background but include the whole object. At this point, the tool works like the *Fuzzy Select* tool.
When you release the mouse button, the deselected part of the image is covered with a dark blue mask.
3. Draw a continuous line through the foreground object going over colors which will be kept for the extraction. Do not paint over background pixels.
When you release the mouse button, the entire background is covered with a dark blue mask. If parts of the object are also masked, paint over them. The mask will adapt.
4. When you are satisfied with the mask, press . The mask will be converted to a new selection.

18.6.2.2 Using the Quick Mask

The quick mask is a way of selecting parts of an image using the paint tools. A good way to use it is to first create a rough selection using the *Scissors* or *Free Select* tool. Then start using the *Quick Mask*:

1. To activate the *Quick Mask*, in the lower left corner of the image window, click the icon with the dashed box. The *Quick Mask* icon now changes to a red box. The *Quick Mask* highlights the deselected parts of the image with a red overlay. Areas appearing in their normal color are selected.



Note: Changing the Color of the Mask

To use a different color for displaying the quick mask, right-click the quick mask button then select *Configure Color and Opacity* from the menu. Click the colored box in the dialog that opens to select a new color.

2. To modify the selection, use the paint tools. Painting with white selects the painted pixels. Painting with black deselects pixels. Shades of gray (colors are treated as shades of gray) create a partial selection. Partial selections allow a smooth transition between selected and deselected areas.
3. When you are finished, return to the normal selection view by clicking the icon in the lower left corner of the image window. The selection is then displayed with the marching ants.

18.6.3 Applying and Removing Color

Most image editing involves applying or removing color. By selecting a part of the image, you can limit where color can be applied or removed. When you select a tool and move the mouse pointer onto an image, the appearance of the mouse pointer changes to reflect the chosen tool. With many tools, an icon of the current tool is shown along with the arrow. For paint tools, an outline of the current brush is shown, allowing you to see exactly where you will be painting in the image and how large of an area will be painted.

18.6.3.1 Selecting Colors

The GIMP toolbox always shows two color swatches. The foreground color is used by the paint tools. The background color is used much more rarely, but it can easily be switched to become the foreground color.

1. To change the color displayed in a swatch, click the swatch. A dialog with five tabs opens.
2. These tabs provide different color selection methods. Only the first tab, shown in *Figure 18.2, "The Basic Color Selector Dialog"*, is described here. The new color is shown in *Current*. The previous color is shown in *Old*.




FIGURE 18.2: THE BASIC COLOR SELECTOR DIALOG

The easiest way to select a color is by using the colored areas in the boxes to the left. In the narrow vertical bar, click a color similar to the desired color. The larger box to the left then shows available nuances. Click the desired color. It is then shown in *Current*.

The arrow button to the right of *Current* allows saving colors. Click the arrow to copy the current color to the history. A color can then be selected by clicking it in the history.

A color can also be selected by directly entering its hexadecimal color code in *HTML Notation*.

The color selector defaults to selecting a color by hue. To select by saturation, value, red, green, or blue, select the corresponding radio button to the right. The sliders and number fields can also be used to modify the currently selected color. Experiment a bit to find out what works best for you.

3. When you are finished, click *OK*.

To select a color that already exists in your image, use the eye dropper tool. With the tool options, set whether the foreground or background color should be selected.

18.6.3.2 Painting and Erasing

To paint and erase, use the tools from the toolbox. There are a number of options available to fine-tune each tool. Pressure sensitivity options apply only when a pressure-sensitive graphics tablet is used.

The pencil, brush, airbrush, and eraser work much like their real-life equivalents. The ink tool works like a calligraphy pen. Paint by clicking and dragging. The bucket fill is a method of coloring areas of an image. It fills based on color boundaries in the image. Adjusting the threshold modifies its sensitivity to color changes.

18.6.3.3 Adding Text

To add text, use the text tool. Use the tool options to select the desired font and text properties. Click into the image, then start writing.

The text tool creates text in a special layer. To work with the image after adding text, read [Section 18.6.6, “Layers”](#). When the text layer is active, it is possible to modify the text by clicking in the image to reopen the entry dialog.

18.6.3.4 Retouching Images—The Clone Tool

The clone tool is ideal for retouching images. It enables you to paint in an image using information from another part of the image. If desired, it can instead take information from a pattern. When retouching, use a small brush with soft edges. In this way, the modifications can blend better with the original image.

To select the source point in the image, press and hold **Ctrl** while clicking the desired source point. Then paint with the tool. When you move the cursor while painting, the source point, marked by a cross, moves as well.

If the *Alignment* is set to *None* (the default setting), the source resets to the original when you release the left mouse button.

18.6.4 Adjusting Color Levels

Images often need a little adjusting to get ideal print or display results.

1. Select *Colors > Levels*. A dialog opens for controlling the levels in the image.
2. Good results can usually be obtained by clicking *Auto*. To make manual adjustments to all channels, use the dropper tools in *All Channels* to pick areas in the image that should be black, neutral gray, and white.
To modify an individual channel, select the desired channel in *Channel*. Then drag the black, white, and middle markers in the slider in *Input Levels*. You can also use the dropper tools to select points in the image that should serve as the white, black, and gray points for that channel.
If *Preview* is checked, the image window shows a preview of the image with the modifications applied.
3. When you are finished, click *OK*.

18.6.5 Undoing Mistakes

Most modifications made in GIMP can be undone. To view a history of modifications, use the undo dialog included in the default window layout or open one from the image window menu with *Windows > Dockable Dialogs > Undo History*.

The dialog shows a base image and a series of editing changes that can be undone. Use the buttons to undo and redo changes. In this way, you can often work back to the base image.

You can also undo and redo changes using *Undo* and *Redo* from the *Edit* menu. Alternatively, use the shortcuts **Ctrl-Z** and **Ctrl-Y**.

18.6.6 Layers

Layers are a very important aspect of GIMP. By drawing parts of your image on separate layers, you can change, move, or delete those parts without damaging the rest of the image.

To understand how layers work, imagine an image created from a stack of transparent sheets. Different parts of the image are drawn on different sheets. The stack can be arranged and sorted. Individual layers or groups of layers can shift position, moving sections of the image to other locations. New sheets can be added and others can be removed or made invisible.

Use the *Layers* dialog to view the available layers of an image. The text tool automatically creates special text layers when used. The active layer is selected. The buttons at the bottom of the dialog offer several functions. More are available in the menu opened when a layer is right-clicked in the dialog. The two icon spaces before the image name are used for toggling image visibility (eye icon when visible) and for linking layers. Linked layers are marked with the chain icon and moved as a group.

18.6.7 Image Modes

GIMP has three image modes:

- RGB is a normal color mode and is the best mode for editing most images.
- Grayscale is used for black-and-white images.
- Indexed mode limits the colors in the image to a set number. The maximum number of colors in this mode is 255. It is mainly used for GIF images.

If you need an indexed image, it is normally best to edit the image in RGB, then convert to indexed right before exporting. If you export to a format that requires an indexed image, GIMP offers to index the image when exporting.

18.6.8 Special Effects

GIMP includes a wide range of filters and scripts for enhancing images, adding special effects to them or making artistic manipulations. They are available in *Filters*. Experimenting is the best way to find out what is available.

18.7 Printing Images

To print an image, select *File > Print* from the image menu. If your printer is configured in the system, it should appear in the list. You can configure printing options on *Page Setup* and *Image Settings* tabs.




FIGURE 18.3: THE PRINT DIALOG

When you are satisfied with the settings, click *Print*. *Cancel* aborts printing.

18.8 For More Information

The following resources are very useful for users of GIMP. They contain much more information about GIMP than this chapter. If you want to use GIMP for more advanced tasks, you should not miss these resources.

- <http://www.gimp.org> is the official home page of The GIMP. News about GIMP and related software are regularly posted on the front page.
- *Help* provides access to the internal help system including the extensive GIMP User Manual. The package `gimp-help` needs to be installed. This documentation is also available online in HTML and PDF formats at <http://docs.gimp.org>. Translations into many languages are available.
- A collection of many interesting GIMP tutorials is maintained at <http://www.gimp.org/tutorials/>. It contains basic tutorials for beginners and tutorials for advanced or expert users.
- Printed books about GIMP are published regularly. You will find a selection of the best ones with short annotations at <http://www.gimp.org/books/>.
- GIMP functionality can be extended with scripts and plug-ins. Many such scripts and plug-ins are distributed in the GIMP package, but others can be downloaded from the Internet.

You can also use mailing lists or IRC channels to ask questions about GIMP. Always try to find answers in the documentation mentioned above or in mailing list archives before asking your question. The time of experienced users present on GIMP lists and channels is limited. Be polite and patient. It may take some time before your question is answered.

- There are several mailing lists about GIMP. You will find them at http://www.gimp.org/mail_lists.html. The GIMP User list is the most appropriate place to ask user questions.
- There is a whole IRC network dedicated to GIMP and GNOME desktop environment—GIMPNet. You can connect to GIMPNet with your favorite IRC client by pointing it at the irc.gimp.org server. The `#gimp-users` channel is the right place to ask question about using GIMP. If you want to listen to developer's discussions, join the `#gimp` channel.

19 GNOME Videos

GNOME Videos is the default movie player. GNOME Videos provides the following multimedia features:

- Support for a variety of video and audio files
- A variety of zoom levels and aspect ratios, and a full screen view
- Seek and volume controls
- Playlists
- Complete keyboard navigation

To start GNOME Videos, click *Applications > Sound & Video > Videos*.

19.1 Using GNOME Videos

When you start GNOME Videos, the following window is displayed.




FIGURE 19.1: GNOME VIDEOS START-UP WINDOW

19.1.1 Opening a Video or Audio File

1. Click *Videos > Open*.
2. Select the files you want to open, then click *Add*

You can also drag a file from another application (such as a file manager) to the GNOME Videos window. GNOME Videos opens the file and plays the movie or song. GNOME Videos displays the title of the movie or song beneath the display area and in the titlebar of the window.



Note: Unrecognized File Format

If you try to open a file format that GNOME Videos does not recognize, the application displays an error message and recommends a suitable codec.

You can double-click a video or audio file in GNOME Files to open it in the GNOME Videos window by default.


19.1.2 Opening a Video or Audio File By URI Location


1. Click *Videos > Open Location*.
2. Specify the URI location of the file you want to open, then click *Open*.


19.1.3 Playing a DVD, VCD, or CD

To play a DVD, VCD, or CD, insert the disc in the optical device of your computer, then click *Movie > Play Disc*.

To eject a DVD, VCD, or CD, click *Movie > Eject*.

To pause a movie or song that is playing, click the  button, or click *Movie > Play/Pause*. When you pause a movie or song, the statusbar displays *Paused* and the time elapsed on the current movie or song.

To resume playing a movie or song, click the  button, or click *Movie > Play/Pause*.


To play or pause a movie, you can also press .

To view properties of a movie or song, click *View > Sidebar* to make the sidebar appear. The dialog contains the title, artist, year, and duration of movie or song, video dimensions, codec, frame rate, and the audio bit rate.

19.1.4 Seeking Through Movies or Songs

To seek through movies or songs, use any of the following methods:

To skip forward

Click *Go > Skip Forward*. Alternatively, use .


To skip backward

Click *Go > Skip Backward*. Alternatively, use .

To move to next movie or song

Click *Go > Next Chapter/Movie*, or click the  button.

To move to previous movie or song

Click *Go > Previous Chapter/Movie*, or click the  button.

19.1.5 Changing the Zoom Factor

To change the zoom factor of the display area, use any of the following methods:

To zoom to full screen mode

Click *View > Fullscreen*. Alternatively, press .

To exit fullscreen mode, click *Leave Fullscreen* or press .

To zoom to half size (50%) of the original movie or visualization

Click *View > Fit Window to Movie > Resize 1:2*.

To zoom to size (100%) of the original movie or visualization

Click *View > Fit Window to Movie > Resize 1:1*.

To zoom to double size (200%) of the original movie or visualization

Click *View > Fit Window to Movie > Resize 2:1*.

To switch between different aspect ratios, click *View > Aspect Ratio*.

The default aspect ratio is *Auto*.

19.1.6 Showing or Hiding Controls

To hide the window controls of GNOME Videos, click *View > Show Controls* and deselect the option. To show the controls on the GNOME Videos window, right-click the window, then select *Show Controls*. If the Show Controls option is selected, GNOME Videos shows the menubar, time elapsed slider, seek control buttons, volume slider, and statusbar on the window. If the Show Controls option is not selected, the application hides these controls and shows only the display area.

19.1.7 Managing Playlists

To show the playlist, click *View > Sidebar*. The Playlist sidebar is displayed.

You can use the Playlist dialog to do the following:

- **To add a track or movie:** Click the *Add* button. Select the file you want to add to the playlist, then click *OK*.
- **To remove a track or movie:** Select the file names from the file name list box, then click *Remove*.
- **To save a playlist to file:** Click the *Save Playlist* button, then specify a file name.
- **To move a track or movie up the playlist:** Select the file name from the file name list box, then click the *Move Up* button.
- **To move a track or movie down the playlist:** Select the file name from the file name list box, then click the *Move Down* button.

To hide the playlist, click *View > Sidebar*, or click the *Sidebar* button.

To enable or disable repeat mode, click *Edit > Repeat Mode*. To enable or disable shuffle mode, click *Edit > Shuffle Mode*.

19.1.8 Choosing Subtitles

To choose the language of the subtitles, click *View > Subtitles > Select Text Subtitles*, then select the subtitles language (DVD) or subtitle file (AVI etc.) you want to display.

To disable the display of subtitles, click *View > Subtitles > None*.

By default, GNOME Videos chooses the same language for the subtitles that you use on your computer.

GNOME Videos automatically loads and displays subtitles if the file that contains them has the same name as the video file. It supports the following subtitle file extensions: srt, asc, txt, sub, smi, or ssa.

19.2 Modifying GNOME Videos Preferences

To modify GNOME Videos preferences, click *Videos > Preferences*.

19.2.1 General Preferences

The General Preferences let you select a network connection speed, specify if media files should be played from the last used position, and change the font and encoding used to display subtitles.




FIGURE 19.2: GNOME VIDEOS GENERAL PREFERENCES

General Preferences include the following:

Playback

Lets you specify whether to start playing the movie from the last position.

Networking

Select network connection speed from the Connection speed drop-down box.

Text Subtitles

Lets you specify whether to load the subtitles automatically, and change the font and encoding used to display the subtitles.

19.2.2 Display Preferences

The Display Preferences let you choose to automatically resize the window when a new video is loaded, change the color balance, and configure visual effects when an audio file is played.




FIGURE 19.3: GNOME VIDEOS DISPLAY PREFERENCES

Display Preferences include the following:

Automatically resize the window when a new video is loaded

Select this option if you want GNOME Videos to automatically resize the window when a new video is loaded.

Disable the screen saver when playing video or audio

Select this option if you want GNOME Videos to automatically disable the desktop screen saver while an audio file is playing.

Visual Effects

You can choose to show visual effects when an audio file is playing, select the type of visualization you want to show, and the visualization size.

Color Balance

Specify the level of color brightness, contrast, saturation, and hue.

19.2.3 Audio Preferences

The Audio Preferences dialog lets you select the audio output type.




FIGURE 19.4: GNOME VIDEOS AUDIO PREFERENCES

20 Brasero: Burning CDs and DVDs

Brasero is a GNOME program for writing data and audio CDs and DVDs. Start the program from the main menu by clicking *Applications > Sound & Video > Brasero*.

The following sections are a quick introduction on how to create your own CD or DVD.

20.1 Creating a Data CD or DVD

After starting Brasero for the first time, the main window appears as shown in *Figure 20.1*.



FIGURE 20.1: MAIN VIEW OF BRASERO

To create a data CD or DVD, proceed as follows:

1. Click *Data project* or select *Project > New Project > New Data Project*. The project view appears.
2. Drag and drop the desired directories or individual files either from your file manager or by clicking the plus icon. To show your directory structure directly in Brasero, select *View > Show Side Panel* or press **F7**.
3. Optionally, save the project under a name of your choice with *Project > Save As*.

4. Name your medium. The original label is *Data disc (date)*.
5. Choose the output medium from the pull down menu next to the *Burn* button (CD/DVD or an ISO image file).
6. Click *Burn*. A new dialog appears, depending on what medium you have selected in the previous step:
 - **CD/DVD.** You can define some parameters, like the burning speed or where to store temporary files. Under *Options* you can also choose whether to burn the image directly, close the session, verify the written data, and others.
 - **ISO Image.** Specify a file name for your ISO image file.
7. Start the process with *Burn*.

20.2 Creating an Audio CD

There are no significant differences between creating an audio CD and creating a data CD. Proceed as follows:

1. Select *Project > New Project > New Audio Project*.
2. Drag and drop the individual audio tracks to the project directory. The audio data must be in WAV or Ogg Vorbis format. Determine the sequence of the tracks by moving them up or down in the project directory.
3. Click *Burn*. A dialog opens.
4. Specify a drive to write to.
5. Click *Properties* to adjust burning speed and other preferences. When burning audio CDs, choose a lower burning speed to reduce the risk of burn errors.
6. Click *Burn*.

20.3 Copying a CD or DVD

To copy a CD or DVD, proceed as follows:

1. Click *Disc Copy* or go to *Project > New Project > Copy Disc*. The *Copy CD/DVD* dialog opens.

2. Specify the source drive you want to copy.
3. Specify a drive or image file to write to.
4. If necessary, change the burning speed, the temporary directory and other options in *Properties*.
5. Click *Copy*.

20.4 Writing ISO Images

If you already have an ISO image, click *Burn image* or go to *Project > New Project > Burn Image*. Choose the image to write and a disc to write to. If necessary, change parameters by clicking *Properties*. Choose the location of the image file with the pop-up menu labeled *Path*. Start the burning process and click *Burn*.

20.5 Creating a Multisession CD or DVD

Multisession discs can be used to write data in more than one burning session. This is useful, for example, for writing backups that are smaller than the media. In each session, you can add another backup file. One note of interest is that you are not only limited to data CDs or DVDs. You can also add audio sessions in a multisession disc.

To start a new multisession disc, do the following:

1. Start with a data disc first as described in *Section 20.1, "Creating a Data CD or DVD"*. You cannot start with an audio CD session. Make sure that you do not fill up the entire disc, because otherwise you cannot append a new session.
2. Click *Burn*. The window *Disc Burning Setup* opens.
3. Select *Leave the disc open to add other files later* to make the disc multisession capable. Configure other options if needed.
4. Start the burning session with *Burn*.

20.6 For More Information

You can find more information about Brasero at <https://wiki.gnome.org/Apps/Brasero> .

A Help and Documentation

SUSE® Linux Enterprise Server comes with various sources of information and documentation, many of which are already integrated in your installed system:

Desktop Help Center

The help center of the GNOME desktop (Help) provides central access to the most important documentation resources on your system, in searchable form. These resources include online help for installed applications, man pages, info pages, and the SUSE manuals delivered with your product. Learn more in [Section A.1, “Using GNOME Help”](#).

Separate Help Packages for Some Applications

When installing new software with YaST, the software documentation is installed automatically, and usually appears in the help center of your desktop. However, some applications, such as GIMP, may have different online help packages that can be installed separately with YaST and do not integrate into the help centers.

Documentation in /usr/share/doc

This traditional help directory holds various documentation files and the release notes for your system. Find more detailed information in *Book “Administration Guide”, Chapter 39 “Help and Documentation”, Section 39.1 “Documentation Directory”*.

Man Pages and Info Pages for Shell Commands

When working with the shell, you do not need to know the options of the commands by heart. Traditionally, the shell provides integrated help by means of man pages and info pages. Read more in *Book “Administration Guide”, Chapter 39 “Help and Documentation”, Section 39.2 “Man Pages”* and *Book “Administration Guide”, Chapter 39 “Help and Documentation”, Section 39.3 “Info Pages”*.

A.1 Using GNOME Help

On the GNOME desktop, to start Help directly from an application, either click the *Help* button or press **F1**. Both options take you directly to the application's documentation in the help center. However, you can also start Help by opening a terminal and entering **yelp** or from the main menu by clicking *Applications > Favorites > Help*.





FIGURE A.1: MAIN WINDOW OF HELP

To see an overview of available application manuals, click the menu icon and select *All Help*.

The menu and the toolbar provide options for navigating the help center, for searching and for printing contents from Help. The help topics are grouped into categories presented as links. Click one of the links to open a list of topics for that category. To search for an item, click the search icon and enter the search string into the search field at the top of the window.

A.2 Additional Help Resources

In addition to the SUSE manuals installed under `/usr/share/doc`, you can also access the product-specific manuals and documentation on the Web. For an overview of all documentation available for SUSE Linux Enterprise Server check out your product-specific documentation Web page at <https://documentation.suse.com/> .

If you are searching for additional product-related information, you can also refer to the following Web sites:


- SUSE Knowledgebase (<http://www.suse.com/support/kb/>) 
- SUSE Linux Enterprise Server Forums (<https://forums.suse.com/forumdisplay.php?8-SUSE-Linux-Enterprise-Server>) 
- SUSE Blog (<https://www.suse.com/communities/blog/>) 
- GNOME Web Site (<http://www.gnome.org/>) 
- KDE Web Site (<http://www.kde.org/>) 

You can also try general-purpose search engines. For example, use the search terms Linux CD-RW help or LibreOffice file conversion problem if you were having trouble with the CD burning or with LibreOffice file conversion.

A.3 For More Information

Apart from the product-specific help resources, there is a broad range of information available for Linux topics.

A.3.1 The Linux Documentation Project

The Linux Documentation Project (TLDP) is run by a team of volunteers who write Linux-related documentation (see <http://www.tldp.org> ). The set of documents contains tutorials for beginners, but is mainly focused on experienced users and professional system administrators. TLDP publishes Howtos, FAQs, and guides (handbooks) under a free license. Parts of the documentation from TLDP is also available on SUSE Linux Enterprise Server.

A.3.1.1 Frequently Asked Questions

FAQs (frequently asked questions) are a series of questions and answers. They originate from Usenet newsgroups where the purpose was to reduce continuous reposting of the same basic questions.

A.3.1.2 Guides

Manuals and guides for various topics or programs can be found at <http://www.tldp.org/guides.html>. They range from *Bash Guide for Beginners* to *Linux File System Hierarchy* to *Linux Administrator's Security Guide*. Generally, guides are more detailed and exhaustive than Howtos or FAQs. They are usually written by experts for experts.

A.3.2 Wikipedia: The Free Online Encyclopedia

Wikipedia is “a multilingual encyclopedia designed to be read and edited by anyone” (see <http://en.wikipedia.org>). The content of Wikipedia is created by its users and is published under a dual free license (GFDL and CC-BY-SA). However, as Wikipedia can be edited by any visitor, it should be used only as a starting point or general guide. There is much incorrect or incomplete information in it.

A.3.3 Standards and Specifications

There are various sources that provide information about standards or specifications.

<http://www.linux-foundation.org/en/LSB>

The Linux Foundation is an independent nonprofit organization that promotes the distribution of free and open source software. The organization endeavors to achieve this by defining distribution-independent standards. The maintenance of several standards, such as the important LSB (Linux Standard Base), is supervised by this organization.

<http://www.w3.org>


The World Wide Web Consortium (W3C) is one of the best-known standards organizations. It was founded in October 1994 by Tim Berners-Lee and concentrates on standardizing Web technologies. W3C promotes the dissemination of open, license-free, and manufac-

turer-independent specifications, such as HTML, XHTML, and XML. These Web standards are developed in a four-stage process in *working groups* and are presented to the public as *W3C recommendations* (REC).

<http://www.oasis-open.org> 

OASIS (Organization for the Advancement of Structured Information Standards) is an international consortium specializing in the development of standards for Web security, e-business, business transactions, logistics, and interoperability between various markets.

<http://www.ietf.org> 

The Internet Engineering Task Force (IETF) is an internationally active cooperative of researchers, network designers, suppliers, and users. It concentrates on the development of Internet architecture and the smooth operation of the Internet by means of protocols. Every IETF standard is published as an RFC (Request for Comments) and is available free-of-charge. There are six types of RFC: proposed standards, draft standards, Internet standards, experimental protocols, information documents, and historic standards. Only the first three (proposed, draft, and full) are IETF standards in the narrower sense (see <http://www.ietf.org/rfc/rfc1796.txt> )

<http://www.ieee.org> 

The Institute of Electrical and Electronics Engineers (IEEE) is an organization that draws up standards in the areas of information technology, telecommunication, medicine and health care, transport, and others. IEEE standards are subject to a fee.

<http://www.iso.org> 

The ISO Committee (International Organization for Standards) is the world's largest developer of standards and maintains a network of national standardization institutes in over 140 countries. ISO standards are subject to a fee.

<http://www.din.de>  ,

<http://www.din.com> 

The Deutsches Institut für Normung (DIN) is a registered technical and scientific association. It was founded in 1917. According to DIN, the organization is “the institution responsible for standards in Germany and represents German interests in worldwide and European standards organizations.”

The association brings together manufacturers, consumers, trade professionals, service companies, scientists and others who have an interest in the establishment of standards. The standards are subject to a fee and can be ordered using the DIN home page.

B GNU Licenses

This appendix contains the GNU Free Documentation License version 1.2.

GNU Free Documentation License

Copyright (C) 2000, 2001, 2002 Free Software Foundation, Inc. 51 Franklin St, Fifth Floor, Boston, MA 02110-1301 USA. Everyone is permitted to copy and distribute verbatim copies of this license document, but changing it is not allowed.

0. PREAMBLE

The purpose of this License is to make a manual, textbook, or other functional and useful document "free" in the sense of freedom: to assure everyone the effective freedom to copy and redistribute it, with or without modifying it, either commercially or non-commercially. Secondly, this License preserves for the author and publisher a way to get credit for their work, while not being considered responsible for modifications made by others.

This License is a kind of "copyleft", which means that derivative works of the document must themselves be free in the same sense. It complements the GNU General Public License, which is a copyleft license designed for free software.

We have designed this License to use it for manuals for free software, because free software needs free documentation: a free program should come with manuals providing the same freedoms that the software does. But this License is not limited to software manuals; it can be used for any textual work, regardless of subject matter or whether it is published as a printed book. We recommend this License principally for works whose purpose is instruction or reference.

1. APPLICABILITY AND DEFINITIONS

This License applies to any manual or other work, in any medium, that contains a notice placed by the copyright holder saying it can be distributed under the terms of this License. Such a notice grants a world-wide, royalty-free license, unlimited in duration, to use that work under the conditions stated herein. The "Document", below, refers to any such manual or work. Any member of the public is a licensee, and is addressed as "you". You accept the license if you copy, modify or distribute the work in a way requiring permission under copyright law.

A "Modified Version" of the Document means any work containing the Document or a portion of it, either copied verbatim, or with modifications and/or translated into another language.

A "Secondary Section" is a named appendix or a front-matter section of the Document that deals exclusively with the relationship of the publishers or authors of the Document to the Document's overall subject (or to related matters) and contains nothing that could fall directly within that overall subject. (Thus, if the Document is in part a textbook of mathematics, a Secondary Section may not explain any mathematics.) The relationship could be a matter of historical connection with the subject or with related matters, or of legal, commercial, philosophical, ethical or political position regarding them.

The "Invariant Sections" are certain Secondary Sections whose titles are designated, as being those of Invariant Sections, in the notice that says that the Document is released under this License. If a section does not fit the above definition of Secondary then it is not allowed to be designated as Invariant. The Document may contain zero Invariant Sections. If the Document does not identify any Invariant Sections then there are none.

The "Cover Texts" are certain short passages of text that are listed, as Front-Cover Texts or Back-Cover Texts, in the notice that says that the Document is released under this License. A Front-Cover Text may be at most 5 words, and a Back-Cover Text may be at most 25 words.

A "Transparent" copy of the Document means a machine-readable copy, represented in a format whose specification is available to the general public, that is suitable for revising the document straightforwardly with generic text editors or (for images composed of pixels) generic paint programs or (for drawings) some widely available drawing editor, and that is suitable for input to text formatters or for automatic translation to a variety of formats suitable for input to text formatters. A copy made in an otherwise Transparent file format whose markup, or absence of markup, has been arranged to thwart or discourage subsequent modification by readers is not Transparent. An image format is not Transparent if used for any substantial amount of text. A copy that is not "Transparent" is called "Opaque".

Examples of suitable formats for Transparent copies include plain ASCII without markup, Texinfo input format, LaTeX input format, SGML or XML using a publicly available DTD, and standard-conforming simple HTML, PostScript or PDF designed for human modification. Examples of transparent image formats include PNG, XCF and JPG. Opaque formats include proprietary

formats that can be read and edited only by proprietary word processors, SGML or XML for which the DTD and/or processing tools are not generally available, and the machine-generated HTML, PostScript or PDF produced by some word processors for output purposes only.

The "Title Page" means, for a printed book, the title page itself, plus such following pages as are needed to hold, legibly, the material this License requires to appear in the title page. For works in formats which do not have any title page as such, "Title Page" means the text near the most prominent appearance of the work's title, preceding the beginning of the body of the text.

A section "Entitled XYZ" means a named subunit of the Document whose title either is precisely XYZ or contains XYZ in parentheses following text that translates XYZ in another language. (Here XYZ stands for a specific section name mentioned below, such as "Acknowledgements", "Dedications", "Endorsements", or "History".) To "Preserve the Title" of such a section when you modify the Document means that it remains a section "Entitled XYZ" according to this definition.

The Document may include Warranty Disclaimers next to the notice which states that this License applies to the Document. These Warranty Disclaimers are considered to be included by reference in this License, but only as regards disclaiming warranties: any other implication that these Warranty Disclaimers may have is void and has no effect on the meaning of this License.

2. VERBATIM COPYING

You may copy and distribute the Document in any medium, either commercially or non-commercially, provided that this License, the copyright notices, and the license notice saying this License applies to the Document are reproduced in all copies, and that you add no other conditions whatsoever to those of this License. You may not use technical measures to obstruct or control the reading or further copying of the copies you make or distribute. However, you may accept compensation in exchange for copies. If you distribute a large enough number of copies you must also follow the conditions in section 3.

You may also lend copies, under the same conditions stated above, and you may publicly display copies.

3. COPYING IN QUANTITY

If you publish printed copies (or copies in media that commonly have printed covers) of the Document, numbering more than 100, and the Document's license notice requires Cover Texts, you must enclose the copies in covers that carry, clearly and legibly, all these Cover Texts: Front-Cover Texts on the front cover, and Back-Cover Texts on the back cover. Both covers must also clearly and legibly identify you as the publisher of these copies. The front cover must present the full title with all words of the title equally prominent and visible. You may add other material on the covers in addition. Copying with changes limited to the covers, as long as they preserve the title of the Document and satisfy these conditions, can be treated as verbatim copying in other respects.

If the required texts for either cover are too voluminous to fit legibly, you should put the first ones listed (as many as fit reasonably) on the actual cover, and continue the rest onto adjacent pages.

If you publish or distribute Opaque copies of the Document numbering more than 100, you must either include a machine-readable Transparent copy along with each Opaque copy, or state in or with each Opaque copy a computer-network location from which the general network-using public has access to download using public-standard network protocols a complete Transparent copy of the Document, free of added material. If you use the latter option, you must take reasonably prudent steps, when you begin distribution of Opaque copies in quantity, to ensure that this Transparent copy will remain thus accessible at the stated location until at least one year after the last time you distribute an Opaque copy (directly or through your agents or retailers) of that edition to the public.

It is requested, but not required, that you contact the authors of the Document well before redistributing any large number of copies, to give them a chance to provide you with an updated version of the Document.

4. MODIFICATIONS

You may copy and distribute a Modified Version of the Document under the conditions of sections 2 and 3 above, provided that you release the Modified Version under precisely this License, with the Modified Version filling the role of the Document, thus licensing distribution and modification of the Modified Version to whoever possesses a copy of it. In addition, you must do these things in the Modified Version:

- A. Use in the Title Page (and on the covers, if any) a title distinct from that of the Document, and from those of previous versions (which should, if there were any, be listed in the History section of the Document). You may use the same title as a previous version if the original publisher of that version gives permission.
- B. List on the Title Page, as authors, one or more persons or entities responsible for authorship of the modifications in the Modified Version, together with at least five of the principal authors of the Document (all of its principal authors, if it has fewer than five), unless they release you from this requirement.
- C. State on the Title page the name of the publisher of the Modified Version, as the publisher.
- D. Preserve all the copyright notices of the Document.
- E. Add an appropriate copyright notice for your modifications adjacent to the other copyright notices.
- F. Include, immediately after the copyright notices, a license notice giving the public permission to use the Modified Version under the terms of this License, in the form shown in the Addendum below.
- G. Preserve in that license notice the full lists of Invariant Sections and required Cover Texts given in the Document's license notice.
- H. Include an unaltered copy of this License.
- I. Preserve the section Entitled "History", Preserve its Title, and add to it an item stating at least the title, year, new authors, and publisher of the Modified Version as given on the Title Page. If there is no section Entitled "History" in the Document, create one stating the title, year, authors, and publisher of the Document as given on its Title Page, then add an item describing the Modified Version as stated in the previous sentence.
- J. Preserve the network location, if any, given in the Document for public access to a Transparent copy of the Document, and likewise the network locations given in the Document for previous versions it was based on. These may be placed in the "History" section. You may omit a network location for a work that was published at least four years before the Document itself, or if the original publisher of the version it refers to gives permission.
- K. For any section Entitled "Acknowledgements" or "Dedications", Preserve the Title of the section, and preserve in the section all the substance and tone of each of the contributor acknowledgements and/or dedications given therein.
- L. Preserve all the Invariant Sections of the Document, unaltered in their text and in their titles. Section numbers or the equivalent are not considered part of the section titles.
- M. Delete any section Entitled "Endorsements". Such a section may not be included in the Modified Version.
- N. Do not retitle any existing section to be Entitled "Endorsements" or to conflict in title with any Invariant Section.
- O. Preserve any Warranty Disclaimers.

If the Modified Version includes new front-matter sections or appendices that qualify as Secondary Sections and contain no material copied from the Document, you may at your option designate some or all of these sections as invariant. To do this, add their titles to the list of Invariant Sections in the Modified Version's license notice. These titles must be distinct from any other section titles.

You may add a section Entitled "Endorsements", provided it contains nothing but endorsements of your Modified Version by various parties—for example, statements of peer review or that the text has been approved by an organization as the authoritative definition of a standard.

You may add a passage of up to five words as a Front-Cover Text, and a passage of up to 25 words as a Back-Cover Text, to the end of the list of Cover Texts in the Modified Version. Only one passage of Front-Cover Text and one of Back-Cover Text may be added by (or through arrangements made by) any one entity. If the Document already includes a cover text for the same cover, previously added by you or by arrangement made by the same entity you are acting on behalf of, you may not add another; but you may replace the old one, on explicit permission from the previous publisher that added the old one.

The author(s) and publisher(s) of the Document do not by this License give permission to use their names for publicity for or to assert or imply endorsement of any Modified Version.

5. COMBINING DOCUMENTS

You may combine the Document with other documents released under this License, under the terms defined in section 4 above for modified versions, provided that you include in the combination all of the Invariant Sections of all of the original documents, unmodified, and list them all as Invariant Sections of your combined work in its license notice, and that you preserve all their Warranty Disclaimers.

The combined work need only contain one copy of this License, and multiple identical Invariant Sections may be replaced with a single copy. If there are multiple Invariant Sections with the same name but different contents, make the title of each such section unique by adding at the end of it, in parentheses, the name of the original author or publisher of that section if known, or else a unique number. Make the same adjustment to the section titles in the list of Invariant Sections in the license notice of the combined work.

In the combination, you must combine any sections Entitled "History" in the various original documents, forming one section Entitled "History"; likewise combine any sections Entitled "Acknowledgements", and any sections Entitled "Dedications". You must delete all sections Entitled "Endorsements".

6. COLLECTIONS OF DOCUMENTS

You may make a collection consisting of the Document and other documents released under this License, and replace the individual copies of this License in the various documents with a single copy that is included in the collection, provided that you follow the rules of this License for verbatim copying of each of the documents in all other respects.

You may extract a single document from such a collection, and distribute it individually under this License, provided you insert a copy of this License into the extracted document, and follow this License in all other respects regarding verbatim copying of that document.

7. AGGREGATION WITH INDEPENDENT WORKS

A compilation of the Document or its derivatives with other separate and independent documents or works, in or on a volume of a storage or distribution medium, is called an "aggregate" if the copyright resulting from the compilation is not used to limit the legal rights of the compilation's users beyond what the individual works permit. When the Document is included in an aggregate, this License does not apply to the other works in the aggregate which are not themselves derivative works of the Document.

If the Cover Text requirement of section 3 is applicable to these copies of the Document, then if the Document is less than one half of the entire aggregate, the Document's Cover Texts may be placed on covers that bracket the Document within the aggregate, or the electronic equivalent of covers if the Document is in electronic form. Otherwise they must appear on printed covers that bracket the whole aggregate.

8. TRANSLATION

Translation is considered a kind of modification, so you may distribute translations of the Document under the terms of section 4. Replacing Invariant Sections with translations requires special permission from their copyright holders, but you may include translations of some or all Invariant Sections in addition to the original versions of these Invariant Sections. You may include a translation of this License, and all the license notices in the Document, and any Warranty Disclaimers, provided that you also include the original English version of this License and the original versions of those notices and disclaimers. In case of a disagreement between the translation and the original version of this License or a notice or disclaimer, the original version will prevail.

If a section in the Document is Entitled "Acknowledgements", "Dedications", or "History", the requirement (section 4) to Preserve its Title (section 1) will typically require changing the actual title.

9. TERMINATION

You may not copy, modify, sublicense, or distribute the Document except as expressly provided for under this License. Any other attempt to copy, modify, sublicense or distribute the Document is void, and will automatically terminate your rights under this License. However, parties who have received copies, or rights, from you under this License will not have their licenses terminated so long as such parties remain in full compliance.

10. FUTURE REVISIONS OF THIS LICENSE

The Free Software Foundation may publish new, revised versions of the GNU Free Documentation License from time to time. Such new versions will be similar in spirit to the present version, but may differ in detail to address new problems or concerns. See <http://www.gnu.org/copyleft/>.

Each version of the License is given a distinguishing version number. If the Document specifies that a particular numbered version of this License "or any later version" applies to it, you have the option of following the terms and conditions either of that specified version or of any later version that has been published (not as a draft) by the Free Software Foundation. If the Document does not specify a version number of this License, you may choose any version ever published (not as a draft) by the Free Software Foundation.

ADDENDUM: How to use this License for your documents

```
Copyright (c) YEAR YOUR NAME.
Permission is granted to copy, distribute and/or modify this document
under the terms of the GNU Free Documentation License, Version 1.2
or any later version published by the Free Software Foundation;
with no Invariant Sections, no Front-Cover Texts, and no Back-Cover Texts.
A copy of the license is included in the section entitled "GNU
Free Documentation License".
```

If you have Invariant Sections, Front-Cover Texts and Back-Cover Texts, replace the "with...Texts," line with this:

```
with the Invariant Sections being LIST THEIR TITLES, with the
Front-Cover Texts being LIST, and with the Back-Cover Texts being LIST.
```

If you have Invariant Sections without Cover Texts, or some other combination of the three, merge those two alternatives to suit the situation.

If your document contains nontrivial examples of program code, we recommend releasing these examples in parallel under your choice of free software license, such as the GNU General Public License, to permit their use in free software.